

Filtered By: [UIRF Planning Area: Clintonville]

Project Number	Project Name	Project Type	UIRF Planning Area	UIRF Secondary Planning Area	UIRF ID	Project Description	Community Endorsement	Project Stage	Project Status	Project Phase	Estimated Implementation / NTP Date	Community Notes	Development Verification Date
(P) 440005-100004	UIRF - Clintonville	Planted Median	Clintonville	N/A	0000	This project consists of installing a 100' long planted median on N. High Street between W. Orchard Lane and E. Dunedin Road, a 140' long planted median on Indianola Avenue between Melrose Avenue and Milford Avenue, and brick crosswalks at the following intersections: N. High Street at W. Rathbone Avenue/Morse Road, N. High Street at Hollenback Road/Acton Road, Henderson Road at N. High Street, and E. Dominion Boulevard at N. High Street.	Confirmed	Completion	Closeout (Active)	Design	03/08/2018	Medians and brick crosswalks are installed. Project is complete.	3/25/2019 1:25PM Jackie Yeoman
(P) 440005-102199	UIRF - Glen Echo Bridge Balustrade	Other	Clintonville	University District	2199	Construction of an historic balustrade on the Indianola bridge over Glen Echo Ravine.	Confirmed	Completion	Closed		N/A	Project complete. \$75,000 from Clintonville, \$75,0000 from University District.	4/12/2019 5:04PM Christopher Lohr
(C) 440005-101944	UIRF Indianola Sidewalks	Sidewalk	Clintonville	N/A	1944	Construction of new sidewalks on the west side of Indianola from Garden Road to Jeffrey Place	Confirmed	Execution	Active		07/20/2020	Planned as part of 4th sidewalk package with construction in 2019	3/25/2019 11:42AM Jackie Yeoman
(P) 440005-101845	UIRF - Clintonville/Indianola Planted Median	Planted Median	Clintonville	N/A	1845	Indianola at one location to the south of Weber.	Confirmed	Conception	Active		N/A	Funding from High Street median project has been moved to Indianola as it was determined that there were no eligible locations south North Broadway. Two medians to be installed on Indianola. This project is On Hold	3/25/2019 1:38PM Jackie Yeoman
(P) 440005-100062	UIRF - Indianola Road Diet	Road Diet	Clintonville	N/A	1848	Construction of a road diet on Indianola Avenue from Morse Road to Oakland Park Avenue. The existing roadway consists of 4 lanes (2 in each direction), the proposed roadway will retain the existing width and be restriped as 3 lanes (1 in each direction with a two way left turn lane) with bike lanes.	Confirmed	Completion	Closed	Design	03/04/2017	Complete. This project consists of Indianola Road Diet and also includes Indianola Bike Lanes (originally UIRF ID 1956).	3/25/2019 11:38AM Jackie Yeoman
(P) 440005-101844	UIRF - Clintonville/High Street Planted Median	Planted Median	Clintonville	N/A	1844	High Street at one location to the south of North Broadway.	Confirmed	Conception	Rejected		N/A	Project rejected. Two medians planned for Indianola instead - project 440005-101845	3/25/2019 1:37PM Jackie Yeoman
(P) 440005-101842	UIRF - West North Broadway Road Diet	Road Diet	Clintonville	N/A	1842	Possible road diet features are curb extensions, bike lanes, re-striping, center medians, on-street parking.	Confirmed	Conception	Rejected		N/A	Abandoned Per Department of Public Service	3/25/2019 1:39PM Jackie Yeoman

Filtered By: [UIRF Planning Area: Clintonville]

Project Number	Project Name	Project Type	UIRF Planning Area	UIRF Secondary Planning Area	UIRF ID	Project Description	Community Endorsement	Project Stage	Project Status	Project Phase	Estimated Implementation / NTP Date	Community Notes	Development Verification Date
(P) 440005-101955	UIRF - Clintonville North-South Bike Route	Bike Facility	Clintonville	N/A	1955	North-South bike route as an alternative to High Street and Indianola.	Confirmed	Execution	Active		N/A	Majority of Phase I (signage and pavement markings) to be installed Fall of 2018. Some streets are scheduled to be resurfaced in 2018 and will be receive pavement marking at that time. Study of further phases is also being planned. Phase 2 completion date is yet to be determined.	3/25/2019 1:36PM Jackie Yeoman