

EXISTING UNDERGROUND STREET LIGHT SYSTEM REMOVAL

I. Quantity

The base bid shall include the removal of the existing street lighting system as hereinafter specified.

II. Material

All materials removed shall remain the property of the City of Columbus, Division of Power & Water (P)-(DOPW)(P)

III. Removal

The existing system shall be removed and disassembled as shown on the drawings and as indicated in the field by the engineer. The removal shall consist of any or all of the following items:

1. Street Light Standards and Mast Arms.
2. Street Light Fixtures and Lamps.
3. Conduit and underground cable (The contractor need not remove the existing direct buried series lighting cable where the same can be abandoned in place).
4. Pull boxes.
5. Removal of concrete foundations is not a part of this specification. The concrete foundation removal is bid as a separate item. (MIS-23 Concrete Foundation Removal).
6. Coils, transformers, and associated apparatus.
7. Miscellaneous hardware.

The contractor will be required to make connections to assure the continued operation of the adjacent streetlights not to be removed in this project. All material removed shall be promptly delivered to the Division of Power & Water (P) Distribution Warehouse, 3500 Indianola Avenue, unless the contractor is otherwise directed by the engineer. All material must be checked in by storeroom personnel before it is unloaded. Please contact DOPW(P) 645-7627 48 hrs prior to delivery to arrange for material to be returned to the Distribution Warehouse.

IV. Quotation

The existing system removal, as hereinbefore specified, shall be quoted on as a lump sum unit price in the appropriate place of this document.