

ITEM 652 PLACING STOCKPILED TOPSOIL

652.01 Description

652.02 Construction Requirements

652.03 Method of Measurement

652.04 Basis of Payment

652.01 Description. This work consists of hauling and spreading topsoil from stockpiles and preparing the surface.

652.02 Construction Requirements. Prepare the surface according to 653.03. Place and spread the topsoil according to 653.03.

652.03 Method of Measurement. The City will measure Placing Stockpiled Topsoil by the number of cubic yards (cubic meters) completed and accepted in place.

652.04 Basis of Payment. The City will pay for accepted quantities at the contract price as follows:

Item	Unit	Description
652	Cubic Yard (Cubic Meter)	Placing Stockpiled Topsoil