

PLAN NOTES - REQUIRED [CIP]

REFERENCE SPECIFICATIONS-

THE CITY OF COLUMBUS CONSTRUCTION AND MATERIALS SPECIFICATIONS (CMSC), 2012 EDITION INCLUDING ALL REVISIONS AND SUPPLEMENTS THERETO, SHALL GOVERN ALL CONSTRUCTION ITEMS THAT ARE A PART OF THE PLANS UNLESS NOTED OTHERWISE.

PERMITS-

WHEN EXCAVATING WITHIN COLUMBUS PUBLIC RIGHT OF WAY LIMITS, THE CONTRACTOR SHALL OBTAIN AN EXCAVATION PERMIT FROM CITY OF COLUMBUS, DEPARTMENT OF PUBLIC SERVICE- PERMIT OFFICE BETWEEN THE HOURS OF 7:30 AM AND 4:00 PM MONDAY THROUGH FRIDAY. PHONE (614) 645-7497; FAX: (614) 645-1876; EMAIL: colspemits@columbus.gov

UTILITIES-

THE IDENTITY AND LOCATION OF EXISTING UNDERGROUND UTILITIES LOCATED IN AND AROUND THE CONSTRUCTION AREA HAVE BEEN SHOWN AND LABELED ON THE PLANS BY USING INFORMATION PROVIDED BY THE RESPECTIVE UTILITY OWNERS. THE CITY OF COLUMBUS OR THE CONSULTING ENGINEER WILL NOT ASSUME RESPONSIBILITY FOR THE ACCURACY OF LOCATION OR DEPTH OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THE PLAN.

SUPPORT AND PROTECTION OF ALL UTILITIES AND APPURTENANCES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. COSTS FOR THE REPAIR AND RESTORATION OF EXISTING UTILITIES DAMAGED BY THE CONTRACTOR SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CITY OF COLUMBUS UTILITIES WILL ONLY LOCATE AND MARK MAIN LINE FACILITIES. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL SERVICE LATERAL AND LINES. COSTS ASSOCIATED WITH THE ABOVE WORK AND RESPONSIBILITIES SHALL BE INCLUDED IN THE PRICE BID FOR VARIOUS ITEMS.

PRIOR TO EXCAVATION, THE CONTRACTOR SHALL GIVE A 48-HOUR NOTICE TO THE OHIO UTILITIES PROTECTION SERVICE (OUPS) BY CALLING (800) 362-2764. A 48-HOUR NOTICE SHALL BE GIVEN TO THE OWNERS OF UNDERGROUND UTILITIES SHOWN ON THE PLANS WHO ARE NOT MEMBERS OF A REGISTERED UNDERGROUND PROTECTION SERVICE.

LISTED BELOW ARE UTILITY COMPANIES THAT HAVE FACILITIES LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT AND SUBSCRIBE TO OUPS.

*******CONSULTANT: PLEASE LIST THE NAMES, ADDRESSES, AND PHONE NUMBERS OF THE UTILITY COMPANIES WITH FACILITIES LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT AND SUBSCRIBE TO OUPS.*******

CITY OF COLUMBUS
DEPARTMENT OF PUBLIC SERVICE
TRAFFIC MANAGEMENT
1820 EAST 17TH AVENUE
COLUMBUS, OHIO 43219
OFFICE: (614) 645-7393

CITY OF COLUMBUS
SUPPORT SERVICES DIVISION-COMMUNICATIONS
4211 GROVES ROAD
COLUMBUS, OH 43232
TELEPHONE: (614) 724-7047
RADIO ROOM: (614) 724-4006

CITY OF COLUMBUS
DEPARTMENT OF TECHNOLOGY
1355 MCKINLEY AVENUE
BUILDING C
COLUMBUS, OHIO 43222
CONTRACTOR LINE: (614) 645-7756

THE FOLLOWING UTILITIES MAY BE LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT AND DO NOT SUBSCRIBE TO A REGISTERED UNDERGROUND PROTECTION SERVICE:

FIRM: XXXXX
ADDRESS: XXXX
CITY, ZIP CODE
TELEPHONE: (XXX) XXX-XXXX

EMERGENCY PROVISIONS-

THE CONTRACTOR SHALL PROVIDE TO THE CITY OF COLUMBUS PROJECT REPRESENTATIVE A LIST OF 24 HOUR EMERGENCY TELEPHONE NUMBERS (IN WRITING) PRIOR TO THE START OF CONSTRUCTION.

SECURING EXCAVATIONS & TRENCHES FOR NON-WORKING HOURS-

EXCAVATIONS AND TRENCHES OVER 24 INCHES DEEP SHALL BE SECURELY PLATED OR BACKFILLED DURING NON-WORKING HOURS.

CONSTRUCTION LIMITS-

THE CONSTRUCTION LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. THE INSTALLATION AND OPERATION OF ALL TEMPORARY TRAFFIC CONTROL AND TEMPORARY TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS SHALL BE PROVIDED BY THE CONTRACTOR WHETHER INSIDE OR OUTSIDE OF THESE CONSTRUCTION LIMITS.

MISCELLANEOUS WORK ITEMS-

THE CONTRACTOR SHALL PERFORM ALL ITEMS OF WORK CALLED FOR ON THE PLANS, FOR WHICH NO SPECIFIC METHOD OF PAYMENT IS PROVIDED. THE COST OF THESE ITEMS SHALL BE INCLUDED IN THE VARIOUS UNIT PRICES BID FOR THE PROJECT IMPROVEMENT.

BENCHMARKS AND SURVEY MONUMENTS-

DO NOT DISTURB ANY FRANKLIN COUNTY CERTIFIED BENCHMARKS (VERTICAL AND/OR HORIZONTAL) LOCATED WITHIN THE WORKING LIMITS OF THE PROJECT. CONTRACTOR SHALL CONTACT THE FRANKLIN COUNTY SURVEY DEPARTMENT (614) 525-3026, PRIOR TO CONSTRUCTION, TO COORDINATE THE PROPER PROCEDURES FOR THE RESETTING, RELOCATION, OR REPLACEMENT OF ANY FRANKLIN COUNTY CERTIFIED BENCHMARK OR SURVEY MONUMENT.

PLAN NOTES - INCLUDE ONLY IF APPLICABLE [CIP]

SAW CUTTING IS INCLUDED-

THE COST OF SAW CUTTING FOR THE REMOVAL OF PAVEMENT, CURB, WALKS, ETC. SHALL BE INCLUDED IN THE CONTRACT PRICE FOR ITEM 202 WORK ITEMS. SAW CUTTING IS REQUIRED TO PROVIDE SMOOTH STRAIGHT EDGES FOR REMOVAL PURPOSES.

NEW CURB RADIUS-

INTERSECTION CORNERS OR HORIZONTAL CURVES SHALL MATCH THE EXISTING RADIUS UNLESS NOTED OTHER WISE.

COTA- SIGNS AND/OR BUS STOPS-

PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL CONTACT SENIOR SERVICE PLANNER OF THE CENTRAL OHIO TRANSIT AUTHORITY (COTA) @ PH- (614) 308-4373 OR FAX- (614) 275-5933 TO COORDINATE PROPER BUS MOVEMENTS THROUGH OR AROUND THE JOB SITE DURING THE PROJECT. THIS WILL INCLUDE, BUT NOT BE LIMITED TO, THE TEMPORARY RELOCATION OR REMOVAL OF COTA SIGNS AND/OR BUS STOP LOCATIONS.

COTA- BUS SHELTERS/PADS-

THE CONTRACTOR SHALL NOTIFY SENIOR SERVICE PLANNER OF COTA @ PH- (614) 308-4373 OR FAX- (614) 275-5933 A MINIMUM OF TWO WEEKS PRIOR TO THE REQUIRED REMOVAL OF A BUS SHELTER. COTA WILL DISASSEMBLE THE SHELTER AND THEN REINSTALL IT ONCE THE NEW CONCRETE SLAB IS IN PLACE. CONTRACTOR SHALL CONSTRUCT THE SLAB AS DIRECTED BY THE PLANS OR OTHER CONTRACT DOCUMENTS. ALL CONCRETE SLAB WORK SHALL BE PAID AS PER ITEM SPECIAL, REMOVE AND REPLACE BUS SHELTER SLAB, WITH THE CONTRACT UNIT PRICE PER EACH. THIS PAY ITEM SHALL INCLUDE ALL EXCAVATION AND REMOVAL WORK, EXPANSION JOINT MATERIAL, ITEM 608 - 6" CONCRETE WALK, AND ANY OTHER WORK AS REQUIRED OR DIRECTED BY THE ENGINEER.

GAS SERVICE VALVES ADJUSTED TO GRADE-

THE CONTRACTOR SHALL CONTACT COLUMBIA GAS (614) 460-2244 TO COORDINATE THE ADJUSTMENT OF GAS SERVICE VALVES.

COLUMBIA GAS DAMAGE PREVENTION CENTER-

FOR INFORMATION CONCERNING COLUMBIA GAS LINES OR EQUIPMENT, OR IF DAMAGE OCCURS TO GAS LINES OR EQUIPMENT, THE CONTRACTOR CAN CALL THE COLUMBIA GAS DAMAGE PREVENTION CENTER @ (614) 280-7372 OR TOLL FREE @ (866) 632-6243.

NEW PIPE CONNECTION TO AN EXISTING SEWER STRUCTURE-

WHERE THE PLANS PROVIDE FOR NEW PIPE TO BE CONNECTED TO AN EXISTING SEWER/STRUCTURE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CREATING AN OPENING AT THE PROPER SIZE, ALIGNMENT, AND ELEVATION FOR THE CONNECTION. THE OPENING SHALL BE MADE LARGE ENOUGH TO RECEIVE AND JOIN THE PROPOSED PIPE PER CMSC ITEM 604.

NO DIRECT PAYMENT SHALL BE MADE. ALL COSTS ASSOCIATED WITH THIS WORK SHALL BE INCLUDED IN THE UNIT PRICE FOR ITEM 901- PIPE WITH TYPE _ BEDDING.

CONTINGENCY QUANTITIES-

THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK SHOWN, LABELED, OR LISTED AS 'CONTINGENCY' OR REFERENCED BY PLAN NOTE TO BE USED 'AS DIRECTED BY THE ENGINEER,' UNLESS AUTHORIZED BY THE ENGINEER, OR A REPRESENTATIVE OF THE CITY OF COLUMBUS, DIVISION OF DESIGN AND CONSTRUCTION.

CONCRETE WALKS-

ALL EXISTING CONCRETE SIDEWALKS BEING REPLACED WITH NEW CONCRETE SIDEWALKS SHALL BE REMOVED AT AN EXISTING JOINT AND REPLACED PER STANDARD DRAWING 2300. INSTALL EXPANSION JOINT WHERE NEW CONCRETE ADJOINS EXISTING SIDEWALK.

ALL EXISTING CONCRETE SIDEWALKS NOT SCHEDULED FOR REPLACEMENT BUT BEING CROSSED BY THE INSTALLATION OF TRAFFIC ITEMS, ELECTRICAL CONDUIT, PIPING, ETC. SHALL BE FULLY REMOVED AT AN EXISTING JOINT AND REPLACED PER STANDARD DRAWING 2300 UNLESS NOTED OTHERWISE. PAYMENT SHALL BE INCLUDED IN THE PRICE BID FOR ITEM 608- CONCRETE WALK.

"AS PER PLAN" NOTES - INCLUDE ONLY IF APPLICABLE [CIP]

AN 'AS PER PLAN' ITEM IS A STANDARD PAY ITEM WHOSE REQUIREMENTS NEED TO BE MODIFIED FROM THAT WHICH IS DEFINED IN THE CMSC OR SUPPLEMENTAL SPECIFICATIONS. EACH 'AS PER PLAN' ITEM SHALL HAVE A CORRESPONDING PLAN NOTE(S) OR PLAN DETAIL(S) OR COMBINATION. CLEARLY SPECIFY THE DEVIATIONS FROM THE STANDARD ITEM IF AN ITEM IS 'AS PER PLAN.' THE 'AS PER PLAN' TEXT SHALL BE INSERTED AT THE END OF THE ITEM DESCRIPTION.

EXAMPLES:

WALK REMOVED 'AS PER PLAN'

THE EXISTING SIDEWALK SHALL BE REMOVED IN ACCORDANCE WITH THE PROPOSED SIDEWALK DETAILS. REMOVAL SHALL BE IN CONFORMANCE WITH CMSC SECTION 202. REFERENCE THE PLANS FOR LOCATIONS. THICKNESS' OF EXISTING WALKS VARY FROM 4" TO 8". NO SEPARATE PAYMENT SHALL BE MADE FOR REMOVAL OF THE VARIOUS THICKNESS' OF THE WALKS ENCOUNTERED. ANY SAW CUTTING NECESSARY TO REMOVE SIDEWALKS SHALL BE INCLUDED. PAYMENT SHALL BE PER SQUARE FOOT AND SHALL INCLUDE ALL NECESSARY TOOLS, LABOR, AND MATERIALS.

PAVEMENT PLANING 'AS PER PLAN'

UNDER THIS ITEM, ASPHALT SHALL BE MILLED FROM DESIGNATED STREETS TO A MINIMUM 1" DEPTH (TYPICAL 1.5"), OR AS INDICATED WITHIN THESE PLANS. PLANING DEPTHS INDICATED MAY BE ADJUSTED IN THE FIELD AT THE ENGINEER'S DISCRETION. INCREASED OR DECREASED PAVEMENT PLANING THICKNESS SHALL BE PERFORMED AT NO ADDITIONAL COST. ALL STREET PLANING SHALL MAINTAIN THE EXISTING CROWN. IF THE CROWN IS REMOVED AS A RESULT OF THE CONTRACTOR'S ERROR OR WITHOUT THE ENGINEER'S PRIOR APPROVAL, NO ADDITIONAL ASPHALT ABOVE THE PLAN QUANTITY FOR EACH SHEET SHALL BE PAID.

THE CONTRACTOR SHALL LOCATE ALL EXISTING LOOP DETECTORS PRIOR TO PLANING. IN THE EVENT A LEAD-IN CABLE IS DAMAGED, THE CONTRACTOR SHALL REPAIR. NO SEPARATE PAYMENT SHALL BE MADE FOR LOOP DETECTOR REPAIRS.

BRICKS REMOVED, SALVAGED AND DELIVERED (S.Y.)

REMOVAL: CAREFULLY REMOVE ALL BRICKS AS INDICATED FOR REMOVAL WITHOUT UNNECESSARY DAMAGE AND CLEANED FOR RE-USE. INCLUDE THE REMOVAL AND DISPOSAL OF THE SAND SETTING BED.
SALVAGE: STACK ALL UNDAMAGED AND CLEANED BRICKS ON PALLETS AND SECURELY WRAP, FASTEN OR BOX IN PALLETS. STACK BRICKS NO MORE THAN EIGHT (8) LAYERS HIGH.
DELIVERY: TRANSPORT ALL SALVAGED BRICKS TO THE CITY OF COLUMBUS DEPARTMENT OF PUBLIC SERVICE 25TH AVE. MAINTENANCE YARD. CONTRACTOR SHALL CALL THE MAINTENANCE YARD MANAGER AT (614) 645-8120 AT LEAST TWO WEEKS IN ADVANCE TO MAKE ARRANGEMENTS FOR DELIVERY. PAYMENT FOR THIS WORK SHALL BE MADE AFTER THE UNDAMAGED BRICK HAS BEEN DELIVERED. INCLUDE IN THE COST ALL WORK REQUIRED TO REMOVE, CLEAN, SALVAGE, AND DELIVER BRICK AS BID PRICE FOR ITEM 202 - BRICK REMOVED FOR STORAGE, AS PER PLAN - SY.

REVISED 4/1/16

CALCULATED
ABC

CHECKED
ABC

GENERAL NOTES

PROJECT NAME

XXXX-E
XX