

250 PAVEMENT REPAIRS

ITEM 253 - TEMPORARY PAVEMENT

- 253.01 Description
- 253.02 General
- 253.03 Construction
- 253.04 Materials
- 253.05 Maintenance
- 253.06 Method of Measurement
- 253.07 Basis of Payment

253.01 Description. To provide for temporary pavement, wherever ordered, on permanent pavements damaged or removed by the Contractor in the performance of the work.

Permanent pavement as herein used shall mean any hard surface type pavement including, sheet asphalt, concrete, brick, asphalt concrete, surface treated macadam and similar materials.

253.02 General. As soon as the excavation has been backfilled, temporary pavement shall be provided wherever ordered by the Engineer. The temporary pavement shall be installed on the same work day the original pavement is removed and the Engineer may require that all materials and equipment incidental to providing the temporary pavement be on the job site prior to removing the existing pavement.

253.03 Construction. Temporary pavement shall consist of 2 inches (50 mm) of compacted bituminous material placed upon 6 inches (152 mm) of compacted granular base material, as shown on City of Columbus, *Transportation Division*, Standard Drawing 2161 Dr. A.

253.04 Materials. Bituminous material shall be either hot mix or cold mix conforming to Items 404 or 405, or as directed by the Engineer. Granular base material shall be "Aggregate Base" conforming to Item 304, of the Specifications or an approved substitute.

253.05 Maintenance. The Contractor shall maintain the temporary pavement in a condition suitable to the Engineer until such time as the permanent pavement is constructed. If the temporary pavement is not maintained in a condition acceptable to the Engineer, the City may take any necessary action to have the temporary pavement placed in a proper condition, and the cost of any such actions by the City shall be deducted from payments which may be due or may come due the Contractor.

253.06 Method of Measurement. Temporary pavement furnished and placed under this Item shall be measured for payment as the actual area placed, but in no case will

the limiting lines for measurement be in excess of 1 foot (0.3 m) exterior to the excavation limits shown on standard drawings, unless otherwise approved by the Engineer.

253.07 Basis of Payment. Payment for this Item shall be at the unit price bid per square yard (square meter) for Temporary Pavement, placed and measured as specified above, including bituminous topping and granular base, and shall include all cost for constructing and maintaining same until permanent pavement is replaced.

Payment will be made at the contract price for:

Item	Unit	Description
253	Square Yard (Square Meter)	Temporary Pavement