

## 600 INCIDENTALS

### ITEM 618 - PIPE ROOF DRAINS

- 618.01 Description**
- 618.02 Materials**
- 618.03 Construction**
- 618.04 Method of Measurement**
- 618.05 Basis of Payment**

**618.01 Description.** This item shall consist of excavating, furnishing, installing and backfilling pipe designated by the plans in accordance with the lines and grades given or as otherwise directed by the Engineer.

**618.02 Materials.** Specific pipe and fitting materials shall be as:

Vitrified clay pipe.....	706.08
Polyvinyl chloride plastic pipe (3 inch) (76 mm) .....	720.01

**618.03 Construction.** The laying of the pipe, type of joints and other details of construction shall conform to standards for type of pipe selected. The upper end of the pipe, when not connected to existing roof drain, shall be blocked with an approved stopper. Payment for stopper shall be included in the price bid for pipe roof drain.

**618.04 Method of Measurement.** The quantity shall be the actual length of pipe installed in place, completed and accepted.

**618.05 Basis of Payment.** Payment will be made at the contract price for:

<b>Item</b>	<b>Unit</b>	<b>Description</b>
618	Linear Foot (Meter)	Pipe Roof Drains