

ITEM 635 - DERRICK STONE

635.01 Description

635.02 Materials

635.03 Placement

635.04 Method of Measurement

635.05 Basis of Payment

635.01 Description. This work shall consist of furnishing all materials and labor for the placement of Derrick Stone, including clearing and grubbing, removal of all materials necessary for placing the Derrick Stone as required, constructing, maintaining, and subsequently removing all necessary cofferdams, cribs and sheeting, provide pumping if necessary, or providing some other method of placement of the Derrick Stone, at the locations and in reasonably close conformity with the lines, grades, and thicknesses as shown on the plans.

635.02 Materials. The Derrick Stone shall be Limestone, with its greatest dimension not greater than two times its least dimension. Individual stones shall weigh not less than 1000 pounds (453.6 kg) and no more than 6000 pounds (2721.6 kg). At least 70 percent of all stones furnished shall weigh over 4000 pounds (1814.4 kg).

635.03 Placement. The Derrick Stone shall be carefully placed within the areas as specified and shown on the plans. The larger stone at the outer face and the smaller rocks to fill the voids between the larger stone and to shape the placement according to the plans.

Placement shall be by constructing, maintaining and subsequently removing cofferdams, cribs, sheeting or by some other approved method, including clearing, grubbing, removal of all materials necessary for placing the Derrick Stone, including pumping if necessary and restoration.

635.04 Method of Measurement. The number of tons of Derrick Stone to be paid for under this item shall be the number of tons (metric tons) placed, completed and accepted according to truck scale weight tickets.

635.05 Basis of Payment. Payment will be made at the contract bid price for:

Item	Unit	Description
635	Ton (Metric Ton)	Derrick Stone