

900 SEWERAGE WORK

ITEM 907 - SHEETING AND BRACING LEFT IN PLACE

907.01 Description

907.02 Method of Measurement

907.03 Basis of Payment

907.01 Description. This item shall consist of all sheeting, bracing and other supports left in place where specifically ordered in writing by the Engineer, regardless of the reason or purposes for which installation was made.

907.02 Method of Measurement. Only sheeting and bracing and other supports actually left in place by written order of the Engineer will be measured for payment. No measurement will be made of any sheeting and bracing or other supports cut off, wasted, and extending below the top elevation of the concrete bedding, concrete backing, concrete backfill, or subgrade or left in place without a written order from the Engineer.

907.03 Basis of Payment. The quantities of sheeting, bracing and other supports measured for payment will be paid for at the contract unit price, per square foot (square meter) for timber sheeting and bracing and for steel sheeting and bracing left in place.

Payment will be made under:

Item	Unit	Description
907	Square Foot (Square Meter)	Timber Sheeting and Bracing Left in Place.
907	Square Foot (Square Meter)	Steel Sheeting and Bracing Left in Place.