Mayor Michael B. Coleman

GRAPHICS COMMISSION APPLICATION

City of Columbus, Ohio • Department of Building & Zoning Services
757 Carolyn Avenue, Columbus, Ohio 43224 • Phone: 614-645-7433• www.columbus.gov

OFFICE USE ONLY

Application Number: 11320-00366
Date Received: 7/7/11
Commission/Group: Rocky Fork
Existing Zoning: CPD Application Accepted by: D. Reiss Fee: $1,900.00
Comments: 9/20/11

TYPE(S) OF ACTION REQUESTED

(Check all that apply)

☒ Variance ☐ Graphics Plan ☐ Special Permit ☐ Miscellaneous Graphic

Indicate what the proposal is and list applicable code sections. State what it is you are requesting.

Describe We are requesting the allowance of internally illuminated menu boards and pre sell boards and also a road sign as originally submitted. Pursuant to CPD zoning text Z05-035 - these signs are not in compliance. The manu boards because they are internally illuminated and are not monument style, the pre sell boards because they are internally illuminated and the road sign because it is monument style not post/pole mounted

LOCATION

1. Certified Address Number and Street Name 5421 New Albany Rd., West (McDonald's)
   City New Albany State OH Zip 43054
   Parcel Number (only one required) 010-289804-00

APPLICANT

2. Name Kessler Sign Company
3. Address 2669 National Rd., PO Box 785 City/State Zanesville, OH Zip 43702
4. Phone # 800-686-1870 Fax # 740-453-5301 Email rodger@kesslersignco.com

PROPERTY OWNER(S)

2. Name New Albany Company
3. Address 5906 E. Dublin Granville Rd. City/State New Albany, OH Zip 43054
4. Phone # 614-939-8000 Fax # Email

☐ **Check here if listing additional property owners on a separate page.**

ATTORNEY / AGENT (CIRCLE ONE)

8. Name Rodger Kessler, Vice President of Kessler Sign Company, as Agent for McDonald's Corporation
9. Address 2669 National Rd., PO Box 785 City/State Zanesville, OH Zip 43702
10. Phone # 800-686-1870 Fax # 740-453-5301 Email rodger@kesslersignco.com

SIGNATURES

11. Applicant Signature Rodger Kessler
12. Property Owner Signature Tom Ruby
13. Attorney / Agent Signature Rodger Kessler

If you have any questions regarding this information, please call: (614) 645-4522

Revised 2/03/11

11320-00366
5421 New Albany Road, W.

CITY OF COLUMBUS

DEPARTMENT OF BUILDING AND ZONING SERVICE

One Stop Shop Zoning Report Date: Mon Jul 11 2011

Zoning General Inquiry: 614-645-8637

SITE INFORMATION

Address: 5421 NEWALBANY RD W COLUMBUS OH 43054
Mailing Address: 8000 WALTON PKWY STE 120
NEWALBANY OH 43054

Owner: NEWALBANY COMPANY LLC
Parcel Number: 010289804

ZONING INFORMATION

Zoning: Z05-035, Commercial, CPD
effective 4/3/2006, Height District H-60
Council Variance: N/A
Board of Zoning Adjustment (BZA): N/A
Graphic Commission: N/A
Area Commission: N/A
Planning Overlay: N/A

Historical District: N/A

Historical Site: No
Overlay: N/A
Flood Zone: OUT
Airport Noise Environ: N/A

PENDING ZONING ACTION

Zoning: N/A
Board of Zoning Adjustment (BZA): N/A

Council Variance: N/A
Graphic Commission: N/A



Mayor Michael B. Coleman

GRAPHICS COMMISSION APPLICATION

City of Columbus, Ohio ▪ Department of Building & Zoning Services
757 Carolyn Avenue, Columbus, Ohio 43224 ▪ Phone: 614-645-7433▪ www.columbus.gov

STATEMENT OF HARDSHIP

APPLICATION # 11320-00366

5421 New Albany Road, W.

3382.05 Variance.

Any request for a Variance from this Graphics Code shall be heard and decided by the Graphics Commission as provided by the Graphics Code.

A. The Graphics Commission shall have the power, upon application, to grant a Variance from one (1) or more provisions of this Graphics Code. No Variance shall be granted unless the Commission finds that a hardship exists, based upon special physical conditions which:

1. Are due to exceptional shallowness, shape, topographic conditions or other extraordinary situations peculiar to the premises itself; or
2. Differentiate the premises from other premises in the same zoning district and the general vicinity; or
3. Prevent a reasonable return in service, use or income compared to other conforming premises in the same district; and
4. Where the result of granting the variance will not be injurious to neighboring properties and will not be contrary to the public interest or to the intent and purpose of the Graphics Code.

B. In granting a Variance, the Graphics Commission may impose such requirements and conditions regarding the location, character, and other features of the *graphics* as the Commission deems necessary to carry out the intent and purpose of this Graphics Code and to otherwise safeguard the public safety and welfare.

C. Nothing in this Graphics Code shall be construed as authorizing the Commission to affect changes in the Zoning Map or to add to the uses permitted in any zoning district.

I have read Section 3382.05 Variance, and believe my application for relief from the requirements of the Graphics Code satisfies the four criteria for a variance in the following ways:

Regarding the menu boards and presell boards, it is necessary for the menu boards and pre sell boards to be internally illuminated so that they can be read at night. These menu boards and pre sell boards are designed to be tools to make the traffic flow less confusing and allow for faster, better service to the customer. These are not designed as "signs" to be seen by the road or to advertise products, simply to inform the customer of their choices. These would in no way effect the flow of the main road traffic. Regarding the road sign, the design, as we submitted, is very similar to the other signs in the area and is externally illuminated. We believe that upon review of the design, the committee will agree that the sign acceptable.

Signature of Applicant Robyn Cooke Date 7-7-11

DEVELOPMENT PLAN – ZONING TEXT
PROPOSED DISTRICTS: CPD
PROPERTY ADDRESS: 5475 New Albany Road East
OWNER: The New Albany Company, LLC
APPLICANT: Same as owner
DATE OF TEXT: 3/10/06
APPLICATION NUMBER: Z05-035

1. INTRODUCTION:

The subject site was Subarea 2 in Z95-102 which zoned a large tract of land between the New Albany Expressway and Central College Road in 1998. For continuity with the prior application this Subarea is still referred to Subarea 2 in this new application. The applicant needs to modify the development to reflect new use and proposed development pattern.

Subarea 2 CPD

Subarea 2 because of its location along the New Albany Expressway may be characterized by office, commercial and hotel development

2. PERMITTED USES:

1. The following uses shall be permitted within Subarea 2. Those uses permitted under Chapter 3356. C-4, Commercial District of the Columbus City Code and gas sales and/or car wash.

2. Excepting therefrom:

a. Automobile assessroom
b. Billboards
c. Bowling alley
d. Commercial radio transmitting or television station and appurtenances
e. Electric substation
f. Funeral parlor
g. Motion picture theater
h. Motor vehicle sales or leasing
i. New or used car lot
j. Public parking for pay
k. Stable

3. The northwest quadrant shall consist of inline retail and/or outparcels; the southeast quadrant shall consist of the main retail center and up to three outlots. The parking field for the main retail center may extend into the outparcel area, and the northwest quadrant.

3. DEVELOPMENT STANDARDS:

Except as otherwise noted above and therein, the applicable development standards of Chapter 3356 shall apply to Subarea 2.

A. Density, Height, Lot and/or Setback commitments.

1. Minimum setback from New Albany Expressway shall be 40 ft. for parking, loading and maneuvering areas, 100 ft. for retail center building (excluding drive thru window structure) and 50 ft. for all outparcel buildings. Minimum setback from New Albany Road and New Albany Road West shall be 50 ft. for all buildings and 25 ft. for parking, loading and maneuvering areas.

2. Minimum setback along the main full access entry driveway off of New Albany Road West shall be 15 feet for parking, loading and maneuvering areas and 40 feet for buildings. (Setback measured from back of curb)

3. Lot coverage for building and paved areas shall not exceed seventy percent of the total subarea.

4. Height district shall be 60 ft.; buildings in outlots shall have a maximum height of 35 feet except that architectural elements (i.e. cupolas, catwalks and chimneys) may extend to 38 feet in height.

B. Access, Loading, Parking and/or other Traffic related commitments.

1. The curbcuts for the site are shown on the submitted CPD site data plan; any modification to the curbcuts shall be subject to review and approval of the City's Transportation Division.

C. Buffering, Landscaping, Open space and/or Screening commitments.

1. Landscaping within the 25 ft. parking setback along New Albany Road and New Albany Road West shall contain a 3 ft. –3 ft. high continuously uniform shrubbery screen and/or mound along with a white horse fence. Trees shall be planted within the 25 ft. setback in a hedge row manner per the following standards: 4 deciduous shade trees and 3 multi-stem ornamental trees per 100 foot of frontage.

2. Landscaping within the New Albany Expressway 40 ft. parking setback shall be based on the following standard:

a. Existing trees shall be preserved.

b. There shall be a 3 ft. –4 ft. high continuously uniform shrubbery screen and/or mound along with a white horse fence within the 40' New Albany Expressway parking setback. The shrubbery screen shall be located along the edge of parking lots toward the Expressway right-of-way.

c. New trees shall be planted within the parking setback and in a hedge row manner approximately 30' behind the Expressway right-of-way per the following standards: 6 shade trees and 4 multi-stem ornamental trees shall be planted per 100 lineal feet.

3. A street tree row shall be established along all publicly dedicated right-of-way (other than New Albany Expressway) containing one tree for every 30' of road frontage. Such trees shall be those specified in the Columbus Street Program guidelines from the City of Columbus Forester and located a minimum 1 foot from edge of right-of-way unless the City of Columbus approves planting these trees within the right-of-way. Minimum tree size at installation shall be 2 ½" caliper.

4. One tree shall be planted for every six parking spaces. Trees shall be planted in islands at least five feet wide. At least 5% of the vehicular use area (i.e. parking lot excluding the perimeter circulation drive exterior to the parking lot) shall be landscaped (including trees).

5. All loading docks shall be screened from off-site view to a minimum height of six (6) feet by either landscaping, fencing, walls or buildings used individually or in combination thereof.

6. The property owner shall grant a conservation easement as shown on the submitted CPD site data plan to the City of Columbus along the banks of the Sugar Run Creek subject to retaining its right to cross the easement area with streets, utility lines and to install a leisure path.

7. Unless otherwise specified minimum size of all trees shall be 2.5 in. caliper for deciduous, 6 ft. high for evergreens, and 1.5 in. caliper for ornamental trees. Any mounding shall have a maximum 3:1 slope with landscaping.

8. The landscaping required in this section shall count toward satisfying the landscaping requirements of Chapter 3342 of the Columbus City Code.

9. All trees and landscaping shall be well maintained. Dead items, weather permitting shall be replaced within six months.

10. The area east of the creek within the Subarea as shown on the submitted CPD site data plan as open space shall be subject to a conservation easement granted to the City of Columbus. The property owner retains the right to cross that easement area with utility lines and leisure trail.

11. The developers shall install a sidewalk along New Albany Road West from the 161 Bypass to the north edge of the subarea.

12. Subject to the approval of the Recreation and Parks Department the developer shall install a walking path through the open space connecting the sidewalk along New Albany Road West with the internal pedestrian walkway system within the visual corridor described in Item G4 below.

13. Bike racks shall be provided within the visual corridor described in Item G4 in connection with the proposed walking path.

14. Landscape plans for individual developments within the subarea shall be reviewed by a registered designer or architect selected by the developer.

D. Dumpsters, Lighting, Outdoor display areas and/or other environmental commitments.

1. All external lighting shall be cutoff type fixtures (down-lighting), and shall provide no light spillage to off-site parcels. However, buildings and landscaping at entry locations may be uplit or accent provided that landscaping lighting does not spill over into the public right-of-way. Any wall mounted lighting shall be shielded to create a cut-off type fixture. In the service area adjacent to the conservation corridor the level of outdoor lighting shall be consistent throughout the service area to avoid hot spots. The outdoor light level in the service area shall be minimize subject to maintaining a sufficient level of lighting to provide adequate security in that area.


PARKING DETAIL
(No Scale)
2" Bumper Overhang
6" Curb
18"
16'
Note: Sign posts, light poles, and landscaping or any other obstructions are not permitted within 2' of the face of curb.
ZONED CPD
(Z05-035)
PROPOSED BUILDING
PID: 010-289804
4,353± SF (building)
FFE =1004.30
Patio 700± SF
Prop Bicycle Bakerax (4 Spaces)
Prop Flag Pole (See Architectural Plans for Details)
Proposed Dumpster Pad & Enclosure (Screened per Development Text, See Architectural Plans for Details)
Proposed Mechanical Room (See Architectural Plans for Details)
Proposed Grease Interceptor (See Architectural Plans for Details)
Proposed Striping
Proposed 6" San Ser (By Permit)
Remote FDC
Stop Bar
"Stop" sign
"Do Not Enter" sign
See Note A
Ex Tree
Prop 12" Strm
Ex Private 10' General Utility Easement
Ex ingress/Egress Easement I.N. 200611010219140
Ex 8"x8" Wye
Ex 8" San (BP-72176)
Ex 18" Strm (CC-14630)
Ex 6" San (BP-72176)
Ex 12" Strm (BP-72176)
Ex 12" Strm (BP-72176)
Ex 12" Strm (CC-14664)
Ex 30' Sanitary Sewer Easement I.N. 200606020107232
Ex Storm Sewer Easement I.N. 201101040001755
JPMORGAN BANK NA PID 010-280573 CPD
NEW ALBANY ASSOCIATES LP PID 010-282719 CPD
NEW ALBANY CO LLC PID 010-289804 CPD
NEW ALBANY CO LLC PID 010-289505 CPD
Prop Light Pole (Typ) (By Others)
Ex Utility Easement
Ex 25' Electric Easement I.N. 200703120042972
Ex 21" Strm (1889 Dr E)
Ex 6" Plug
Ex 2" Curb stop
Ex 12" Strm
Ex 12" Strm
Ex 12" Strm



VICINITY MAP
NO SCALE

BENCH MARKS

SOURCE BENCH MARK, Elevation obtained using Topcon RTK GPS equipment and Ohio Department of Transportation CORS/VRS Network, NAVD 1988.

B.M. #1 ~Southwest corner of concrete base of light pole, on SW side of the existing lane connecting New Albany Road West to New Albany Road, 90'± E. of a fire hydrant. ELEV=1003.45

B.M. #2 ~ Bolt on fire hydrant, in New Albany Market parking lot, located 62'± south of the trash area for the Get-Go Gas Station and 18' west of the McDonald's lot line. ELEV=1002.63

NOTES

1. This drawing was prepared in reliance on Chicago Title Insurance Company, Order No. 38100141 dated November 3, 2010.

2. Utility locations on this survey are reported from field locations or information provided by utility representatives. This does not mean there could not be other utilities in the area.

3. According to F.E.M.A. Flood Insurance Rate Map, Number 39049C0202K, effective date June 17th, 2008, for Community No. 390170, this property is in a zone "X" area determined to be outside the 0.2% annual chance flood area.

4. Add 900 to all spot elevations to obtain NAVD 88 elevations.

0' 20' 40' 60' 80'
GRAPHIC SCALE

2 WORKING DAYS BEFORE YOU DIG 1-800-362-2764
CALL TOLL FREE 800-362-2764
OHIO UTILITIES PROTECTION SERVICE

1.020 ACRES

Situated in the State of Ohio, County of Franklin, City of Columbus, located in Section 14, Quarter Township 2, Township 2, Range 16, United States Military Lands, being part of that original 79.298 acre tract conveyed to The New Albany Company, LLC by deeds of record in Official Record 12576815, Official Record 21256E01, and Instrument Number 199811120289607 (all references refer to the records of the Recorder's Office, Franklin County, Ohio), and being described as follows:

Beginning, for reference, at the centerline intersection of New Albany Road West, of record in Plat Book 103, Pages 32-33, with New Albany Road and New Albany Road East, of record in Plat Book 92, Pages 60-61;

thence South 03° 34' 19" West, with the centerline of said New Albany Road, a distance of 183.35 feet to a point;

thence North 88° 25' 41" West, across the right-of-way of said New Albany Road, a distance of 79.66 feet to an iron pin set on the arc of a curve in the easterly right-of-way line of said New Albany Road, the TRUE POINT OF BEGINNING;

thence South 59° 06' 27" West, across said 79.298 acre tract, a distance of 116.56 feet to an iron pin set;

thence South 41° 28' 32" West, continuing across said 79.298 acre tract, a distance of 70.81 feet to an iron pin set;

thence South 77° 22' 13" West, continuing across said 79.298 acre tract, a distance of 151.92 feet to a magnetic nail set on the arc of a curve in the easterly line of that 11.040 acre tract conveyed to New Albany Associates, L.P. by deed of record in Instrument Number 200611010219141;

thence with the easterly line of said 11.040 acre tract, with said curve to the left, having a central angle of 14° 17' 16", a radius of 360.00 feet, an arc length of 64.84 feet and a chord bearing and distance of North 19° 03' 59" West, 64.67 feet to a magnetic nail set at the southerly corner of that 1.241 acre tract conveyed to JPMorgan Chase Bank, National Association by deed of record in Instrument Number 200608020151787;

thence North 41° 28' 32" East, with the southeasterly line of said 1.241 acre tract, a distance of 306.80 feet to an iron pin set on the arc of a curve in the southerly right-of-way line of said New Albany Road West;

thence with said southerly right-of-way line, with the arc of said curve to the right, having a central angle of 31° 06' 29", a radius of 342.70 feet, an arc length 186.07 feet and a chord bearing and distance of South 37° 55' 29" East, 183.79 feet to the TRUE POINT OF BEGINNING, containing 1.020 acres more or less, out of Parcel Number 010-285204.

Subject to all legal rights-of-way and/or easements, if any of previous record.

Iron pins set, where indicated, are iron pipes, thirteen sixteenths (13/16) inch inside diameter, thirty (30) inches long with a plastic plug placed in the top bearing the initials EMHT INC.

Bearings are based on the Ohio State Plane Coordinate System as per NAD83 (1986 adjustment). Control of bearings was from coordinates of monuments Frank 5574 and Frank 5113, with Central College Road having a bearing of South 88° 09' 39" East, established by Franklin County Engineering Department, using Global Positioning System procedures and equipment.

NEW ALBANY MARKET
NEW ALBANY ASSOCIATES, L.P.
11.040 Ac.
INST 200611010219141
Tax Par #010-282719

JPMORGAN CHASE BANK, NATIONAL ASSOCIATION
1.241 Ac.
INST 200608020151787
Tax Par #010-280573

CHASE BANK

NEW ALBANY ROAD WEST (R/W Varies)
P.B. 103, Pg. 32
1989 Dr E

NEW ALBANY ROAD EAST
P.B. 92, PG. 60

REFERENCE POINT OF BEGINNING

TRUE POINT OF BEGINNING

NEW ALBANY ROAD
3983 Dr D

1.020 ACRES

B.M. #1
Ctr LP=1003.49

B.M. #2
FH BOLT=1002.63

R=342.70'
Δ=31°06'29"
CB=S 37°58'29" E
CH=183.79'
L.A.=186.07'

N 41°28'32" E 306.80'
S 77°22'13" W 151.92'
S 41°28'32" W 70.81'
S 59°06'27" W 116.56'
N 86°25'41" W 79.66'
S 3°34'19" W 183.35'

THE NEW ALBANY COMPANY, LLC
79.298 Ac. (Orig.)
O.R. 12576815,
O.R. 21256E01 &
INST 199811120289607
Tax Par #010-285204

25' Ingress/Egress Easement Provided in the Declaration of Covenants, Conditions, Restrictions and Easements in INST 200611010219140

10' Storm Sewer Easement Provides in the Declaration of Covenants, Conditions, Restrictions and Easements in INST 200611010219140

25' Easement to Columbia Gas of Ohio, Inc. INST 200608020151787

25' Easement to Southern Ohio Electric in INST 200703120042972

25' Easement to Ohio Bell Telephone Co. and AT&T in INST 200705240081699

Ex 25' Utility Easement P.B. 103, Pg. 32

Ex 30' Storm Sewer Easement INST 200608020151787

Ex 30' Storm Sewer Easement INST 200608020151787

Ex 10' Storm Sewer Easement INST 200608020151787

Ex 10' Storm Sewer Easement INST 200611010219140

Ex Ingress/Egress Easement Provided in the Declaration of Covenants, Conditions, Restrictions and Easements in INST 200611010219140

Ex 25' Utility Easement P.B. 103, Pg. 32

Ex 25' Utility Easement P.B. 103, Pg. 32

Ex 25' Utility Easement P.B. 103, Pg. 32

City of Columbus
Address Plat

CERTIFIED HOUSE NUMBERS

The House Numbers Contained on This Form are Herein Certified for Securing of Building & Utility Permits

Parcel ID: 010289804
House Number: 5421
Lot Number: N/A
Work Done: NEW

Project Name: MCDONALD'S
Street Name: NEW ALBANY RD W
Subdivision: N/A
Complex: NEW ALBANY MARKET

Owner: NEW ALBANY COMPANY LLC
Request By: EMHT
Issued By: Louis O. McCann **Date: 3/18/2011**



SCALE: 1 inch = 100 feet

PATRICIA A. AUSTIN, P.E., ADMINISTRATOR
DIVISION OF PLANNING AND OPERATIONS
COLUMBUS, OHIO

GIS FILE NUMBER: 1307044

printed: 3/18/2011 - 3:13:36 PM - O:\MAPROOM\ADDRESS IMAGES\NOS

CLARENCE E MINGO II
FRANKLIN COUNTY AUDITOR

MAP ID: S **DATE: 7/7/11**



Disclaimer

This map is prepared for the real property inventory within this county. It is survey plats, and other public records and data. Users of this map are notifi information sources should be consulted for verification of the information county and the mapping companies assume no legal responsibilities for the Please notify the Franklin County GIS Division of any discrepancies.

11320-00366

5421 New Albany Road, W.

11320-00366

5421 New Albany Road, W.



NEW D/F .090 ALUMINUM SIGN
EXTERNALLY LIT W/ STEEL TUBING
& AUGURED FOUNDATION





SIGN A *(national city side at the RI/RO)*

NEW ALBANY BLUE (LOW SHEEN)
CREATIVE PAINTS (JEREMY SYNAL) - 614-263-5437

WHITE

PMS 123

Client: McDonalds
Location: New Albany Market
Client Approval:

Saved as "McDonalds_New_Albany_Market"

REVISED: 5-11-11

Total Area	Design No.
Circuits	Date 3/11/11
Voltage	Drawn by Jared
Scale 1/4" = 1'	Salesman Rodger

All Concepts, Designs and Plans represented by this document are the property of the KESSLER DESIGN GROUP and are for the use on the project specified in this document

Copyright 2008 by KESSLER DESIGN GROUP ALL RIGHTS RESERVED

THE KESSLER DESIGN GROUP

300 NATIONAL ROAD
PO BOX 1785
ZANESVILLE, OHIO 43701-1785
740-450-1470

Presell Board

Everbrite
Identity Systems Division



Illumination:	(2) F60T12 CW/HO
Electrical:	1.82 amps @120V 60 Hz
Ballast:	Fulham Workhorse 7
Ship Weight:	200 lbs.
Other:	

11320-00366

5421 New Albany Road, W.



ALUMINUM SHROUD COVER

NEW ALUMINUM SHROUD COVER FOR MENU BOARD

11320-00366
5421 New Albany Road, W.

Client	McDonalds
Location	New Albany Market
Client Approval	

Saved as "McDonalds_New_Albany_Market"

Total Area	Design No.
Circuits	Date 5/13/11
Voltage	Drawn by Jared
Scale ½" = 1'	Salesman Rodger

All Concepts, Designs and Plans represented by this document are the property of the KESSLER DESIGN GROUP and are for the use on the project specified in this document.

Copyright 2008 by
KESSLER DESIGN GROUP
ALL RIGHTS RESERVED

THE KESSLER DESIGN GROUP
2669 NATIONAL ROAD
P.O. BOX 0785
ZANESVILLE, OHIO 43701-0785
1-800-686-1870

Graphics Plan

11320-00366

5421 New Albany Road, W.



Williams Shepherd Architects

McDONALD'S NEW ALBANY ROAD WEST, NEW ALBANY, OHIO

Mayor Michael B. Coleman

GRAPHICS COMMISSION APPLICATION

City of Columbus, Ohio • Department of Building & Zoning Services
757 Carolyn Avenue, Columbus, Ohio 43224 • Phone: 614-645-7433• www.columbus.gov

PROJECT DISCLOSURE STATEMENT

Parties having a 5% or more interest in the project that is the subject of this application.
THIS PAGE MUST BE FILLED OUT COMPLETELY AND NOTARIZED. Do no'

APPLICATION **11320-00366**
5421 New Albany Road, W.

STATE OF OHIO
COUNTY OF ~~FRANKLIN~~ Muskingum

Being first duly cautioned and sworn (NAME) Rodger Kessler
Of (COMPLETE ADDRESS) 2269 National Rd Zanesville OH 43702 (PO Box 785)
deposes and states that (he/she) is the APPLICANT, AGENT OR DULY AUTHORIZED ATTORNEY FOR SAME and the following is a list of all persons, other partnerships, corporations or entities having a 5% or more interest in the project which is the subject of this application and their mailing addresses:

NAME	COMPLETE MAILING ADDRESS
McDonald's Corporation	2 Easton Oval, Ste 200, Columbus, OH 43219
New Albany Company	5906 E. Dublin Granville Rd., New Albany, OH 43054

SIGNATURE OF AFFIANT Rodger Kessler

Subscribed to me in my presence and before me this 7th day of July, in the year 2011

SIGNATURE OF NOTARY PUBLIC Jessica J Grant

My Commission Expires: 7-18-2012

Notary Seal Here

NOTARIAL SEAL
STATE OF OHIO

JESSICA GRANT
Notary Public, State of Ohio
My Commission Expires 7/18/2012