

City of Columbus

Department of Public Service
Division of Design and Construction

Capital Improvement Plan (CIP) Sample Plan Sheets



CITY OF COLUMBUS, OHIO DEPARTMENT OF PUBLIC SERVICE DIVISION OF DESIGN AND CONSTRUCTION

IMPROVEMENTS OF NAME OF ROAD/STREET

FROM A REFERENCE POINT DESCRIPTION
TO A REFERENCE POINT DESCRIPTION
PROJECT DESIGNATION WHERE APPLICABLE

INDEX OF SHEETS (EXAMPLE BELOW)

TITLE SHEET	-----	#
SCHEMATIC PLAN	-----	#
TYPICAL SECTIONS	-----	#
GENERAL NOTES	-----	#
MAINTENANCE OF TRAFFIC (NOTES AND PLAN DETAILS)	-----	#
GENERAL SUMMARY	-----	#
CALCULATIONS	-----	#
STORM WATER POLLUTION PREVENTION PLAN	-----	#
*PLAN AND PROFILE (INCLUDING SUB-SUMMARIES)	-----	#
CROSS SECTIONS	-----	#
DETAILS	-----	#
STORM SEWER PROFILES & COORDINATE DATA	-----	#
WATERLINE PROFILES & COORDINATE DATA	-----	#
PAVEMENT MARKING AND SIGNING	-----	#
TRAFFIC SIGNAL AND TRAFFIC SIGNAL INTERCONNECT	-----	#
LIGHTING	-----	#
LANDSCAPING	-----	#
STRUCTURES	-----	#
RIGHT-OF-WAY	-----	#

Submittal Date:
May 6, 2008

PROJECT DESCRIPTION

NORTH ARROW
LOCATION



PLAN SCALE
REFERENCE




2002 SPECIFICATIONS

THE CITY OF COLUMBUS CONSTRUCTION AND MATERIALS SPECIFICATIONS, 2002 EDITION INCLUDING ALL SUPPLEMENTS THERETO, SHALL GOVERN ALL CONSTRUCTION ITEMS THAT ARE A PART OF THIS PLAN UNLESS NOTED OTHERWISE.

CITY OF COLUMBUS APPROVALS

CITY OF COLUMBUS SIGNATURES ON THIS PLAN SIGNIFY ONLY CONCURRENCE WITH THE GENERAL PURPOSES AND GENERAL LOCATION OF THE PROJECT. ALL TECHNICAL DETAILS REMAIN THE RESPONSIBILITY OF THE ENGINEER PREPARING THE PLANS.

DESIGN SECTION ENGINEER, DIVISION OF DESIGN AND CONSTRUCTION	DATE
ADMINISTRATOR, DIVISION OF POWER AND WATER	DATE
ADMINISTRATOR, DIVISION OF SEWERAGE AND DRAINAGE	DATE
DIRECTOR, DEPARTMENT OF PUBLIC UTILITIES	DATE
FIRE PREVENTION BUREAU, DIVISION OF FIRE	DATE
ENGINEERING SUPERVISOR, DEPARTMENT OF TECHNOLOGY	DATE
DIRECTOR, DEPARTMENT OF RECREATION AND PARKS	DATE
CITY ENGINEER/ADMINISTRATOR, DIVISION OF DESIGN AND CONSTRUCTION	DATE
DIRECTOR, DEPARTMENT OF PUBLIC SERVICE	DATE



LOCATION MAP

P.O.B. = LATITUDE: 40° 06' 54" N LONGITUDE: 82° 59' 34" W
SCALE IN MILES



PORTION/S TO BE IMPROVED: _____

DESIGN DESIGNATION DATA (WHEN APPLICABLE)

- CURRENT ADT (2000).....
- DESIGN YEAR ADT (2020).....
- DESIGN HOURLY VOLUME (2020).....
- DIRECTIONAL DISTRIBUTION.....
- TRUCKS (24 HOUR B&C).....
- DESIGN SPEED.....
- LEGAL SPEED.....
- DESIGN FUNCTIONAL CLASSIFICATION.....

DESIGN EXCEPTION.....

*NOTE: SUB-SUMMARIES SHOULD BE LOCATED ON OR IMMEDIATELY AFTER THE APPROPRIATE PLAN & PROFILE SHEET.

SHOW A COMPLETE LISTING OF ALL ANTICIPATED PLAN SECTIONS WITH EACH SUBMITTAL. IF THAT PLAN SECTION IS NOT INCLUDED WITH THE SUBMITTAL THEN LEAVE THE SHEET NUMBER BLANK.

CONSULTING ENGINEERING FIRMS NAME
AND/OR
LOGO

REGISTERED ENGINEER

DATE

ENGINEER'S
SEAL
AREA

ODOT STANDARD CONSTRUCTION DRAWINGS		SUPPLEMENTAL SPECIFICATIONS	
MT-97.10	TC-41.20	SS-1542	
MT-97.11	TC-42.20	SS-1550	
MT-105.10	TC-52.10	SS-1551	
MT-105.11	TC-52.20		
BP-3.1	TC-71.10		

CITY OF COLUMBUS STANDARD CONSTRUCTION DRAWINGS				
AA-S103	AA-S119	AA-S150	2160	L-8502
AA-S106	AA-S125	AA-S151	2166	L-7102
AA-S107	AA-S128	AA-S152	2201	
AA-S108	AA-S133	AA-S165	2202	
AA-S111	AA-S138	1441	2161	
AA-S113	AA-S139	2010	2180	

REF NO	REVISION DESCRIPTION	SHEET OR SHEETS	INITIAL	DATE



Drawer Number to be placed on every plan sheet.
Assigned by City of Columbus
Division of Design and Construction
Text height = 0.24"
Style = Arial (Bold)

Either for Page Numbering Style

1
74

XXXX - E

PROJECT NAME

TITLE SHEET / PLAN SHEET TITLE & STATION LIMITS


PID NUMBER

INSIDE BORDER

OUTSIDE EDGE OF SHEET



HORIZ. SCALE



CALCULATED

CHECKED

SCHEMATIC PLAN

PROJECT NAME

XXXX-XX

EX. P.I. STA = 147+77.72
D = 0° 47' 20" (LT)
NO CURVE

BEGIN PROJECT
STA. 148+60.00
BEGIN WORK
STA. 148+60.00

STREET NO. 4
CURVE DATA
P.I. STA = 1+92.28
D = 42° 50' 17" (RT)
Dc = 45° 50' 12"
R = 125.00'
T = 49.03'
L = 93.46'
E = 9.27'




EX. CURVE DATA
STREET NO. 2
P.I. STA = 1+02.62
D = 45° 54' 39" (RT)
Dc = 30° 09' 20"
R = 190.00'
T = 80.48'
L = 152.25'
E = 16.34'

BENCHMARKS
ALL ELEVATIONS ARE BASED ON NAVD88 (USGS) DATUM

SOURCE B.M. 42-73 BRASS DISK SET IN CONCRETE ON THE NE BRIDGE ABUTMENT OF ROAD NO. 1 WESTBOUND, 166' EAST OF THE INTERSECTION OF XXXX AVE AND XXXX STREET. ELEV. = 837.43

T.B.M. #1: CHISELED SQUARE ON SW CORNER OF CONCRETE BASE OF LIGHT POLE. STA. 157+75 20.15' RT ELEV. = 839.19

T.B.M. #2: SOUTH BOLT OF FIRE HYDRANT, EAST OF STREET NO. 5, N SIDE OF ROAD NO. 1 STA. 181+56 7.86' LT ELEV. = 838.95




I.P.S. = IRON PIN SET
I.P.F. = IRON PIN FOUND
M.S. = MAG SET
ALL CL POINTS ARE I.P.S.

ROAD NO. 1 CURVE DATA
P.I. STA = 190+41.11
D = 41° 51' 42" (LT)
Dc = 4° 59' 23"
R = 1,148.29'
Ls = 393.70'
Theta = 9° 49' 20"
LT = 262.87'
ST = 131.60'
x = 392.55'
y = 22.45'
k = 196.66'
p = 5.62'
Dc = 22° 13' 03" (LT)
Lc = 445.27'
Ts = 638.01'
Es = 87.14'
emax = 0.060


END PROJECT
STA. 191+73.81
END WORK
STA. 191+73.81

XXXX-E


REVISED 12/2/11




TYPICAL SECTION - STREET NAME 1
Sta. 133+90.00 to Sta. 135+13.48
Not to Scale




TYPICAL SECTION - STREET NAME 1
Sta. 135+13.48 to Sta. 150+01.52
Not to Scale



STRAIGHT 18" CONCRETE CURB W/UNDERDRAIN (STD DWG 2000)
Not to Scale




EXISTING PAVEMENT COMPOSITION
STREET NAME 1
Sta. 118+00 to Sta. 125+00
Not to Scale




EXISTING PAVEMENT COMPOSITION
STREET NAME 1
Sta. 133+00 to Sta. 139+50
Not to Scale

- LEGEND**
- * ① Item XXX - 1 1/2" Asphalt Concrete Surface Course
 - ② Item 407 - Tack Coat, Bituminous
 - * ③ Item XXX (Item 402) - 1 1/2" Asphalt Concrete Intermediate Course
 - ④ Item 407 - Tack Coat Bituminous
 - ⑤ Item 305 - 8" Portland Cement Concrete Base
 - ⑥ Item 304 - 6" Aggregate Base
 - ⑦ Item 204 - Subgrade Compaction
 - ⑧ Item 609 - Straight 18" Concrete Curb
 - ⑨ Item 605 - 4" Pipe Underdrain
 - ⑩ Item 659 - Seeding and Mulching
 - ⑪ Item 653 - Topsoil Furnished & Placed
 - ⑫ Item 608 - 4" / 8" Concrete Walk
 - ⑬ Item XXX - 2 1/2" Asphalt Concrete
 - ⑭ Item 408 - Prime Coat, Bituminous
 - ⑮ Item 304 - 8" Aggregate Berm
 - ⑯ Item 408 - Prime Coat, Bituminous
 - ⑰ Item 409 - Seal Coat, Bituminous
 - ⑱ Item 254 - Pavement Planning, (Varies-1-1/2" Typ.)
 - ⑲ Item 617 - Compacted Aggregate, Type A, As Per Plan

* Note to Consultant: Refer to City of Columbus Pavement Design Policies and Standard Drawings for pavement design.



TYPICAL SECTION - STREET NAME 1
Sta. 155+02.29 to Sta. 155+79.84
Not to Scale



TYPICAL SECTION - STREET NAME 1
Sta. 155+79.84 to Sta. 161+87.51
Not to Scale

CALCULATED
CHECKED





TYPICAL SECTIONS & DETAILS

PROJECT NAME

X
XX


LEGEND

- ① Item XXX - 1 1/2" Asphalt Concrete Surface Course
- ② Item 407 - Tack Coat, Bituminous (0.10 Gal./Sq. Yd.)
- ③ Item XXX - 1 1/2" Asphalt Concrete Intermediate Course
- ④ Item 407 - Tack Coat, Rubber
- ⑤ Item 305 - 8" Portland Cement Concrete Base
- ⑥ Item 304 - 6" Aggregate Base
- ⑦ Item 204 - Subgrade Compaction
- ⑧ Item 609 - Straight 18" Concrete Curb
- ⑨ Item 605 - 4" Pipe Underdrain
- ⑩ Item 659 - Seeding and Mulching
- ⑪ Item 653 - Topsoil Furnished & Placed
- ⑫ Item 304 - 8" Aggregate Berm
- ⑬ Item 408 - Prime Coat, Bituminous
- ⑭ Item 409 - Seal Coat, Bituminous and Cover Aggregate
- ⑮ Item 254 - Pavement Planing, (Varies 1 1/2" Typ.)
- ⑯ Item 609 - Curb and Gutter
- ⑰ Item 608 - 4" Concrete Walk
- ⑱ Item 202 - Remove Existing Curb and Gutter
- Ⓐ Existing Pavement



Note: Existing pavement composition is based on limited field information. No additional payment shall be made for removal if thickness or composition of pavement differs from that shown.


* Note to Consultant: Refer to City of Columbus Pavement Design Policies and Standard Drawings for pavement design.



Note A:
Existing Pavement Edge to be Sawcut as Required to Provide a Smooth Clean Edge as Directed by the Engineer. (Maintain 2'-0" Min. Widening Section)

Note B:
At Sections Requiring Removal of Existing Curb, Sawcut to Maintain a Smooth Clean Edge as Directed by the Engineer. (Maintain 2'-0" Min. Widening Section)

Note C:
Mill Existing Asphalt Pavement along the Existing Curb & Gutter to Provide a Minimum of 1 1/2" Depth for the Final Overlay Section.



CALCULATED
CHECKED

TYPICAL SECTIONS

PROJECT NAME

X
XX

XXXX-E

**SECTION 1- GENERAL NOTES
REQUIRED FOR CIP PLANS**

1.0 REFERENCE SPECIFICATIONS-

THE CITY OF COLUMBUS CONSTRUCTION AND MATERIALS SPECIFICATIONS 2002, (CMSC), INCLUDING ALL SUPPLEMENTS THERETO, SHALL GOVERN ALL CONSTRUCTION ITEMS THAT ARE A PART OF THE PLANS UNLESS NOTED OTHERWISE.

1.2 PRE-CONSTRUCTION NOTIFICATIONS REQUIRED-

CONTRACTOR SHALL NOTIFY THE FOLLOWING DIVISIONS AT LEAST 24 HOURS BEFORE STARTING WORK: CITY OF COLUMBUS DIVISION OF DESIGN AND CONSTRUCTION @ (614) 645-3182, CITY OF COLUMBUS DIVISION OF PLANNING AND OPERATIONS - OPERATIONS SECTION @ (614) 645-7738, DIVISION OF POWER AND WATER (WATER) @ (614) 645-7677, SEWERAGE AND DRAINAGE @ (614) 645-7102, RECREATION AND PARKS @ (614) 645-7665, AND 48 HOUR NOTICE WILL BE GIVEN TO THE DIVISION OF POWER AND WATER (POWER) @ (614) 645-7627.

1.3 PERMITS-

WHEN EXCAVATING WITHIN COLUMBUS PUBLIC RIGHT OF WAY LIMITS, THE CONTRACTOR SHALL OBTAIN AN EXCAVATION PERMIT FROM CITY OF COLUMBUS, DIVISION OF PLANNING AND OPERATIONS - PERMIT OFFICE, BY CALLING (614) 645-3039 BETWEEN THE HOURS OF 8:00AM AND 4:00PM MONDAY - FRIDAY.

1.4 UTILITIES-

THE IDENTITY AND LOCATION OF EXISTING UNDERGROUND UTILITIES LOCATED IN AND AROUND THE CONSTRUCTION AREA HAVE BEEN SHOWN AND LABELED ON THE PLANS BY USING INFORMATION PROVIDED BY THE RESPECTIVE UTILITY OWNERS. THE CITY OF COLUMBUS OR THE CONSULTING ENGINEER WILL NOT ASSUME RESPONSIBILITY FOR THE ACCURACY OF LOCATION OR DEPTH OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THE PLAN.

SUPPORT AND PROTECTION OF ALL UTILITIES AND APPURTENANCES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. COSTS FOR THE REPAIR AND RESTORATION OF EXISTING UTILITIES DAMAGED BY THE CONTRACTOR SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CITY OF COLUMBUS UTILITIES WILL ONLY LOCATE AND MARK MAIN LINE FACILITIES. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL SERVICE LATERAL AND LINES. COSTS ASSOCIATED WITH THE ABOVE WORK AND RESPONSIBILITIES SHALL BE INCLUDED IN THE PRICE BID FOR VARIOUS ITEMS.

PRIOR TO EXCAVATION, THE CONTRACTOR SHALL GIVE A 48-HOUR NOTICE TO THE OHIO UTILITIES PROTECTION SERVICE (OUPS) BY CALLING (800) 362-2764. A 48-HOUR NOTICE SHALL BE GIVEN TO THE OWNERS OF UNDERGROUND UTILITIES SHOWN ON THE PLANS WHO ARE NOT MEMBERS OF A REGISTERED UNDERGROUND PROTECTION SERVICE.

LISTED BELOW ARE UTILITY COMPANIES THAT HAVE FACILITIES LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT AND SUBSCRIBE TO OUPS.

*******CONSULTANT:** PLEASE LIST THE NAMES, ADDRESSES, AND PHONE NUMBERS OF THE UTILITY COMPANIES WITH FACILITIES LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT AND SUBSCRIBE TO OUPS.*****

THE FOLLOWING CITY OF COLUMBUS UTILITIES MAY BE LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT AND DO NOT SUBSCRIBE TO A REGISTERED UNDERGROUND PROTECTION SERVICE:

CITY OF COLUMBUS DEPARTMENT OF TECHNOLOGY 90 W. BROAD ST. COLUMBUS, OH 43215 TELEPHONE- (614) 645-1501 FAX- (614) 645-6627	DIVISION OF PLANNING AND OPERATIONS TRAFFIC MAINTENANCE 1820 17TH AVE. COLUMBUS, OH 43219 TELEPHONE- (614) 645-7393 FAX- (614) 645-5967
-------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------

CITY OF COLUMBUS
COMMUNICATIONS DIVISION
220 GREENLAWN AVE.
COLUMBUS, OH 43223
TELEPHONE- (614) 645-7334 EXT. 125
FAX- (614) 645-6588

1.5 EMERGENCY PROVISIONS-

THE CONTRACTOR SHALL PROVIDE TO THE CITY OF COLUMBUS PROJECT REPRESENTATIVE A LIST OF 24 HOUR EMERGENCY TELEPHONE NUMBERS (IN WRITING) PRIOR TO THE START OF CONSTRUCTION.

1.6 SECURING EXCAVATIONS & TRENCHES FOR NON-WORKING HOURS-

EXCAVATIONS AND TRENCHES OVER 24 INCHES DEEP SHALL BE SECURELY PLATED OR BACKFILLED DURING NON-WORKING HOURS.

1.7 WORK LIMITS-

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. THE INSTALLATION AND OPERATION OF ALL TEMPORARY TRAFFIC CONTROL AND TEMPORARY TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS SHALL BE PROVIDED BY THE CONTRACTOR WHETHER INSIDE OR OUTSIDE OF THESE WORK LIMITS.

1.8 MISCELLANEOUS WORK ITEMS-

THE CONTRACTOR SHALL PERFORM ALL ITEMS OF WORK CALLED FOR ON THE PLANS, FOR WHICH NO SPECIFIC METHOD OF PAYMENT IS PROVIDED. THE COST OF THESE ITEMS SHALL BE INCLUDED IN THE VARIOUS UNIT PRICES BID FOR THE PROJECT IMPROVEMENT.

1.9 BENCHMARKS AND SURVEY MONUMENTS-

DO NOT DISTURB ANY FRANKLIN COUNTY CERTIFIED BENCHMARKS (VERTICAL AND/OR HORIZONTAL) LOCATED WITHIN THE WORKING LIMITS OF THE PROJECT. CONTRACTOR SHALL CONTACT THE FRANKLIN COUNTY SURVEY DEPARTMENT (614) 462-3026, PRIOR TO CONSTRUCTION, TO COORDINATE THE PROPER PROCEDURES FOR THE RESETTING, RELOCATION, OR REPLACEMENT OF ANY FRANKLIN COUNTY CERTIFIED BENCHMARK OR SURVEY MONUMENT.

**SECTION 2 - GENERAL NOTES
INCLUDE 'IF APPLICABLE' FOR CIP PLANS**

2.0 PRE-CONSTRUCTION CONFERENCE-

THE CONTRACTOR IS TO NOTIFY THE CITY OF COLUMBUS DESIGN AND CONSTRUCTION DIVISION- CONSTRUCTION @ (614) 645-3182 TO ARRANGE A DATE AND TIME FOR PRE-CONSTRUCTION CONFERENCE. NO WORK SHALL START PRIOR TO THIS MEETING. THE DIVISION PROJECT ENGINEER SHALL AUTHORIZE A START DATE.

2.1 SAW CUTTING IS INCLUDED-

THE COST OF SAW CUTTING FOR THE REMOVAL OF PAVEMENT, CURB, WALKS, ETC. SHALL BE INCLUDED IN THE CONTRACT PRICE FOR ITEM 202 WORK ITEMS. SAW CUTTING IS REQUIRED TO PROVIDE SMOOTH STRAIGHT EDGES FOR REMOVAL PURPOSES.

2.2 NEW CURB RADIUS-

INTERSECTION CORNERS OR HORIZONTAL CURVES SHALL MATCH THE EXISTING RADIUS UNLESS NOTED OTHER WISE.

2.3 COTA- SIGNS AND/OR BUS STOPS-

PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL CONTACT SENIOR SERVICE PLANNER OF THE CENTRAL OHIO TRANSIT AUTHORITY (COTA) @ PH- (614) 308-4373 OR FAX- (614) 275-5933 TO COORDINATE PROPER BUS MOVEMENTS THROUGH OR AROUND THE JOB SITE DURING THE PROJECT. THIS WILL INCLUDE, BUT NOT BE LIMITED TO, THE TEMPORARY RELOCATION OR REMOVAL OF COTA SIGNS AND/OR BUS STOP LOCATIONS.

2.4 COTA- BUS SHELTERS/PADS-

THE CONTRACTOR SHALL NOTIFY SENIOR SERVICE PLANNER OF COTA @ PH- (614) 308-4373 OR FAX- (614) 275-5933 A MINIMUM OF TWO WEEKS PRIOR TO THE REQUIRED REMOVAL OF A BUS SHELTER. COTA WILL DISASSEMBLE THE SHELTER AND THEN REINSTALL IT ONCE THE NEW CONCRETE SLAB IS IN PLACE. CONTRACTOR SHALL CONSTRUCT THE SLAB AS DIRECTED BY THE PLANS OR OTHER CONTRACT DOCUMENTS. ALL CONCRETE SLAB WORK SHALL BE PAID AS PER ITEM SPECIAL, REMOVE AND REPLACE BUS SHELTER SLAB, WITH THE CONTRACT UNIT PRICE PER EACH. THIS PAY ITEM SHALL INCLUDE ALL EXCAVATION AND REMOVAL WORK, EXPANSION JOINT MATERIAL, ITEM 608 - 6" CONCRETE WALK, AND ANY OTHER WORK AS REQUIRED OR DIRECTED BY THE ENGINEER.

2.5 GAS SERVICE VALVES ADJUSTED TO GRADE-

THE CONTRACTOR SHALL CONTACT COLUMBIA GAS (614) 460-2244 TO COORDINATE THE ADJUSTMENT OF GAS SERVICE VALVES.

2.6 COLUMBIA GAS DAMAGE PREVENTION CENTER-

FOR INFORMATION CONCERNING COLUMBIA GAS LINES OR EQUIPMENT, OR IF DAMAGE OCCURS TO GAS LINES OR EQUIPMENT, THE CONTRACTOR CAN CALL THE COLUMBIA GAS DAMAGE PREVENTION CENTER @ (614) 280-7372 OR TOLL FREE @ (866) 632-6243.

2.7 NEW PIPE CONNECTION TO AN EXISTING SEWER STRUCTURE-

WHERE THE PLANS PROVIDE FOR NEW PIPE TO BE CONNECTED TO AN EXISTING SEWER/STRUCTURE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CREATING AN OPENING AT THE PROPER SIZE, ALIGNMENT, AND ELEVATION FOR THE CONNECTION. THE OPENING SHALL BE MADE LARGE ENOUGH TO RECEIVE AND JOIN THE PROPOSED PIPE PER CMSC ITEM 604.

NO DIRECT PAYMENT SHALL BE MADE. ALL COSTS ASSOCIATED WITH THIS WORK SHALL BE INCLUDED IN THE UNIT PRICE FOR ITEM 901- PIPE WITH TYPE _ BEDDING.

2.8 CONTINGENCY QUANTITIES-

THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK SHOWN, LABELED, OR LISTED AS 'CONTINGENCY' OR REFERENCED BY PLAN NOTE TO BE USED 'AS DIRECTED BY THE ENGINEER,' UNLESS AUTHORIZED BY THE ENGINEER, OR A REPRESENTATIVE OF THE CITY OF COLUMBUS, DIVISION OF DESIGN AND CONSTRUCTION.

2.9 CONCRETE WALKS-

ALL EXISTING CONCRETE SIDEWALKS BEING REPLACED WITH NEW CONCRETE SIDEWALKS SHALL BE REMOVED AT AN EXISTING JOINT AND REPLACED PER STANDARD DRAWING 2300. INSTALL EXPANSION JOINT WHERE NEW CONCRETE ADJOINS EXISTING SIDEWALK.

ALL EXISTING CONCRETE SIDEWALKS NOT SCHEDULED FOR REPLACEMENT BUT BEING CROSSED BY THE INSTALLATION OF TRAFFIC ITEMS, ELECTRICAL CONDUIT, PIPING, ETC. SHALL BE FULLY REMOVED AT AN EXISTING JOINT AND REPLACED PER STANDARD DRAWING 2300 UNLESS NOTED OTHERWISE.

PAYMENT SHALL BE INCLUDED IN THE PRICE BID FOR ITEM 608- CONCRETE WALK.

**SECTION 3 -GENERAL NOTES
INCLUDE 'AS PER PLAN' ITEMS FOR CIP AS APPLICABLE**

AN 'AS PER PLAN' ITEM IS A STANDARD PAY ITEM WHOSE REQUIREMENTS NEED TO BE MODIFIED FROM THAT WHICH IS DEFINED IN THE CMSC OR SUPPLEMENTAL SPECIFICATIONS. EACH 'AS PER PLAN' ITEM SHALL HAVE A CORRESPONDING PLAN NOTE(S) OR PLAN DETAIL(S) OR COMBINATION. CLEARLY SPECIFY THE DEVIATIONS FROM THE STANDARD ITEM IF AN ITEM IS 'AS PER PLAN.' THE 'AS PER PLAN' TEXT SHALL BE INSERTED AT THE END OF THE ITEM DESCRIPTION.

EXAMPLES:

3.0 WALK REMOVED 'AS PER PLAN'

THE EXISTING SIDEWALK SHALL BE REMOVED IN ACCORDANCE WITH THE PROPOSED SIDEWALK DETAILS. REMOVAL SHALL BE IN CONFORMANCE WITH CMSC SECTION 202. REFERENCE THE PLANS FOR LOCATIONS. THICKNESS' OF EXISTING WALKS VARY FROM 4" TO 8". NO SEPARATE PAYMENT SHALL BE MADE FOR REMOVAL OF THE VARIOUS THICKNESS' OF THE WALKS ENCOUNTERED. ANY SAW CUTTING NECESSARY TO REMOVE SIDEWALKS SHALL BE INCLUDED. PAYMENT SHALL BE PER SQUARE FOOT AND SHALL INCLUDE ALL NECESSARY TOOLS, LABOR, AND MATERIALS.

3.1 PAVEMENT PLANING 'AS PER PLAN'

UNDER THIS ITEM, ASPHALT SHALL BE MILLED FROM DESIGNATED STREETS TO A MINIMUM 1" DEPTH (TYPICAL 1.5"), OR AS INDICATED WITHIN THESE PLANS. PLANING DEPTHS INDICATED MAY BE ADJUSTED IN THE FIELD AT THE ENGINEER'S DISCRETION. INCREASED OR DECREASED PAVEMENT PLANING THICKNESS SHALL BE PERFORMED AT NO ADDITIONAL COST. ALL STREET PLANING SHALL MAINTAIN THE EXISTING CROWN. IF THE CROWN IS REMOVED AS A RESULT OF THE CONTRACTOR'S ERROR OR WITHOUT THE ENGINEER'S PRIOR APPROVAL, NO ADDITIONAL ASPHALT ABOVE THE PLAN QUANTITY FOR EACH SHEET SHALL BE PAID.

THE CONTRACTOR SHALL LOCATE ALL EXISTING LOOP DETECTORS PRIOR TO PLANING. IN THE EVENT A LEAD-IN CABLE IS DAMAGED, THE CONTRACTOR SHALL REPAIR. NO SEPARATE PAYMENT SHALL BE MADE FOR LOOP DETECTOR REPAIRS.



CALCULATED
CHECKED

GENERAL NOTES

PROJECT NAME



SECTION - 4 GENERAL NOTES
INCLUDE 'ITEM SPECIAL' FOR CIP PLANS AS APPLICABLE

A 'SPECIAL' ITEM IS AN ITEM THAT DOES NOT EXIST IN THE STANDARD DRAWINGS, THE CMSC, OR SUPPLEMENTAL SPECIFICATIONS. IT SHALL BE CREATED BY MEANS OF CORRESPONDING PLAN NOTES, PLAN DETAILS, OR A COMBINATION THEREOF WHICH CLEARLY SPECIFIES ALL ASPECTS OF THE ITEM. IF AN ITEM IS A 'SPECIAL' THE WORD 'SPECIAL' SHALL BE INSERTED IN THE ITEM COLUMN.

EXAMPLES:

4.0 STONE CURB TO BE REMOVED AND SALVAGED

THE CONTRACTOR SHALL REMOVE, SALVAGE, AND DELIVER TO THE CITY OF COLUMBUS THE STONE (SANDSTONE, GRANITE) CURBING FROM THE EXISTING STREETS AS DIRECTED BY THE PLAN. THE CURB SECTIONS SHOWN ON THE PLANS TO BE SALVAGED SHALL BE CAREFULLY REMOVED WITHOUT NECESSARY DAMAGE AND CLEANED FOR RE-USE. STRAIGHT CURB SECTIONS TO BE SALVAGED SHALL BE AT LEAST FOUR FEET IN LENGTH. CURVED SECTIONS OF ANY LENGTH SHALL BE SALVAGED. ALL CLEANED CURB SECTIONS SHALL BE STACKED (NO MORE THAN FOUR HIGH) AND SECURELY FASTENED OR BOXED ONTO PALLETS.

WHEN THE CURBING HAS BEEN SECURED ONTO PALLETS, THE CONTRACTOR SHALL TRANSPORT IT TO THE CITY OF COLUMBUS, DIVISION OF PLANNING AND OPERATIONS - 25TH AVE. STREET MAINTENANCE YARD. THE CONTRACTOR SHALL CALL THE MAINTENANCE YARD MANAGER @ (614) 645-8120 AT LEAST TWO WEEKS IN ADVANCE TO MAKE ARRANGEMENTS FOR DELIVERY. PAYMENT FOR THIS WORK SHALL BE MADE AFTER THE CURBING HAS BEEN DELIVERED TO THE 25TH AVE MAINTENANCE YARD.

THE COST FOR ALL WORK REQUIRED TO REMOVE, CLEAN, SALVAGE, AND DELIVER CURBING SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM SPECIAL - CURB REMOVED FOR STORAGE - L.F.

4.1 ASPHALT CONCRETE PATCHING

THIS ITEM IS TO BE USED AS DIRECTED BY THE ENGINEER, WHEREVER AND WHENEVER IT BECOMES NECESSARY, IN THE OPINION OF THE ENGINEER, TO ALLEVIATE HAZARDOUS SITUATIONS, SUCH AS MANHOLE CASTINGS, VALVE CASTINGS, AND OTHER HAZARDOUS CONDITIONS THAT MAY EXIST. EACH SEPARATE AND DISTINCT AREA WHICH REQUIRES THIS ITEM WILL BE PAID AS ITEM SPECIAL - ASPHALT CONCRETE PATCHING.

4.2 BRICK PAVERS, COMPLETE

ALL BRICK PAVERS SHALL BE SOLID CONCRETE PAVING UNITS CONFORMING TO ASTM C936.

CONCRETE BASE

ALL WORK FOR THE CONCRETE BASE SHALL CONFORM TO ITEM 608, EXCEPT THE 608 REQUIREMENTS FOR EDGING OUTSIDE EDGES AND CONTROL JOINTS AT FIVE FOOT INTERVALS SHALL BE WAIVED.

NEOPRENE MODIFIED ASPHALT ADHESIVE

FURNISH NEOPRENE - MODIFIED ASPHALT ADHESIVE THAT CONTAINS TWO PERCENT NEOPRENE, GRADE WMI, OXIDIZED ASPHALT WITH A 150 DEGREE SOFTENING POINT (77 PENETRATION), AND 10 PERCENT LONG FIBERIZED INERT MATERIAL AS SUPPLIED BY BELOW (OR APPROVED EQUAL):

SEIDEL COMPANY INC.
 11 MARKET SQUARE
 NEWBURYPORT, MA 01950
 (614) 649-6740

HASTINGS PAVEMENT CO., INC.
 410 LAKEVILLE RD
 LAKE SUCCESS, NY 11042
 (516) 379-3500

BITUMINOUS SETTING BED

FURNISH ASPHALT CEMENT CONFORMING TO ASTM D3381, VISCOSITY GRADE AC-10 OR AC-20. FURNISH FINE AGGREGATE OF NATURAL SAND AND/OR STONE SAND, COMPOSED OF HARD, TOUGH, DURABLE, UNCOATED PARTICLES, FREE FROM CLAY, SILT, ORGANIC MATERIAL OR OTHER DELETERIOUS SUBSTANCES. ENSURE THE SAND IS UNIFORMLY GRADED WITH ALL MATERIAL PASSING THE NO. 4 SIEVE AND MEETING THE REQUIREMENTS OF ASTM C136. COMBINE THE DRIED FINE AGGREGATE WITH HOT ASPHALT CEMENT AND MIX, HEAT TO APPROXIMATELY 300 DEGREES FAHRENHEIT AT AN ASPHALT PLANT. PROVIDE AN APPROXIMATE PORTION OF MATERIALS OF SEVEN PERCENT ASPHALT CEMENT AND 93 PERCENT FINE AGGREGATE. PROVIDE EACH TO APPORTION BY WEIGHT TO 140 POUNDS OF ASPHALT CEMENT AND 1860 POUNDS OF FINE AGGREGATE. PAYMENT FOR ALL LABOR, EQUIPMENT, AND MATERIALS NECESSARY TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM SPECIAL - BRICK PAVER COMPLETE - S.F.

SECTION 5 - GENERAL NOTES
INCLUDE PROJECT SPECIFIC NOTES FOR CIP PLANS AS APPLICABLE

A PROJECT SPECIFIC NOTE IS A 'CUSTOM' NOTE THAT IS UNIQUE TO EACH INDIVIDUAL PLAN. IT IS TYPICALLY USED TO CONVEY INFORMATION AND/OR DETAIL CONCERNING WORK ASSOCIATED WITH THE PROJECT.

EXAMPLE:

5.0 SOILS INVESTIGATION

GEOTECHNICAL REPORTS HAVE BEEN PREPARED FOR THIS PROJECT. COPIES OF THESE REPORTS MAY BE OBTAINED FROM THE DIVISION OF DESIGN AND CONSTRUCTION.

SECTION 6 - GENERAL NOTES
INCLUDE DEPARTMENT / AGENCY NOTES FOR CIP PLANS AS APPLICABLE

EXAMPLE:

6.0 DIVISION OF POWER AND WATER (DOPW) (P)

DIVISION OF POWER AND WATER (P) MAY HAVE UNDERGROUND STREET LIGHTING IN THE PROJECT AREA. THE CONTRACTOR IS REQUIRED TO CONTACT OUPS PRIOR TO CONDUCTING ACTIVITY WITHIN THE CONSTRUCTION AREA. THE DOPW (P) DISPATCH OFFICE NUMBER IS (614) 645-7627.

LEGEND

EXISTING CONDITIONS

-----	CENTERLINE SURVEY	-----	CONC. WALL
-----	CENTERLINE EXIST. DRIVE	-----	STONE WALL
=====	EDGE OF PAVEMENT	-----	ROCK
=====	CURB	-----	TREELINE
-----	BERM	-----	TREES
-----	EDGE OF ASPHALT DRIVE/PARKING LOT	-----	BUSHES
-----	EDGE OF GRAVEL DRIVE/PARKING LOT	-----	HEDGE/SHRUB
-----	CONC. WALK	-----	STUMP
-----	BRICK WALK/DRIVE	-----	CONC. PAD
-----	FENCE	-----	WOOD POST
-----	GUARDRAIL	-----	POST/BOLLARD
-----	RIGHT-OF-WAY	-----	MAILBOX
-----	PROPERTY LINE	-----	FLAGPOLE
-----	LOT LINE (SAME OWNER BOTH SIDES)	-----	PARKING BLOCK
-----	RAILROAD RIGHT-OF-WAY	-----	SIGNS
-----	STORM (18" AND UNDER)	-----	BIRDBATH
-----	SANITARY	-----	HANDRAIL
-----	WATER	-----	STEPS
-----	GAS	-----	
-----	TELEPHONE (UNDERGROUND)	-----	
-----	ELECTRIC	-----	
-----	CATV	-----	
-----	BUILDING	-----	
-----	CANOPY	-----	

SURVEY SYMBOLS

⊙	IRON PIN FND./METAL BAR FND.	⊙	IRON ROD FND./RR SPIKE FND.
⊙	PK NAIL FND.	⊙	BENCHMARK
⊙	RIGHT-OF-WAY MON. FND.	⊙	SOIL BORING
⊙	PK NAIL SET/TRaverse DRILL HOLE	⊙	IRON PIN SET
⊙	MAG NAIL SET	⊙	RR SPIKE SET

ABBREVIATIONS

1"WS 1" WATER SERVICE	(PA).....PREVIOUSLY ABANDONED	(TBRL).....TO BE RELOCATED BY OTHERS
1"SS 1" SANITARY SERVICE	(ENC).....ENCROACHMENT TO REMAIN UNLESS OTHERWISE DIRECTED BY THE ENGINEER-IN-CHARGE	(REM).....REMOVE
1"GS 1" GAS SERVICE	(ENC-TBR).....ENCROACHMENT TO BE REMOVED BY THIS PROJECT	(REC).....RECONSTRUCT
1"RD 1" ROOF DRAIN	(DND).....DO NOT DISTURB	(REB).....REBUILD
OHE OVERHEAD ELECTRIC	(TBA).....TO BE ABANDONED (SEE NOTE BELOW)	(R&R).....REMOVE & REPLACE
OHT OVERHEAD TELEPHONE	(TBR).....TO BE REMOVED	(APP).....AS PER PLAN
UGT UNDERGROUND TELEPHONE	(TBRL).....TO BE RELOCATED BY THIS PROJECT	(ATG).....ADJUST TO GRADE
CATV.....CABLE TELEVISION	(TBR).....TO BE REMOVED (BY OTHERS)	(ATGO).....ADJUST TO GRADE BY OTHERS
	(TBRO).....TO BE REMOVED (BY OTHERS)	(RTG).....RECONSTRUCT TO GRADE
		(RTGO).....RECONSTRUCT TO GRADE BY OTHERS

NOTE: STORM SEWERS INDICATED (TBA) SHALL BE FILLED IN PLACE UNLESS OTHERWISE SHOWN.

PROPOSED LAYOUT

-----	CENTERLINE CONSTRUCTION	⊙	PROPOSED FIRE HYDRANT
-----	CENTERLINE PROP. DRIVE	⊙	WATER VALVE
=====	EDGE OF PAVEMENT	⊙	AIR RELEASE VALVE (WATER)
=====	BACK OF CURB	⊙	STM. MH
-----	FACE OF CURB	⊙	SAN. MH
-----	CONC. WALK/ASPH. BIKEPATH	⊙	CURB INLET
-----	RIGHT-OF-WAY	⊙	CATCH BASIN
-----	WORK LIMITS	⊙	STM. MH TYPE A W/CURB INLET TOP
-----	STORM (24" AND LARGER)	⊙	STM. MH TYPE B W/CURB INLET TOP
-----	STORM (18" AND SMALLER)	⊙	
-----	WATER	⊙	DETECTABLE WARNING

EXISTING UTILITY SYMBOLS

⊙	STM. MH	⊙	TEL. BOOTH	⊙	FIRE HYDRANT
⊙	STM. MH (OPEN GRATE)	⊙	ELEC. PULLBOX	⊙	GAS VALVE
⊙	CURB & GUTTER INLET	⊙	GROUND LIGHT	⊙	CATCH BASIN
⊙	CURB INLET	⊙	GUY ANCHOR	⊙	GAS METER
⊙	SAN. MH	⊙	TEL. MH	⊙	TEL. PEDESTAL
⊙	WATER VALVE	⊙	TEL. ELECTRIC POLE	⊙	ELECTRIC POLE
⊙	TELEPHONE POLE	⊙	TELEPHONE ELECTRIC POLE	⊙	LIGHT POLE
⊙	TELEPHONE LIGHT POLE	⊙		⊙	
⊙	TELEPHONE ELECTRIC LIGHT POLE	⊙		⊙	



CALCULATED
 CHECKED

GENERAL NOTES

PROJECT NAME

X
 XX

XXXX-E

A. TEMPORARY TRAFFIC CONTROL ITEMS

1. ALL TEMPORARY TRAFFIC CONTROL (TTC) DEVICES SHALL BE FURNISHED, ERECTED, MAINTAINED AND REMOVED BY THE CONTRACTOR IN ACCORDANCE WITH THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS. (OMUTCD), (CURRENT EDITION). COPIES ARE AVAILABLE FROM THE OHIO DEPARTMENT OF TRANSPORTATION, OFFICE OF CONTRACTS, 1980 WEST BROAD STREET, COLUMBUS, OHIO, 43216. **NOTE:** ALL DEVICES SHALL COMPLY, FOR CONDITION AND LOCATION, WITH THE CURRENT EDITION OF THE NCHRP 350 CRASH TESTING GUIDELINES.
2. CONSTRUCTION OPERATIONS SHALL **NOT** BEGIN UNTIL ALL TRAFFIC CONTROL IS IN PLACE AND APPROVED BY THE DIVISION OF DESIGN AND CONSTRUCTION INSPECTOR. IF THE CONTRACTOR DOES NOT COMPLY WITH THE STANDARDS, INCLUDING THE INSTALLATION OF TEMPORARY PAVEMENT MARKINGS AND THE REMOVAL OF CONFLICTING TRAFFIC CONTROLS, THEIR PERMIT SHALL BE REVOKED AND ALL WORK SHALL BE TERMINATED. TEMPORARY PAVEMENT MARKINGS TO INCLUDE, BUT NOT LIMITED TO, CHANNELIZING LINES, EDGE LINES, AND CENTERLINES SHALL BE INSTALLED AND MAINTAINED ON ALL CONSTRUCTION OPERATIONS LASTING A MINIMUM OF 14 CALENDAR DAYS OR AS DIRECTED BY THE TEMPORARY TRAFFIC CONTROL COORDINATOR OR THE PROJECT ENGINEER.
3. PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS) SHALL BE INSTALLED A MINIMUM OF 7 DAYS PRIOR TO THE CLOSURE OF A ROADWAY. THE MESSAGE SHALL ADVISE THE MOTORISTS OF THE DATES, TIMES, AND DURATION OF THE CLOSURE. THE PCMS SHALL REMAIN IN PLACE FOR 7 DAYS AFTER THE START OF THE CLOSURE.
4. THE CONTRACTOR SHALL GIVE ADVANCE NOTIFICATION (WRITTEN AND VERBALLY) TO THE TEMPORARY TRAFFIC CONTROL COORDINATOR AT 645-6269 OR 645 5845, THE COLUMBUS PAVING THE WAY PROGRAM COORDINATOR AT 645-7283 OR 645 6016, AND THE PROJECT ENGINEER, INFORMING THEM OF ALL UPCOMING MAINTENANCE OF TRAFFIC CHANGES ON A WEEKLY BASIS. NOTIFICATION SHALL INCLUDE, BUT NOT LIMITED TO, WHAT, WHERE, WHEN, AND HOW PEDESTRIAN AND VEHICULAR TRAFFIC WILL BE AFFECTED, AND THE TEMPORARY TRAFFIC CONTROL PROCEDURES THE CONTRACTOR IS PLANNING TO USE. THE TYPE OF TRAFFIC CHANGES SHALL DETERMINE THE LENGTH OF ADVANCE NOTIFICATION REQUIRED:

TYPE OF CHANGE	ADVANCE NOTIFICATION NEEDED
DETOURS / ROAD CLOSURES	30-DAY NOTIFICATION PRIOR TO CLOSURE
LANE CLOSURE LASTING TWO WEEKS OR MORE	2-WEEKS
LANE CLOSURES LESS THAN TWO WEEKS	3-DAYS
LANE CLOSURE OF TWO DAYS OR LESS	1-DAY
ANY OTHER UNFORESEEN IMPACTS TO TRAFFIC SHALL BE IMMEDIATELY REPORTED AS THEY OCCUR	
5. A TTC PLAN (TTCP) INCLUDING PEDESTRIAN CONTROL SHALL BE SUBMITTED TO THE TTC COORDINATOR AT 645-6269 OR 645-5845 AT THE PRE-CONSTRUCTION MEETING OR A MINIMUM OF TEN (10) WORKING DAYS PRIOR TO THE BEGINNING OF WORK. COPIES OF THE APPROVED TTCP SHALL BE GIVEN TO THE PROJECT ENGINEER AND KEPT ON SITE ALONG WITH THE STREET CLOSURE / OCCUPANCY PERMIT.
6. TYPE C STEADY-BURN OR TYPE D 360-DEGREE STEADY BURN WARNING LIGHTS SHALL BE REQUIRED ON ALL BARRICADES, DRUMS, AND SIMILAR TRAFFIC CONTROL DEVICES IN USE AT NIGHT. ONLY 42" REFLECTORIZED CHANNELIZING DEVICES (CONES) SHALL BE PERMITTED FOR NIGHTTIME WORK WITH THE APPROVAL OF THE TTC COORDINATOR AT 645-6269 OR 645-5845 PER ODOT STANDARDS.
7. A FLASHING ARROW PANEL (48" x 96"-TYPE C) SHALL BE USED IN LANE CLOSURES AS PER THE OHIO MANUAL (OMUTCD).
8. ALL TRENCHES WITHIN THE ROAD RIGHT OF WAY SHALL BE BACKFILLED OR SECURELY PLATED PER (CITY OF COLUMBUS GENERAL POLICY ON STEEL PLATE USAGE DATES 11/15/2006 AND 2007 STD. DWG. 1441) DURING NON-WORKING HOURS.
9. ACCESS FOR PEDESTRIAN AND VEHICULAR TRAFFIC TO ALL ADJOINING PROPERTIES SHALL BE MAINTAINED AT ALL TIMES.
10. ALL EXISTING TRAFFIC LANES SHALL BE OPEN TO TRAFFIC AT ALL TIMES ON: _____.
11. ALL TRAFFIC LANES SHALL BE FULLY OPEN TO TRAFFIC FROM 6:00 A.M. TO 9:00 A.M. AND 4:00 P.M. TO 6:00 P.M., OR 6:00 A.M. TO 9:00 A.M. AND 3:00 P.M. TO 6:00 P.M. IN THE COLUMBUS BUSINESS DISTRICT AREA, MONDAY THROUGH FRIDAY ON _____ LANE (S) MAY BE CLOSED TO TRAFFIC DURING WORKING HOURS.
12. ONE-WAY _____ LANE (S) OF TRAFFIC SHALL BE MAINTAINED AT ALL TIMES ON _____.
13. TWO-WAY TWO-LANE (ONE-LANE EACH DIRECTION) SHALL BE MAINTAINED AT ALL TIMES BY USE OF EXISTING, PROPOSED, OR TEMPORARY PAVEMENT PER FIGURE 6H-32 TYPICAL APPLICATION 32 (TA-32) OF THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
14. TWO-WAY ONE-LANE TRAFFIC MAY BE MAINTAIN DURING CONSTRUCTION OPERATIONS ON _____, PER FIGURE 6H-10 (TA-10) OF THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
15. _____ MAY BE CLOSED BETWEEN _____ AND _____ FOR A MAXIMUM OF _____ HOUR (S)/ DAY (S) BETWEEN THE HOURS OF _____ AND _____ PER FIGURE 6H-20 (TA-20) OF THE OMUTCD AND/OR APPROVED BY THE DIVISION OF DESIGN AND CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS IN PROVIDING A DETOUR INCLUDING THE REMOVAL AND REINSTALLATION OF ANY CONFLICTING TRAFFIC CONTROL AND/OR ANY NECESSARY TRAFFIC SIGNAL WORK.
16. A TEMPORARY DIVERSION SHALL BE PROVIDED AND MAINTAINED IN GOOD CONDITION ON _____ DURING THE PERIOD OF WORK. ALL SUCH DIVERSIONS SHALL BE IN ACCORDANCE WITH THE OMUTCD.
17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION AND SAFE MOVEMENT OF PEDESTRIAN THROUGH, AROUND, OR DETOURED AWAY FROM THE CONSTRUCTION SITE. TRAFFIC CONTROL FOR PEDESTRIAN MOVEMENT SHALL BE AS PER FIGURES 6H-28 (TA-28) AND 6H-29 (TA-29) OF PART VI OF THE OMUTCD. ALL SIDEWALK DIVERSIONS AND TEMPORARY MID-BLOCK CROSSINGS SHALL BE PRE-APPROVED BY THE PROJECT ENGINEER OR THE TEMPORARY TRAFFIC CONTROL COORDINATOR.
18. THE DIVISION OF PLANNING AND OPERATIONS WILL REMOVE OR COVER ALL PARKING METER HEADS PUT OUT OF SERVICE BY THIS CONTRACT. THERE IS A \$60.00 CHARGE FOR THE REMOVAL AND RE-INSTALLATION OF EACH METER. IN ADDITION, A DAILY METER FEE WILL BE CHARGED FOR ALL ENFORCEMENT HOURS FOR EACH METER TAKEN OUT OF SERVICE. THESE CHARGES WILL BE COLLECTED FROM THE CONTRACTOR IN ADVANCE WITH THE ISSUANCE OF THE STREET OCCUPANCY / EXCAVATION PERMIT FROM THE DIVISION OF PLANNING AND OPERATIONS' PERMIT OFFICE. (645-7497) THE MANAGER OF PARKING SERVICES SUPPORT (645-7890) SHALL BE NOTIFIED A MINIMUM OF FORTY-EIGHT (48) HOURS (EXCLUDING SAT. SUN., & HOLIDAYS) PRIOR TO THE BEGINNING OF WORK. CALL 645-8376 IF UNABLE TO MAKE CONTACT THROUGH THE PRIOR PHONE NUMBER.
19. TEMPORARY "EMERGENCY NO PARKING" SIGNS SHALL BE INSTALLED AT 50' INTERVALS C/C MINIMUM BY USE OF ANY OF THE FOLLOWING ITEMS: EXISTING SIGN POSTS, EXISTING UTILITY POLES, DRUMS AND/OR 42" CONES AND REMOVED BY THE CONTRACTOR IN AREAS WITH NO PARKING METERS. THE SIGNS SHALL HAVE THE INSTALLATION DATE, WORKING DATES, AND HOURS OF RESTRICTION SHOWN ON EACH SIGN. THESE SIGNS CAN BE OBTAINED FROM THE DIVISION OF PLANNING AND OPERATIONS' PERMIT OFFICE. THE POLICE DIVISION REQUIRES THE "EMERGENCY NO PARKING" SIGNS TO BE POSTED A MINIMUM OF SEVENTY-TWO (72) HOURS PRIOR TO ANY VEHICLES BEING TOWED. WITHIN TWENTY-FOUR (24) HOURS OF POSTING, THE CONTRACTOR SHALL SUPPLY THE DIVISION OF DESIGN AND CONSTRUCTION WITH A WRITTEN RECORD OF POSTED LOCATIONS (FAX 645-3298).
20. TRAFFIC OPERATIONS' PERSONNEL SHALL LOCATE AND MARK ALL UNDERGROUND TRAFFIC CONTROL CABLES. THE TRAFFIC OPERATIONS SHOP SHALL BE NOTIFIED 645-7393 (FAX 645-5967) AT LEAST FORTY-EIGHT (48) HOURS (EXCLUDING SATURDAY & SUNDAY) PRIOR TO THE BEGINNING OF ANY WORK WITH 450 FEET OF ANY SIGNALIZED INTERSECTION (S) OR WITHIN ANY POSTED AREA WHERE THE DIVISION HAS UNDERGROUND CABLE. THE SIGNAL OPERATION ENGINEER (645-6418) SHALL BE NOTIFIED SIX (6) WEEKS IN ADVANCE FOR SIGNAL REVISION OR POLE RELOCATIONS.
21. NO EXCAVATION SHALL BE MADE WITHIN FIVE (5) FEET OF ANY POLE THAT SUPPORTS TRAFFIC SIGNAL DISPLAYS OR SIGNS BY MAST ARMS OR SIGNAL SPAN. EXCAVATION WITHIN EIGHT (8) FEET, BUT MORE THAN FIVE (5) FEET SHALL REQUIRE ADDITIONAL SUPPORT (DOWN GUY, HEAD GUY, BASE GUY, ETC.). THE CONTRACTOR SHALL CONTACT SIGNAL OPERATION PERSONNEL AT 645-0423 (CELL 419-4501) AT LEAST FORTY-EIGHT (48) HOURS (EXCLUDING SATURDAY & SUNDAY) PRIOR TO BEGINNING OF SUCH EXCAVATION SO THAT THE CITY CAN APPROVE THE STABILIZATION SETUP BY THE CONTRACTOR. IF UNABLE TO MAKE CONTACT THROUGH ABOVE NUMBERS, CALL 645-7393. STABILIZATION WILL BE DONE BY THE CONTRACTOR AT THE OWNERS' / CONTRACTING AGENCY'S EXPENSE.
22. WHEN ANY TRAFFIC CONTROL DEVICE, CONDUIT, OR CABLE IS DAMAGED, THE CONTRACTOR SHALL NOTIFY SIGNAL OPERATION PERSONNEL AT 645-0423 (CELL 451-4501) BETWEEN 7:00 A.M. AND 4:00 P.M., MONDAY THROUGH FRIDAY. IF UNABLE TO MAKE CONTACT THROUGH THE OTHER NUMBERS, CALL 645-7393.
23. THE ROADWAY SHALL **NOT** BE OPENED TO NON-CONSTRUCTION TRAFFIC UNTIL THE CRITICAL PERMANENT TRAFFIC CONTROL ARE IN PLACE, OR UNTIL TEMPORARY TRAFFIC CONTROLS APPROVED BY THE ENGINEER, ARE INSTALLED. THE CRITICAL PERMANENT TRAFFIC CONTROL ARE **STOP, YIELD, ONE-WAY, DO NOT ENTER, AND RESTRICTED TURN SIGNS**. OTHER CRITICAL SIGNS MAY BE NOTED ON THE PLANS AS WELL. THE CONTRACTOR ASSUMES ALL LIABILITY FOR THE PREMATURE REMOVAL OF TEMPORARY TRAFFIC CONTROLS.
24. THE ROADWAY OR ANY SECTION OF ROADWAY SHALL NOT BE OPENED TO NON-CONSTRUCTION TRAFFIC UNTIL ALL TEMPORARY, NON-REFLECTIVE, BLACKOUT TAPE HAS BEEN COMPLETELY REMOVED FROM NON-CONFLICTING PERMANENT PAVEMENT MARKINGS FOR THAT AREA OF THE ROADWAY, OR UNLESS OTHERWISE DIRECTED IN WRITING BY THE ENGINEER. THIS IS SUPPLEMENTAL TO THE CMS-614.11F, AND SHALL BE PAID FOR THROUGH THE 614-LUMP SUM.

25. THE CONTRACTOR SHALL MAINTAIN ALL PERMANENT TRAFFIC CONTROLS NOT IN CONFLICT WITH THE TEMPORARY TRAFFIC CONTROLS THROUGHOUT THIS PROJECT. PERMANENT TRAFFIC CONTROLS MAY BE TEMPORARILY RELOCATED OR COVERED, AS APPROVED BY THE ENGINEER. THE CONTRACTOR SHALL ASSUME ALL LIABILITY FOR MISSING, DAMAGED, OR IMPROPERLY PLACED SIGNS.
26. ANY WORK DONE BY THE DIVISION OF PLANNING AND OPERATIONS, INCLUDING INSTALLATION, RELOCATION, REMOVAL AND/OR REPLACEMENT OF TEMPORARY TRAFFIC CONTROL DEVICES AS RESULT OF WORK DONE BY THE CONTRACTOR OR AS A RESULT OF NEGLIGENCE OF THE CONTRACTOR, SHALL BE AT THE CONTRACTORS' EXPENSE.
27. WHENEVER YELLOW CENTERLINES OR TURN-LANE LINE ARE PAVED OVER, REMOVED, OR OTHERWISE UNSERVICEABLE, THE CONTRACTOR SHALL INSTALL CLASS II TEMPORARY STRIPING (MINIMUM 4' LONG SEGMENTS). TEMPORARY PAINT SHALL BE USED ON ALL MILLED SURFACES. TEMPORARY TAPE SHALL BE USED ON ALL FINAL COURSES OF ASPHALT. PAINT OR TAPE MAY BE USED ON ALL INTERMEDIATE COURSES OF ASPHALT. IF APPROVED BY THE ENGINEER, DRUMS WITH STEADY BURNING TYPE C OR TYPE D 360 DEGREE WARNING LIGHTS AND "KEEP RIGHT" SIGNS MAY BE SUBSTITUTED FOR CENTERLINE MARKINGS.
28. CLASS II TEMPORARY STRIPING (MINIMUM 4' LONG SEGMENTS) SHALL BE AS PER ITEM 614-WORK ZONE PAVEMENT MARKINGS AND SHALL BE PLACED WITH ONE (1) FOOT LONGITUDINAL TOLERANCE OF THE PERMANENT STRIPE (S). ALL STRIPING NOT TO WITHIN ONE (1) FOOT TOLERANCE SHALL BE REMOVED AND REPLACED IN THE PROPER LOCATION BY THE CONTRACTOR. CLASS II TEMPORARY STRIPING SHALL BE OF THE APPROPRIATE COLOR AND SPACED AT A MAXIMUM OF FORTY (40) FEET CENTER TO CENTER.
29. ITEM 614 - MAINTAINING TRAFFIC

ALL COSTS THAT CONSIST OF MAINTAINING AND PROTECTING VEHICULAR AND PEDESTRIAN TRAFFIC ACCORDING TO THE LATEST EDITION OF THE CITY OF COLUMBUS CONSTRUCTION AND MATERIAL SPECIFICATIONS, THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS (OMUTCD), AND PER THE REQUIREMENTS DESIGNATED IN THE PLAN INCLUDING ALL LAW ENFORCEMENT OFFICER (LEO) AND FLAGGER HOURS SHALL BE INCLUDED IN THE LUMP SUM ITEM 614.

IN ADDITION TO THE REQUIREMENTS HEREIN, AND THE LATEST EDITION OF THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, A UNIFORMED LAW ENFORCEMENT OFFICER (LEO) SHALL BE PROVIDED FOR CONTROLLING TRAFFIC UNDER THE FOLLOWING CONDITIONS:

- WORK WITHIN A SIGNALIZED INTERSECTION, DEFINED AS THE AREA BOUNDED BY THE REAR X-WALK LINES
- WHEN FLAGGING WITHIN THE INTERSECTION OF TWO ARTERIAL ROADWAYS
- WHEN SPECIFIED IN THE MAINTENANCE OF TRAFFIC PLAN OR AS DIRECTED BY THE PROJECT ENGINEER

A LAW ENFORCEMENT OFFICER (LEO) WITH PATROL CAR SHALL BE REQUIRED ONLY WHEN DIRECTED BY THE CITY. THE OFFICIAL PATROL CAR WITH WORKING TOP MOUNTED EMERGENCY FLASHING LIGHTS SHALL BE A PUBLIC SAFETY VEHICLE AS REQUIRED BY THE OHIO REVISED CODE.

A FLAGGER SHALL BE UTILIZED TO ASSIST IN CONTROLLING TRAFFIC WHILE EQUIPMENT IS ENTERING OR EXITING AN INTERSECTION OR WORK ZONE. THE CONTRACTOR MAY UTILIZE HIS OWN OR LEO UNDER PAY ITEM 614 MAINTAINING TRAFFIC, LUMP SUM.

FLAGGERS AND LEO'S SHALL BE EQUIPPED ACCORDING TO THE STANDARDS FOR FLAGGING TRAFFIC CONTAINED IN THE OMUTCD. FLAGGING OPERATIONS PERFORMED BY LEO'S OR DESIGNATED FLAGGERS SHALL ONLY BE PERMITTED AS LONG AS ALL TRAFFIC CONTROL IS IN PLACE ACCORDING TO FIGURE 6H-10 (TA-10) IN THE OHIO MANUAL.

IF THE CONTRACTOR WISHES TO UTILIZE LEOS' FOR TRAFFIC CONTROL OTHER THAN FOR THE REQUIRED IN THE PLANS, THEY DO SO AT THEIR OWN EXPENSE. THE CONTRACTOR SHALL MAKE ARRANGEMENT THROUGH THE COLUMBUS POLICE DIVISION AT (614) 645-4795.

LEO'S SHALL BE CONSIDER TO BE EMPLOYED BY THE CONTRACTOR AND THE CONTRACTOR SHALL BE RESPONSIBLE FOR THEIR ACTIONS. ALTHOUGH EMPLOYED BY THE CONTRACTOR, THE CITY REPRESENTATIVE SHALL HAVE CONTROL OVER THEIR PLACEMENT.

IF A SAFETY HAZARD DEVELOPS, A LEO MAY BE ASSIGNED BY THE COLUMBUS SAFETY AND SERVICES DIRECTOR AT THE CONTRACTOR'S EXPENSE.

ITEM 614 - LAW ENFORCEMENT OFFICER (LEO) WITH PATROL CAR, AS PER PLAN

IN ADDITION TO THE LEO AND FLAGGER HOURS INCLUDED IN ITEM 614 MAINTAINING TRAFFIC, LUMP SUM; THE FOLLOWING QUANTITIES HAVE BEEN CARRIED FORWARD TO THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER OR AN ACCEPTABLE REPRESENTATIVE OF THE CITY OF COLUMBUS. THE CONTRACTOR SHALL BE PAID FOR THIS BID ITEM ONLY IF DIRECTED BY THE ENGINEER.

ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR, AS PER PLAN - _____ HOURS

ITEM 614 - LAW ENFORCEMENT OFFICER (LEO) WITHOUT PATROL CAR, AS PER PLAN

IN ADDITION TO LEO AND FLAGGER HOURS INCLUDED IN THE ITEM 614 MAINTAINING TRAFFIC, LUMP SUM; THE FOLLOWING QUANTITIES HAVE BEEN CARRIED FORWARD THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER OR AN ACCEPTABLE REPRESENTATIVE OF THE CITY OF COLUMBUS. THE CONTRACTOR SHALL BE PAID FOR THIS BID ITEM ONLY IF DIRECTED BY THE ENGINEER.

ITEM 614, LAW ENFORCEMENT OFFICER WITHOUT PATROL CAR, AS PER PLAN - _____ HOURS

B. EXISTING PERMANENT TRAFFIC CONTROL ITEMS

1. ALL OVERHEAD CABLE, DOWN GUYS OR BACK GUYS SHALL NOT BLOCK ANY PORTION OF A TRAFFIC SIGNAL, TRAFFIC CONTROL SIGN, OR OTHER TRAFFIC CONTROL DEVICE SUCH THAT VISIBILITY OR OPERATION OF THE TRAFFIC CONTROL DEVICE IS IMPAIRED.
2. THE ROADWAY SHALL NOT BE OPENED TO NON-CONSTRUCTION TRAFFIC UNTIL THE CRITICAL PERMANENT TRAFFIC CONTROLS ARE IN PLACE, OR UNTIL TEMPORARY TRAFFIC CONTROLS APPROVED BY THE ENGINEER, ARE INSTALLED. THE CRITICAL PERMANENT TRAFFIC CONTROLS ARE **STOP, YIELD, ONE WAY, DO NOT ENTER** AND RESTRICTED TURN SIGNS. OTHER CRITICAL SIGNS MAY BE NOTED ON THE PLAN AS WELL. THE CONTRACTOR ASSUMES ALL LIABILITY FOR THE PREMATURE REMOVAL OF TEMPORARY TRAFFIC CONTROLS.
3. ALL PERMANENT PAVEMENT MARKINGS AND TRAFFIC CONTROL SIGNS AS SHOWN ON THIS PLAN SHALL BE INSTALLED BY THE CONTRACTOR AT THE PROJECTS EXPENSE. THE PROJECT ENGINEER SHALL BE NOTIFIED TO DIRECT APPROPRIATE PERSONNEL A MINIMUM OF FORTY-EIGHT (48) HOURS (EXCLUDING SAT. & SUN.) PRIOR TO THE INSTALLATION OF PERMANENT MARKING TO INSPECT AND APPROVE THE PAVEMENT MARKING LAYOUT PRIOR TO PLACING THE PERMANENT MARKINGS.
4. ANY WORK DONE BY THE DIVISION OF PLANNING AND OPERATIONS, INCLUDING INSTALLATION, RELOCATION, REMOVAL AND/OR REPLACEMENT OF PERMANENT TRAFFIC CONTROL DEVICES AS A RESULT OF WORK DONE BY THE CONTRACTOR OR AS A RESULT OF NEGLIGENCE OF THE CONTRACTOR, SHALL BE AT THE CONTRACTOR'S EXPENSE.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REINSTALLATION AND/OR REPLACEMENT OF ALL PERMANENT TRAFFIC CONTROL DEVICES DAMAGED OR REMOVED DURING CONSTRUCTION. PERMANENT TRAFFIC CONTROL NO LONGER IN CONFLICT WITH TEMPORARY TRAFFIC CONTROL SHALL BE REPLACED IMMEDIATELY.
6. PERMANENT STRIPING OR CLASS I TEMPORARY STRIPING SHALL BE INSTALLED NO LATER THAN FOURTEEN (14) CALENDAR DAYS AFTER THE FINAL PAVING COURSE IS COMPLETED. THE PAVING CONTRACTOR SHALL BE RESPONSIBLE TO NOTIFY THE STRIPING CONTRACTOR TO INSURE THE PERMANENT STRIPING IS INSTALLED WITHIN THE FOURTEEN (14) CALENDAR DAY LIMIT.
7. IF THE DIVISION OF PLANNING AND OPERATIONS IS TO INSTALL PERMANENT STRIPING, THE PROJECT ENGINEER SHALL BE NOTIFIED TO DIRECT APPROPRIATE PERSONNEL A MINIMUM OF TEN (10) WORKING DAYS PRIOR TO THE APPLICATION OF THE FINAL COURSE OF PAVEMENT.

NOTE #8 INSTRUCTIONS:

INSERT NOTE WHEN; WORKING NEAR A LOCATION WHERE TRAFFIC LOOP DETECTION AND/OR ITS LEAD IN CABLES COULD BE INADVERTENTLY DAMAGED. *CONTINGENCY ITEMS AND ESTIMATED QUANTITIES SHALL ONLY BE INCLUDED AS DIRECTED BY THE PLAN REVIEWER . LOOP DETECTION AND/OR ITS LEAD IN CABLES BEING DESTROYED OR ELSE RENDERED INOPERATIVE DUE TO TYPICAL CONSTRUCTION ACTIVITIES SHALL BE QUANTIFIED IN THE GENERAL SUMMARY AND SIGNAL SUMMARY AND SHOWN AS REMOVED AND REPLACED. NOTE #8 IS NOT REQUIRED FOR THIS OPERATION UNLESS THE AFOREMENTIONED REQUIREMENT IS MET.*

8. AT ANY LOCATION WHERE THE CONTRACTOR DAMAGES DETECTORS AND/OR THEIR LEAD IN CABLES THE CONTRACTOR SHALL REPLACE THEM. AT ANY LOCATION WHERE DETECTION IS CHANGED FROM MAG PROBE UNTIS TO LOOPS, THE CONTRACTOR SHALL REPLACE THE PROBE LEAD-IN WITH LOOP LEAD-IN CABLE. ALL REPAIRS TO DETECTION SHALL BE COMPLETED WITHIN 21 DAYS FROM DAMAGE TO DETECTION ON A PER INTERSECTION BASIS . IF THE 21 DAY REPAIR REQUIREMENT CANNOT BE SATISFIED AT ANY LOCATION WHERE THE CONTRACTOR DAMAGES DETECTORS AND/OR THEIR LEAD-IN CABLES, THE CONTRACTOR, AT THE DIRECTION OF SIGNAL OPERATION PERSONNEL, MAY BE REQUIRED TO INSTALL TEMPORARY MICROWAVE DETECTION OR TEMPORARY LOOP DETECTION. ANY CONTRACTOR FAILING TO COMPLY WITH THESE GUIDELINES SHALL BE SUBJECT TO PENALTY TO THE SUM OF \$100.00 PER DAY FOR EACH DAY BEYOND THE 21 DAY REPAIR PERIOD ON A PER INTERSECTION BASIS, UNTIL CONDITIONS ARE MET TO THE SATISFACTION OF SIGNAL OPERATIONS PERSONNEL. THIS PENALTY DEDUCTION SHALL BE SPECIFIC TO EACH SIGNALIZED INTERSECTION EFFECTED BY THIS PROJECT AND SEPARATE FROM ANY LIQUIDATED DAMAGES FOR THE PROJECT AS A WHOLE. THE WORK TO INSTALL THE DETECTION SHALL CONFORM TO ODOT STANDARD DRAWING TC-82.10 (DATED 4/19/02 OR LATER) AND TO THE CURRENT STATE OF OHIO CONSTRUCTION AND MATERIAL SPECIFICATIONS WITH THE FOLLOWING PROVISIONS:

- A) THE CONTRACTOR SHALL PROVIDE THE DIVISION OF DESIGN AND CONSTRUCTION'S INSPECTOR, PRIOR TO THE COMMENCEMENT OF WORK, THE IMSA (INTERNATIONAL MUNICIPAL SIGNAL ASSOCIATION) CERTIFICATION PAPERS FOR ALL SIGNAL TECHNICIANS WORKING ON THIS PROJECT.
- B) LOCATION OF THE REPLACEMENT DETECTION SHALL BE FIELD MARKED OR DIMENSIONED DRAWINGS SHALL BE SUBMITTED TO THE INSPECTION SERVICES SECTION BY DIVISION OF DESIGN AND CONSTRUCTION SECTION PERSONNEL. LOCATION OF FINAL PAVEMENT MARKINGS OR THE MARKINGS THEMSELVES SHALL BE CLEARLY INDICATED ON THE ASPHALT PRIOR TO DETECTOR LOCATIONS BEING MARKED. THE CONTRACTOR SHALL LAYOUT THE LOOPS ON THE PAVEMENT IF DRAWINGS ARE SUBMITTED. IF DRAWINGS HAVE NOT BEEN PROVIDED, CONTACT SIGNAL OPERATIONS PERSONNEL AT 645-0423 (CELL 419-4501) AT LEAST TWO WORKING DAYS PRIOR TO NEEDING THE LOCATION MARKED. IF UNABLE TO MAKE CONTACT THROUGH THE ABOVE NUMBERS, CALL 645-7393.
- C) THE SAW SLOT DEPTH FOR LOOP WIRE INSTALLATION SHALL BE FOUR (4) INCHES WITH SIX (6) INCHES AT THE CONDUIT ENTRANCE. IF ADVERSE PAVEMENT CONDITIONS WARRANT, DEPTH MAY BE INCREASED TO SIX (6) INCHES THROUGHOUT AND SHALL BE DETERMINED BY THE DIVISION OF DESIGN AND CONSTRUCTION INSPECTOR.
- D) EACH LOOP SHALL HAVE ITS OWN CONDUIT FROM EDGE OF PAVEMENT TO PULL BOX UNLESS SPECIFIED OTHERWISE BY THE DIVISION OF DESIGN AND CONSTRUCTION INSPECTOR.
- E) THE PULL BOX ASSEMBLY SHALL BE RATED AS MEDIUM TO HEAVY DUTY, TO BE INSTALLED IN CONCRETE WALKWAYS, AND SHALL HAVE ALL STAINLESS STEEL HARDWARE. THE PULL BOX COVER SHALL HAVE THE WORD "TRAFFIC" ON IT. THE COVER SHALL BE BOLTED TO THE BOX AND SHALL BE EITHER POLYMER CONCRETE OR STEEL PLATE. THE COVER PLUS HOUSING AS A UNIT SHALL BE RATED TO WITHSTAND A MINIMUM 20,000 LB. STATIC LOAD OVER A 10" x 10" AREA AS PER ASTM C-857. THE BOX DEPTH SHALL BE 18 INCHES MINIMUM TO 30 INCHES MAXIMUM. IF THE PROJECT DOES NOT SPECIFY 713.08 CONCRETE PULL BOXES, THE SUPPLIED ASSEMBLIES SHALL BE AS FOLLOWS: CDR SYSTEMS MODEL SA32-1015-18, OR SYNRETECH MODEL 11" x 18". SIX (6) INCHES OF #4 AGGREGATE SHALL BE PLACED AT THE BOTTOM OF THE PULL BOX. NO CONDUIT SHALL PROTRUDE MORE THAN THREE (3) INCHES INSIDE THE PULL BOX. CONDUIT ELLS OR EXTENSIONS MAY BE USED TO ALIGN THE CONDUIT WITH THE HOUSING. THE COST FOR EXTENSIONS OR ELLS IF NEEDED SHALL BE INCIDENTAL TO THE PER UNIT PRICE.
- F) WHEN A PULL BOX IS NOT USED, THE SOLDERED SPLICE SHALL BE MADE IN AN ANCHOR BASE STRAIN POLE OR A CONDUIT RISER SPECIFIED BY THE DIVISION OF PLANNING AND OPERATIONS' REPRESENTATIVE, EXCEPT WHERE A CONTROLLER CABINET IS MOUNTED ON THAT POLE IN WHICH CASE THE LOOP WIRE SHALL BE ROUTED DIRECTLY INTO THE CABINET.
- G) THE CONTRACTOR SHALL NOT MAKE ANY WIRING CONNECTIONS OR ADJUSTMENTS INSIDE THE CONTROLLER CABINET. WHEN SUCH CONNECTIONS ARE REQUIRED, THE CONTRACTOR SHALL NOTIFY THE TRAFFIC OPERATIONS SHOP 645-7393, MONDAY THROUGH FRIDAY, 8:00 A.M. TO 4:00 P.M., TO SCHEDULE CITY FORCES FOR MAKING THE ACTUAL CONNECTIONS. THE CONTRACTOR SHALL BE AVAILABLE AT THE AGREED TIME. THE CONTRACTOR SHALL BE BILLED FOR ANY TIME THAT CITY FORCES ARE REQUIRED TO WAIT FOR THE CONTRACTOR'S WORK TO BE COMPLETED.
- H) CONDUIT PLACED IN "RIGHT OF WAY" AREAS BEARING NO TRAFFIC FOR DETECTOR LEAD IN SHALL BE ODOT ITEM 725.051, ODOT CONSTRUCTION AND MATERIAL SPECIFICATIONS, LATEST EDITION. CONDUIT PLACED UNDER A ROADWAY OR IN AREAS THAT MAY BEAR TRAFFIC SHALL BE ODOT ITEM 725.04, SIZES AND TYPE TO BE DETERMINED BY THE DIVISION OF PLANNING AND OPERATIONS' REPRESENTATIVE. ALL CONDUITS SHALL BE PLACED AT A MINIMUM DEPTH OF TWENTY-FOUR (24) INCHES.
- I) LOOP WIRE SHALL BE IDENTIFIED WITH A PLASTIC TAG (WBLT, EBRT, ECT.) AT THE SPLICE POINT OR AT ENTRANCE TO THE CABINET IF LEAD-IN CABLE IS NOT USED.
- J) THE ITEMS AND ESTIMATED QUANTITIES FOR THE OF THE DIVISION OF PLANNING AND OPERATIONS' DETECTION ITEMS SHALL BE INCLUDED IN THESE PLANS WHEN DIRECTED BY THE PLAN REVIEWER. THESE ESTIMATES ARE FOR THE PURPOSE OF BIDDING THE PROJECT. THE FOLLOWING IS A LIST OF THE ITEMS AND QUANTITIES PROJECTED FOR USE IN DETECTOR REPLACEMENT FOR THIS PROJECT:

ITEM	QUANTITY	UNIT	ITEM DESCRIPTION
202		SF	WALK REMOVED
608		SF	4" CONCRETE WALK
632		LF	CONDUIT RISER, 1 OR 2 INCH DIA.
625		LF	CONDUIT 1, 1 1/2, OR 2 INCH DIA.
625		LF	TRENCH
625		EACH	PULL BOX, AS PER PLAN
632		EACH	DETECTOR LOOP
632		LF	LOOP DETECTOR LEAD-IN CABLE
632		LF	LASH / UNLASH CABLE

THE CONTRACTOR SHALL NOTIFY SIGNAL OPERATIONS' PERSONNEL AT 645-0423 (CELL 419-4501) AFTER ALL LOOPS HAVE BEEN INSTALLED AT EACH INTERSECTION. IF UNABLE TO MAKE CONTACT THROUGH THE ABOVE NUMBER CALL 645-7393. THE DIVISION OF PLANNING AND OPERATIONS SHALL INSPECT ALL SENSORS AND TEST AS NECESSARY. THE CONTRACTOR SHALL REPLACE ALL LOOPS NOT MEETING SPECIFICATIONS.



HORIZ SCALE



CALCULATED CHECKED

MAINTENANCE OF TRAFFIC NOTES

PROJECT NAME



XXXX-E



HORIZ SCALE



CALCULATED



CHECKED

MAINTENANCE OF TRAFFIC

PROJECT NAME




DRUMS WITH STEADY BURN LIGHTS
TYPICAL SPACINGS :-
8' RADI
25' TAPERS AND TANGENTS



SIGNAL MOT
PHASE I
DURING PHASE I EASTBOUND SIGNAL HEADS FOR STREET NAME 11 @ STREET NAME 4 SHALL BE COVERED AND HAVE POWER DISCONNECTED TO THE HEADS AT THE CONTROL CABINET. (SEE ITEM 632 COVERING OF VEHICULAR/PED SIGNAL HEADS AND PUSHBUTTONS, AS PER PLAN SHEETS 31-46) CONTACT THE CITY OF COLUMBUS TRAFFIC MAINTENANCE SHOP AT 645-7933 WHEN SIGNAL HEADS ARE TO BE COVERED SO THE CITY CAN DISCONNECT THE EASTBOUND LOOP. (GIVE 3 CITY WORK DAY NOTICE) TEMPORARY SIGNAL POLE INSTALLATION WILL BE COMPLETED AT THIS TIME. EACH TEMPORARY SIGNAL POLE LOCATION IS TO BE STAKED AND THE LOCATION APPROVED BY THE TRANSPORTATION DIVISION SIGNAL INSPECTOR. THE CONTRACTOR MAY REUSE EXISTING SPAN OR INSTALL NEW AS REQUIRED BUT INSTALL TWO NEW PIGTAILS. AS PER PLAN, THE CONTRACTOR SHALL TRANSFER EXISTING SIGNAL ITEMS (SIGNAL CONTROLLER CABINET, PED UNITS, & PUSHBUTTONS W/SIGNS) AND EXTEND CABLE AS NEEDED. WEATHERPROOF SPLICING IS PERMITTED INCLUDING HEAD SHIFTING. ONE OR TWO DOWN GUYS ARE TO BE USED AS SPECIFIED.

PHASE II
SHIFT WESTBOUND SIGNAL HEADS AT STREET NAME 1 @ STREET NAME 4 AND STREET NAME 1 @ STREET NAME 2. THE CONTRACTOR SHALL SHIFT OVERHEAD SIGNS AS INDICATED AND PLACE SIGNAL HEADS AT STREET NAME 1 @ STREET NAME 2 4' ON EACH SIDE OF THE CENTER LINE OF THE LANE. SIGNAL HEADS AT ROAD NO. 1 @ xxxx ST SHALL BE PLACED IN SAME MANNER UNLESS LEFT TURN LANE IS ADDED THEN SHIFT SIGNAL HEADS 1' FROM DOUBLE YELLOW LINE WITH 9' SPACING. THE CONTRACTOR SHALL NOTIFY THE SIGNAL MAINTENANCE SHOP (645-7933) THREE (3) CITY WORKDAYS PRIOR TO ANY LANE SHIFTING THAT EFFECTS TRAFFIC PASSING THROUGH A SIGNALIZED INTERSECTION OR PRIOR TO ANY SIGNAL WORK SO REQUIRED SIGNAL TIMING, PHASING OR CONTROL CABINET CHANGES CAN BE MADE TO THE EXISTING EQUIPMENT.

- CONSTRUCTION STAGING: STAGE 2**
CONSTRUCTION OF NEW PAVEMENT ON THE NORTH SIDE OF STREET NAME 1.
1. THE ERECTION OF THE TEMPORARY SIGNS AND TRAFFIC MARKINGS.
 2. THE CONSTRUCTION OF THE NEW WIDENING SECTION ON THE NORTH SIDE OF STREET NAME 1 AND THE CONSTRUCTION/RELOCATION OF ALL UNDERGROUND UTILITIES AND CONDUITS.
 3. THE FINAL PAVING OF THE ENTIRE PROJECT WIDTH AND LENGTH
 4. THE SEEDING AND MULCHING OF THE ENTIRE SITE.
 5. THE FINAL STRIPING AND SIGNING OF THE ENTIRE PROJECT
 6. THE CONSTRUCTION OF THE NEW SIGNAL AT THE INTERSECTION OF STREET NAME 1 AND STREET NAME 4, AND THE SIGNAL AT THE INTERSECTION OF STREET NAME 1 AND STREET NAME 2.
 7. THE CONTRACTOR SHALL PERFORM FINAL CLEANING AND REMOVE ALL EQUIPMENT FROM SITE
 8. THE CONTRACTOR SHALL COMPLY WITH THE FINAL PUNCH LIST PREPARED BY THE CITY'S INSPECTOR.
 9. THE CLOSE-OUT OF THE PROJECT.
 10. PAYMENT FOR MAINTENANCE OF TRAFFIC (NOT INCLUDING MOBILIZATION, PERMANENT SIGNING AND STRIPING) SHALL BE INCLUDED IN THE LUMP SUM ITEM 614 MAINTENANCE OF TRAFFIC.
 11. CONTRACTOR TO FURNISH AND INSTALL DRUMS TO CLOSE THE SOUTH BOUND LEFT LANE OF STREET NAME 4 AT ALL TIMES.



PAVEMENT WIDENING AREA:

STREET NAME 1

STA. 46+00 TO STA. 47+00	= 100' X (0' + 11')/2	= 550.00 SF.
STA. 47+00 TO STA. 49+26	= 226' X 11'	= 2486.00 SF.
SOUTH-WEST CORNER	= PLANIMETERED	= 860.00 SF.
STA. 50+75 TO STA. 52+35	= 160' X 11'	= 1760.00 SF.
STA. 52+35 TO STA. 53+35	= 100' X (11' + 0')/2	= 550.00 SF.
NORTH-EAST CORNER	= PLANIMETERED	= 767.00 SF.

SUB-TOTAL = 6973.00 SF.

STREET NAME 2

STA. 17+08 TO STA. 19+19	= 211' X 11'	= 2321.00 SF.
STA. 19+19 TO STA. 19+74	= PLANIMETERED	= 997.00 SF.
STA. 20+82 TO STA. 21+87.50	= 105.5' X 11'	= 1160.50 SF.
STA. 21+87.50 TO STA. 22+46	= 58.5' X (11' + 0')/2	= 321.75 SF.
NORTH-WEST CORNER	= PLANIMETERED	= 877.00 SF.

SUB-TOTAL = 5677.25 SF.

TOTAL = 12,650.25 SF.

ITEM: 416: 1 1/2" ASPHALT CONCRETE, CONTRACTOR MIX

DESIGN, TYPE III, SURFACE COURSE, AS PER PLAN = (12,650.25 SF. X 1.50"/12)/27 X 2 = 117.13 TONS

PAVEMENT PLANING AND RESURFACING AREA = (74,077.00 SF. X 1.50"/12)/27 X 2 = 685.90 TONS

TOTAL = 803.03 TONS

ITEM: 305: 8" PORTLAND CEMENT CONCRETE BASE - ARTERIAL: = 12,650.25 SF./9 = 1405.58 S.Y.

ITEM: 416: 1 1/2" ASPHALT CONCRETE, CONTRACTOR MIX

DESIGN, TYPE III, INTERMEDIATE COURSE, AS PER PLAN = (12,650.25 SF. X 1.50"/12)/27 X 2 = 117.13 TONS

AREA FOR ITEM: 204: SUBGRADE COMPACTION

STREET NAME 1

STA. 46+00 TO STA. 47+00	= 100' X (0' + 11')/2	= 550.00 SF.
STA. 47+00 TO STA. 49+26	= 226' X 11'	= 2486.00 SF.
SOUTH-WEST CORNER	= PLANIMETERED	= 860.00 SF.
STA. 50+75 TO STA. 52+35	= 160' X 11'	= 1760.00 SF.
STA. 52+35 TO STA. 53+35	= 100' X (11' + 0')/2	= 550.00 SF.
NORTH-EAST CORNER	= PLANIMETERED	= 767.00 SF.

SUB-TOTAL = 6973.00 SF.

STREET NAME 2

STA. 17+08 TO STA. 19+19	= 211' X 13.5'	= 2848.50 SF.
STA. 19+19 TO STA. 19+74	= PLANIMETERED	= 997.00 SF.
STA. 20+82 TO STA. 21+87.50	= 105.5' X 13.5'	= 1424.25 SF.
STA. 21+87.50 TO STA. 22+46	= 58.5' X (13.5' + 0')/2	= 394.88 SF.
NORTH-WEST CORNER	= PLANIMETERED	= 877.00 SF.

SUB-TOTAL = 6541.63 SF.

TOTAL = 13,514.63 SF.

ITEM: 204: SUBGRADE COMPACTION: = 13,514.63 SF./9 = 1501.63 S.Y.

ITEM: 609: COMBINATION CURB AND GUTTER

STA. 17+10 TO STA. 19+19 (RT.)	= 214.00 L.F.
STA. 20+82 TO STA. 22+46 (LT.)	= 164.00 L.F.

TOTAL = 378.00 L.F.

ITEM: 605: 4" PIPE UNDERDRAIN: = 378' + 996' = 1374.00 L.F.

ITEM: 407: TACK COAT:

FROM PAVEMENT WIDENING	= (12,650.25 SF./9) X 0.10 GAL./S.Y.	= 140.56 GALS.
FROM PAVEMENT PLANING & RESURFACING	= (74,077.00 SF./9) X 0.15 GAL./S.Y.	= 1234.62 GALS.
FROM PAVEMENT CUT	= (1381.00 LF. X 11"/12) X 0.10 GAL./S.Y.	= 14.07 GALS.

TOTAL = 1389.25 GALS.

SURFACE AREA FOR TACK COAT AT PAVEMENT CUT

STA. 46+00 (RT.) TO STA. 19+06 STREET NAME 1 (LT.)	= 425.00 L.F.
STA. 49+14 (LT.) TO STA. 22+46 STREET NAME 1 (LT.)	= 266.00 L.F.
STA. 17+10 (RT.) TO STA. 50+88 STREET NAME 2 (RT.)	= 330.00 L.F.
STA. 20+97 (RT.) TO STA. 53+35 STREET NAME 2 (LT.)	= 360.00 L.F.

TOTAL = 1381.00 L.F.

ITEM: 609: 18" STRAIGHT CONCRETE CURB:

STA. 46+00 (RT.) TO STA. 19+06 (LT.)	= 403.00 L.F.
STA. 40+87 TO STA. 20+82 (LT.)	= 111.00 L.F.
STA. 19+19 TO STA. 51+47 (RT.)	= 140.00 L.F.
STA. 20+97 TO STA. 53+35 (LT.)	= 342.00 L.F.

TOTAL = 996.00 L.F.

ITEM: 608: 4" CONCRETE WALK:

STA. 17+10 TO STA. 17+87 (RT.)	= (5' X 77')+(10'X15') NE-CORNER W/O X AVE.	= 535.00 SF.
STA. 18+13 TO STA. 18+35 (RT.)	= 5' X 22'	= 110.00 SF.
STA. 18+68 TO STA. 19+10 (RT.)	= 5' X 42'	= 210.00 SF.
STA. 51+23 TO STA. 51+47 (RT.)	= 12.5' X 24'	= 300.00 SF.
STA. 51+98 TO STA. 52+18 (LT.)	= 5' X 20'	= 100.00 SF.
STA. 52+29 TO STA. 52+49 (LT.)	= 5' X 20'	= 100.00 SF.
STA. 52+83 TO STA. 53+02 (LT.)	= 5' X 19'	= 95.00 SF.
STA. 53+12 TO STA. 53+35 (LT.)	= 5' X 23'	= 115.00 SF.
STA. 47+98.50 TO STA. 48+15 (RT.)	= (4'X13') + (5'X18')	= 142.00 SF.
STA. 48+53 TO STA. 49+06 (RT.)	= 5' X 53'	= 265.00 SF.
STA. 20+90 TO STA. 21+38 (LT.)	= 8' X 48'	= 384.00 SF.
STA. 21+73 TO STA. 21+95 (LT.)	= 8' X 22'	= 176.00 SF.
STA. 21+00 TO STA. 21+10 (RT.)	= 5' X 10'	= 50.00 SF.
STA. 48+87 TO STA. 49+05 (LT.)	= 4' X 18'	= 72.00 SF.
STA. 50+88 TO STA. 51+56 (LT.)	= 5' X 68'	= 340.00 SF.

TOTAL = 2994.00 SF.

ITEM: 608: 8" CONCRETE WALK:

STA. 19+10 TO STA. 19+69 (RT.) (SE-CORNER)	= 8.5' X 78'	= 663.00 SF.
STA. 20+74 TO STA. 50+88 (RT.) (NE-CORNER)	= 12'(AVG.) X 58'	= 696.00 SF.
STA. 19+06 (LT.) TO STA. 49+06 (RT.) (SW-CORNER)	= 9.5' X 98'	= 931.00 SF.
STA. 49+05 (LT.) TO STA. 20+90 (LT.) (NW-CORNER)	= 9.8'(AVG.) X 99'	= 970.00 SF.

TOTAL = 3260.00 SF.

AREA FOR PAVEMENT PLANING AND RESURFACING:

STREET NAME 2

STA. 17+08 TO STA. 22+50 = (542' X 56') - 2(80' X 11' BUS PADS) = 28,592.00 SF.

STREET NAME 1

STA. 46+00 TO STA. 49+75 = (375' X 52') - (74' X 11' BUS PAD) = 18,686.00 SF.

STA. 50+30 TO STA. 55+35 = (505' X 52') - (105' X 11' BUS PAD) = 25,105.00 SF.

ADD FILLET AREAS

S.W. CORNER	= 322.00 SF.
S.E. CORNER	= 375.00 SF.
N.E. CORNER	= 416.00 SF.
N.W. CORNER	= 581.00 SF.

TOTAL AREA = 74,077.00 SF.

HORIZ. SCALE



N/T'S

CALCULATED


CHECKED

PAVEMENT CALCULATIONS

PROJECT NAME



STABILIZED CONSTRUCTION ENTRANCE




CONSTRUCTION SPECIFICATIONS

1. Stone Size – Use 2 inch stone, or reclaimed or recycled concrete equivalent.
2. Length – As required.
3. Thickness – Not less than six (6) inches.
4. Width – Twenty (20) foot minimum, but not less than the full width at points where ingress or egress occurs.
5. Filter Cloth – will be placed over the entire area prior to placing of stone.
6. Surface Water – All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 5:1 slopes will be permitted.
7. Maintenance – The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public right-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights-of-way must be removed immediately.
8. Washing – Wheels shall be cleaned to remove sediment prior to entrance onto public right-of-ways. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device.
9. Periodic inspection and needed maintenance shall be provided after each rain.

Sediment and Erosion Control Quantities			
Item	Quantity	Unit	Description
207	3	Each	Catch Basin Protection
207	44	Each	Inlet Protection
207	1	Each	Filter Fabric Fence for Catch Basins

LEGEND




Note A: The Contractor shall be responsible for maintaining on-site drainage at all times during construction. No separate payment shall be made for maintaining drainage.

Note B: Structures 45, 47, 49, 51, 53, 54, 76, 77, & 78 are double inlets and require two curb bags.

Construction Sequence

1. Install required sediment fence and inlet protection on existing inlets as shown on Phase 1 Plan.
2. Install utilities and storm sewers. Provide inlet protection.
3. Construct proposed street and utilities.
4. Stabilize the disturbed areas per temporary and permanent seeding requirements.
5. Remove storm sewer inlet protection.



HORIZ. SCALE




CALCULATED
CHECKED

STORM WATER POLLUTION PREVENTION PLAN


PROJECT NAME




XXXX-E



MAINTENANCE:
 Aggregate check dams shall be inspected immediately after each rainfall and at least daily during prolonged rainfall.
 Close attention shall be paid to the repair of damaged check dams, end runs and undercutting beneath dams.
 Necessary repairs to check dams shall be accomplished promptly.
 Sediment deposits should be removed after each rainfall. They must be removed when the level of deposition reaches approximately one-half the height of the barrier.
 Any sediment deposits remaining in place after the aggregate is no longer required shall be dressed to conform to the existing grade, prepared and seeded.



MAINTENANCE:
 With a stiff bristle broom sweep silt and other debris off surface after each event.
USE FOR INLETS:
 6-9, 11-14, 16-18, 21, 37-41, 43-54, 58, 59, 68-70, 73-81, 84, 85, 87-93, 95, 97-103, 126, 127, 129, 131, 150



Concrete trucks shall utilize areas to washout trucks. Accumulated concrete shall be removed from the site and disposed of properly.
 As an alternative, contractor shall use a roll off box with liner.

CONTRACTOR RESPONSIBILITY: Details have been provided on the plans in an effort to help the Contractor provide erosion and sedimentation control. The details shown on the plan shall be considered a minimum. Additional or alternate details may be found in the O.D.N.R. Manual "Rainwater and Land Development". The Contractor shall be solely responsible for providing necessary and adequate measures for proper control of erosion and sediment runoff from the site along with proper maintenance and inspection in compliance with the NPDES General Permit for Storm Water Discharges Associated with Construction Activity.

Prior to Construction Operations in a particular area, all sedimentation and erosion control features shall be in place. Field adjustments with respect to locations and dimensions may be made by the Engineer.

The Contractor shall place inlet and channel protection for erosion control immediately after construction of the inlets or channels which are not tributary to a sediment basin or dam.

It may become necessary to remove portions of the barrier during construction to facilitate the grading operations in certain areas. However, the barrier shall be in place in the evening or during any inclement weather.

The limits of seeding and mulching are as shown within the plans. Those areas disturbed outside the seeding limits shall be seeded and mulched at the Contractor's expense.

"Temporary seeding" No area for which grading has been completed or where a denuded area will remain idle for more than 21 days shall be left unseeded for longer than 7 days. If permanent seed is not applied at this time, temporary seeding shall be done at the following rates:

March 1 to August 15
 Seed: Oats 2 lbs./1,000 Sq.Ft.
 Fertilizer: (12:12:12) 25 lbs./1,000 Sq.Ft.
 Mulch: (Straw or Hay) 2 tons/acre

August 15 to November 1
 Seed: Annual Rye 2 lbs./1,000 Sq.Ft.
 Fertilizer: (12:12:12) 25 lbs./1,000 Sq.Ft.
 Mulch: (Straw or Hay) 2 tons/acre

November 1 to March 1
 Mulch (ONLY): (Straw or Hay) 2 tons/acre

"Permanent seeding" shall be done between March 15 and September 15. If seeding is done between September 15 and March 15, it shall be classified as "Temporary Seeding." Permanent seed shall be 40% Kentucky Bluegrass, 40% Creeping Red Fescue, 20% Annual Ryegrass. Permanent seeding shall consist of fertilizing, watering and seeding rates indicated under Item 659. Seeding shall be applied within two (2) days after final grading or following seed bed preparation.

Rates of application of Item 659:
 Seed: 4 lbs./1,000 Sq.Ft.
 Fertilizer: (12:12:12) 20 lbs./1,000 Sq.Ft.
 Mulch: Straw (Hay) 2 tons/acre (3 tons/acre)

MAINTENANCE: It is the Contractor's responsibility to maintain the sediment control features used on this project. The site shall be inspected periodically and within 24 hours of a significant rainfall. Records of these inspections shall be kept and made available to jurisdictional agencies if requested. Any sediment or debris which has reduced the efficiency of a structure shall be removed immediately. Should a structure or feature become damaged, the Contractor shall repair or replace at no additional cost to the Owner. Not all details shown on this sheet may be required for this project. Reference Sediment Control Plan.


The cost for temporary channels, sediment dams, sediment basins, and other appurtenant earthmoving operations shall be included in the price bid for erosion and sedimentation control quantities.

Not all details shown on this sheet may be required for this project.
 The Contractor shall be responsible to ensure that off-site tracking of sediments by vehicles and equipment is minimized. All such off-site sediment shall be cleaned up daily. Construction of stabilized construction entrances are a part of that responsibility.


Street Cleaning (on an as-needed basis) is required through the duration of this construction project. This includes sweeping, power cleaning and (if necessary) manual removal of dirt or mud in the street gutters.

The Contractor shall be responsible to ensure that no solid or liquid waste is discharged into stormwater runoff. Sediment-laden water shall be filtered through the use of sediment filtering fences or sedimentation basins prior to discharge to surface waters. Concrete trucks will not be allowed to wash out or discharge surplus concrete into or alongside rivers, streams, and creeks or into natural or man-made channels or swales leading thereto. Concrete truck wash water and surplus concrete shall be confined to areas approved by the Engineer; after solidifying, these waste materials shall be removed from the site.

ALL EROSION & SEDIMENT CONTROL PRACTICES ARE SUBJECT TO FIELD MODIFICATION AT THE DIRECTION OF THE CITY OF COLUMBUS AND/OR OHIO EPA.



MAINTENANCE:
 Remove all accumulated sediment and debris from the surface and vicinity of the unit after each storm event.
 If using optional oil absorbents, remove and replace absorbents when they near saturation.
USE FOR INLETS:
 Existing (See sheet 24)



SILT FENCE:
 This sediment barrier utilizes standard strength or extra strength synthetic filter fabrics. It is designed for situations in which only sheet or overland flows are expected.

MATERIAL PROPERTIES ARE:

- The height of a silt fence shall not exceed 36 inches (higher fences may impound volumes of water sufficient to cause failure of the structure).
- The filter fabric shall be purchased in a continuous roll cut to the length of the barrier to avoid the use of joints. When joints are necessary, filter cloth shall be spliced together only at a support post, with a minimum of a 6 inch overlap, and securely sealed.
- Posts shall be spaced a maximum of 10 feet apart at the barrier location and driven securely into the ground (minimum of 12 inches). Wood posts will be a minimum of 32" long. When extra strength fabric is used without the wire support fence, post spacing shall not exceed 6 feet.
- A trench shall be excavated approximately 4 inches wide and 6 inches deep along the line of posts and upslope from the barrier.
- When standard strength filter fabric is used, a wire mesh support fence shall be fastened securely to the upslope side of the posts using heavy duty wire staples at least 1-inch long, tie wires or hog rings. The wire shall extend into the trench a minimum of 2 inches and shall not extend more than 36 inches above the original ground surface.
- The standard strength filter fabric shall be stapled or wired to the fence, and 8 inches of the fabric shall be extended into the trench. The fabric shall not extend more than 36 inches above the original ground surface. Filter fabric shall not be stapled to existing trees.
- When extra strength filter fabric and closer post spacing are used, the wire mesh support fence may be eliminated. In such a case, the filter fabric is stapled or wired directly to the posts with all other provisions of Item No. 6 applying.
- The trench shall be backfilled and soil compacted over the filter fabric. Silt fences shall be removed when they have served their useful purpose, but not before the upslope area has been permanently stabilized.
- Silt fences and filter barriers shall be inspected immediately after each rainfall and at least daily during prolonged rainfall. Any required repairs shall be made immediately.
- To prevent water ponded by the silt fence from flowing around the ends, each end shall be constructed upslope so that the ends are at a higher elevation.

FABRIC PROPERTIES	VALUES	TEST METHOD
Grab Tensile Strength	90 lb. Minimum	ASTM 1682
Mullen Burst Strength	190 psi Minimum	ASTM 3786
Slurry Flow Rate	0.3 gal./min./ft ² Max	
Equivalent Opening Size	40-80	U.S. Std. Sieve CW-02215
Ultraviolet Radiation Stability	90% Minimum	ASTM-G-26

Note: The use of straw wattles has proven to be a versatile and effective ESC BMP, especially in residential settings. Straw wattles may be substituted for silt fence in linear installations. See detail, Sheet 27.


MAINTENANCE:
 Should the fabric on a silt fence or filter barrier decompose or become ineffective prior to the end of the expected usable life and the barrier is still necessary, the fabric shall be replaced promptly.

Sediment deposits should be removed after each storm event. They must be removed when deposits reach approximately one-half the height of the barrier.


Any sediment deposits remaining in place after the silt fence or filter barrier is no longer required shall be dressed to conform with the existing grade, prepared and seeded.

SEDIMENT AND EROSION CONTROL QUANTITIES

ITEM	TOTAL QUANTITY							UNIT	DESCRIPTION
	24	25	26	27	28	29	TOTAL		
207	-	-	-	-	225	3350	3575	LN. FT.	PERIMETER FILTER FABRIC FENCE
207	-	4	3	-	1	-	8	EACH	INLET PROTECTION
207	-	6	44	3	23	-	76	EACH	CATCH BASIN PROTECTION
207	16	-	1	-	15	4	36	EACH	FILTER FABRIC CATCH BASIN PROTECTION
207	-	-	-	7	2	2	11	EACH	ROCK CHECK DAM
207	-	-	-	-	-	1	1	EACH	STABILIZED CONSTRUCTION ENTRANCE
207	-	-	-	-	-	1	1	EACH	CONCRETE WASHOUT AREA



MAINTENANCE:
 With a stiff bristle broom or square point shovel remove silt & other debris off surface after each event.
USE FOR CATCH BASINS:
 71, 72, 133, 134, 136, 138, 140



USE FOR CATCH BASINS:
 57, 104, 105, 110-117, 119, 121-123, 145-148, Existing (See sheets 24 & 28)
SPECIFIC APPLICATION:
 This method of inlet protection is applicable where the inlet drains a relatively flat area (slopes no greater than 5 percent) where sheet or overland flows (not exceeding 0.5 cfs) are typical. This method shall not apply to inlets receiving concentrated flows, such as in street and highway medians.

FOR SIDEWALK RAMP DETAILS
SEE SHEET xxx.
FOR INTERSECTION
DETAIL SEE SHEET xxx.


LEGEND

- T.B.R - TO BE REMOVED
- FH - FIRE HYDRANT
- BT - BEGIN TAPER
- ET - END TAPER
- APP - AS PER PLAN


BENCHMARK ⊕
SOUTH BOLT OF FH
SOUTH SIDE OF ROAD NO. 1
STA 151+84.52, 21.71' RT
ELEV. = 858.42

BEGIN WORK
STA. 148+60.00
BEGIN MILL AND OVERLAY

Existing Curve Data
ROAD NO. 2
P.I. Sta = 1+02.62
D = 45° 54' 39" (RT)
Dc = 30' 09" 20"
R = 190.00'
T = 80.48'
L = 152.25'
E = 16.34'



870	854.63	854.45	854.36	854.28	854.19	853.99	853.98	854.04	854.09	854.20	854.31	854.48	854.72	854.96	855.20	855.43	855.60	855.77	855.90	856.03	856.14	856.26	870
865																							865
860																							860
855																							855
850																							850
845																							845
840																							840
835																							835
	148+00				149+00					150+00				151+00					152+00			153+00	




**PLAN & PROFILE
STATION TO STATION**

PROJECT NAME

XXXX - E

REF NO.	SHEET NO.	STATION		SIDE	202	202	901	901	901	604	604	604	604	608		608	807	810				
					PIPE REMOVED	REMOVAL MISC. POST	12" PIPE W/ TYPE 1 BEDDING	15" PIPE W/ TYPE1 BEDDING	18" PIPE W/ TYPE1 BEDDING	HEADWALL FOR 12" PIPE	STANDARD CATCH BASIN	MANHOLE TYPE C	CURB AND GUTTER INLET	CURB RAMP		DETECTABLE WARNINGS	VALVE BOX ADJUSTED TO GRADE	6" HYDRANT EXTENSION				
		FROM	TO		L.F.	EACH	L.F.	L.F.	L.F.	EACH	EACH	EACH	EACH	EACH		EACH	EACH	EACH				
D-1	36	148+60	151+00	LT			241			1		2										
D-2	36	149+50	149+50	LT			7						1									
D-3	36	148+99	153+00	RT			215		201		2		2									
D-4	36	149+75	149+75	RT			7						1									
D-5	36	151+00	151+00	LT/RT			54	46			2		2									
W-1	36	151+87		RT													1		1			
W-2	36	152+87		RT													1					
R-1	36	149+08	149+37	LT	29																	
R-2	36	149+56	149+74	LT	18																	
R-3	36	148+89	148+91	LT		14																
	36	148+81	148+95	RT										2		2						
	36	148+82		LT												1						
	36	149+33	149+58	RT										2		2						
	36	149+57		LT												1						
TOTALS CARRIED TO GENERAL SUMMARY					47	14	524	46	201	1	2	4	6	4		6	2	1				




CALCULATED
CHECKED

SUBSUMMARY

PROJECT NAME

X
XX

XXXX-E



END AREA	VOLUME	
	CUT	FILL
82	29	
58	66	
48	35	
59	20	
104	36	
53	19	
18	6	
43	11	
66	16	
309	142	


**STREET NAME 1 CROSS SECTIONS
STA. 123+50 TO STA. 125+00**

PROJECT NAME

CALCULATED: _____
 CHECKED: _____

HORIZ. SCALE: 1" = 25'
 VERTICAL SCALE: 1" = 5'

SHEET TOTAL: 377
 XXXX-E



END AREA		VOLUME	
CUT	FILL	CUT	FILL




CROSS SECTION
STATION TO STATION

PROJECT NAME

X
XX

XXXX-E

REVISED 12/2/11




INTERSECTION & CURB RAMP DETAILS

PROJECT NAME





NOTES:
 1. ** CENTERLINE OF RAMP SHALL BE SET WITH STATION/OFFSET; PROJECT LINE PERPENDICULAR TO CENTERLINE OF ROAD TO ARRIVE AT THE RAMP CENTERLINE STATION.
 2. 8" WALK SHALL BE PLACED AT THE INTERSECTIONS OF ARTERIAL ROADWAYS PER STD DWG 2303




SCALE 1" = 10'


** FINAL FOUNDATION ELEVATION DETERMINED BY SIDEWALK PLACEMENT. SEE DETAIL ON SHEET 252.



SCALE 1" = 10'




SCALE 1" = 10'




SCALE 1" = 20'

NOTE:
 THE SHOWN ELEVATIONS ALONG THE CURB AND GUTTER, REPRESENTS EDGE OF PAVEMENT ELEVATIONS.




SCALE 1" = 10'




Commercial Drive @ 134+43.64 Lt.
 Scale: 1"=10'




Residential Drive @ 136+33.13 Lt.
 Scale: 1"=10'



Residential Drive @ 137+15.50 Rt.
 Scale: 1"=10'




Commercial Drive @ 137+90.52 Rt.
 Scale: 1"=10'




Commercial Drive @ 138+63.73 Lt.
 Scale: 1"=10'


Curve Data Table								Rad. Pt. Sta./ Offset Street Name
Ref. Letter	Δ	R	T	L	E	M	A	
A	90°00'00"	20.00'	20.00'	31.42'	8.28'	5.86'	86 SF	140+45.14, 35.00' Rt.
B	90°00'00"	20.00'	20.00'	31.42'	8.28'	5.86'	86 SF	141+11.14, 35.00' Rt.
C	87°08'01"	20.00'	19.02'	30.42'	7.60'	5.50'	76 SF	141+16.45, 35.00' Lt.
D	61°54'58"	20.00'	12.00'	21.61'	3.32'	2.85'	24 SF	141+86.50, 35.00' Lt.




Commercial Drive @ 140+09.96 Lt.
 Scale: 1"=10'



Commercial Drive @ 140+78.14 Rt.
 Scale: 1"=10'



Commercial Drive @ 141+51.49 Lt.
 Scale: 1"=10'



Residential Drive @ 145+99.39 Lt.
 Scale: 1"=10'

- LEGEND**
- XXX.XX Proposed Elevations
 - (XXX.XX) Existing Elevations
 - XXX.XX Proposed Pavement Crown/Walk Elevation
 - +XX Proposed Station
 - TC XXX.XX Proposed Top of Curb Elevation
 - +XX Proposed Station
 - EP XXX.XX Proposed Edge of Pavement Elevation
 - +XX Proposed Station
 - TC Top of Casting
 - T/S Match Typical Section Grades
 - ME Match Existing

* Actual elevation is 0.44' lower due to driveway cutout.
 # Taper curb height from 6" to at walk with 1:10 flare.

PAVEMENT DETAIL NOTES

Curb return and taper data is shown to face of curb in curb areas and edge of pavement in pavement areas.

All elevations shown are to finished pavement unless otherwise noted.





CALCULATED
CHECKED

STORM SEWER
PROFILES

PROJECT NAME



XXXX-E



NOTE: For Curb & Gutter Inlets, TC = Top of Curb = Top of Casting

* Compacted Granular Backfill Per Item 912
** Backfill Per Item 911
*** Concrete Encasement Per Item 910
Watertight joints per 901.15 and place trench dams per 901.11

STORM SEWER COORDINATE DATA							
PHASE	STRUCTURE	PROPOSED			AS BUILT		
		NORTHING	EASTING	ELEVATION	NORTHING	EASTING	ELEVATION
1	HW1	765443.1428	1868084.5487	XXX.XX			
	1	765463.1414	1868119.1381	XXX.XX			
	2	765515.8380	1868140.5214	XXX.XX			
	3	765623.4468	1868144.0679	XXX.XX			
	4	765641.4017	1868016.9000	XXX.XX			
	5	765744.2256	1868022.9199	XXX.XX			
	6	765854.9803	1868029.4042	XXX.XX			
	7	765950.8717	1868035.0182	XXX.XX			
	8	766068.6700	1868041.9149	XXX.XX			
	9	766234.4419	1868051.6202	XXX.XX			
	10	766227.4869	1868170.4167	XXX.XX			
	11	766296.3689	1868174.4495	XXX.XX			
	12	766387.2134	1868179.7681	XXX.XX			
	13	766394.1684	1868060.9715	XXX.XX			
14	766551.8983	1868070.2060	XXX.XX				
2	15	766645.0399	1868075.6591	XXX.XX			
	16	766745.6008	1868080.9619	XXX.XX			
1	17	766851.6598	1868083.0556	XXX.XX			
	18	765453.6270	1868144.5450	XXX.XX			
	19	765442.5894	1868173.5139	XXX.XX			
	20	765387.2464	1868171.8527	XXX.XX			
	21	765622.4240	1868161.5380	XXX.XX			
	22	765620.6121	1868192.4850	XXX.XX			
	23	765846.5320	1868174.6587	XXX.XX			
	24	765844.7202	1868205.6057	XXX.XX			
	25	766214.9569	1868196.2285	XXX.XX			
	26	766213.1450	1868227.1755	XXX.XX			
	27	766294.8201	1868200.9042	XXX.XX			
	28	766293.0083	1868231.8512	XXX.XX			
	29	766752.6450	1868833.2432	XXX.XX			
	2	30	766758.9864	1868724.9287	XXX.XX		
31		766760.7982	1868693.9817	XXX.XX			
32		766761.8650	1868675.7609	XXX.XX			
33		766768.4254	1868563.7047	XXX.XX			
34		766826.3468	1868566.7439	XXX.XX			
35		766777.8152	1868403.3220	XXX.XX			
36		766837.9665	1868402.4935	XXX.XX			
37		766943.0988	1868403.6609	XXX.XX			
38		766723.1954	1868831.5190	XXX.XX			
39		766692.2484	1868829.7072	XXX.XX			
40		767113.2193	1868697.0844	XXX.XX			
41		766732.9559	1868664.8045	XXX.XX			
42		766702.0089	1868662.9927	XXX.XX			
43		766732.5518	1868402.2517	XXX.XX			
44		766702.8258	1868411.0473	XXX.XX			
45		766845.1246	1868280.2281	XXX.XX			
1		Ex 4	765278.0020	1867824.6270	XXX.XX		
	46	765276.6194	1867844.5792	XXX.XX			
	47	765325.3081	1867876.0976	XXX.XX			
	EW1	765356.7696	1867896.4641	XXX.XX			
	Ex 2	765374.4739	1867690.9458	XXX.XX			
	48	765501.2345	1867710.4558	XXX.XX			
	HW2	765509.1319	1867762.5710	XXX.XX			

STORM SEWER DATA					
PHASE	STRUCTURE	DIRECTION	DISTANCE	SIZE	
1	HW1-1	N 59°57'53" E	39.95'	36"	
	1-2	N 22°05'11" E	56.87'	36"	
	2-3	N 01°53'16" E	107.67'	30"	
	3-4	N 81°57'49" W	128.43'	30"	
	4-5	N 03°21'02" E	103.00'	30"	
	5-6	N 03°21'02" E	110.94'	30"	
	6-7	N 03°21'02" E	96.06'	30"	
	7-8	N 03°21'02" E	118.00'	30"	
	8-9	N 03°21'02" E	166.06'	30"	
	9-10	S 86°38'58" E	119.00'	24"	
	10-11	N 03°21'02" E	69.00'	24"	
	11-12	N 03°21'02" E	91.00'	24"	
	12-13	S 86°38'58" E	119.00'	24"	
	13-14	N 03°21'02" E	158.00'	18"	
2	14-15	N 03°21'02" E	93.30'	15"	
	15-16	N 03°01'07" E	100.70'	15"	
	16-17	N 01°07'51" E	106.08'	15"	
1	1-18	S 69°28'12" E	27.13'	18"	
	18-19	S 69°28'12" E	31.00'	15"	
	19-20	S 01°43'10" W	55.37'	12"	
	3-21	N 86°38'58" W	17.50'	12"	
	21-22	S 86°38'58" E	31.00'	12"	
	6-23	S 86°40'17" E	145.50'	12"	
	23-24	S 86°38'58" E	31.00'	12"	
	10-25	S 64°06'23" E	28.69'	12"	
	25-26	S 86°38'58" E	31.00'	12"	
	11-27	S 86°38'58" E	26.50'	15"	
	27-28	S 86°38'58" E	31.00'	12"	
	Ex 3B-29	N 86°38'58" W	17.00'	36"	
	29-30	N 86°38'58" W	108.50'	36"	
	30-31	N 86°38'58" W	31.00'	36"	
31-32	N 86°38'58" W	18.25'	36"		
32-33	N 86°38'58" W	112.25'	36"		
33-34	N 03°00'13" E	58.00'	30"		
33-35	N 86°38'58" W	160.66'	30"		
35-36	N 00°47'21" W	60.16'	24"		
36-37	N 00°38'10" E	105.14'	24"		
2	29-38	S 03°21'02" W	29.50'	12"	
	38-39	S 03°21'02" W	31.00'	12"	
	32-40	N 03°28'23" E	352.00'	15"	
	32-41	S 20°45'23" W	30.92'	12"	
	41-42	S 03°21'02" W	31.00'	12"	
	35-43	S 01°21'16" W	45.28'	12"	
	43-44	S 16°28'58" E	31.00'	12"	
	36-45	N 86°38'58" W	122.47'	12"	
	1	Ex 4-46	S 86°02'09" E	20.00'	24"
		46-47	N 32°55'01" E	58.00'	18"
		47-EW1	N 32°55'01" E	37.48'	12"
		Ex 2-48	N 8°44'59" E	128.25'	18"
		48-HW2	N 81°22'59" E	52.71'	12"

* Horizontal Reference Datum = NAD 83 (1986 Adj.) (Ohio South Zone)

HORIZ
SCALE



CALCULATED
CHECKED


STORM
SURVEY COORDINATE DATA

PROJECT NAME




XXXX-E


REVISED 12/2/11



Street Name 1 - Sta. 133+39.44 to Sta. 136+00.00



Street Name 1 - Sta. 136+00.00 to Sta. 138+90.00




Street Name 1 - Sta. 138+90.00 to Sta. 141+80.00

Backfill Shall Be Compacted To The Density Of The Adjacent Suitable Soil Unless Otherwise Noted.

- * Compacted Backfill, Per 801.10
- ** Compacted Granular Backfill, Per 801.09
- *** Flowable Controlled Density Fill, Type III, Per 636.08, 5' min. each side of ex. util crossing.

- # Maintain 18" Vertical Clearance
- † Anti-Infiltration and Inflow Barrier
- ** Maintain a Minimum 4' of Cover When Crossing Over Sanitary and Storm Sewers
- § Denotes Actual Water Service Size is not Known. Size has been Assumed as 3/4 inch. Contractor Shall Match Existing Service Size as Determined Upon Excavation.


Note: Ex. water service and water main elevations are assumed. Contractor to field verify elevations and provide a minimum one foot clearance between the existing and proposed water main.



WATER PROFILE - STREET NAME 1
- STA. 133+39.44 TO STA. 141+80.00

PROJECT NAME

XXXX-E



WATERLINE SURVEY COORDINATE DATA

PROJECT NAME



STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	16"x12" Tapping Sleeve & Valve	133+39.09	733790.2523	1837620.9458	850.94		
2	22.5" Bend (Horiz)	133+44.72	733787.6374	1837626.4294	850.90		
3	3/4" WS (Short)	134+30.00	733782.5933	1837712.0123	849.23		
4	Grade Break Use Joint Defl (Vert)	134+70.00	733780.2664	1837751.4926	848.45		
5	Grade Break Use Joint Defl (Vert)	135+00.00	733778.5013	1837781.4406	848.45		
6	3/4" WS (Long)	135+23.00	733777.1246	1837804.7991	848.13		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	3/4" WS (Short)	135+38.00	733776.2543	1837819.5648	847.92		
2	3/4" WS (Long)	135+57.00	733775.1396	1837838.4785	847.65		
3	12"x6" Anchor Tee	135+70.00	733774.3827	1837851.3194	847.47		
4	22.5" Bend (Horiz)	135+75.00	733744.0886	1837856.3107	847.40		
5	3/4" WS (Short)	135+87.00	733768.4036	1837868.0326	845.59		
6	3/4" WS (Long)	135+95.00	733766.3149	1837872.3390	844.38		
7	22.5" Bend (Horiz)	135+99.14	733762.6854	1837879.8227	843.75		
8	1" WS (Short)	136+20.00	733781.4581	1837900.6464	843.75		
9	3/4" WS (Long)	136+28.00	733760.9878	1837908.6271	843.75		
10	1" WS (Short)	136+58.00	733759.2194	1837938.6304	843.75		
11	3/4" WS (Long)	136+68.00	733758.6283	1837948.6596	843.75		
12	3/4" WS (Short)	136+85.00	733757.6335	1837965.1008	843.75		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	3/4" WS (Long)	137+34.00	733754.7202	1838014.9676	843.75		
2	12"x6" Tee	137+66.16	733752.8585	1838046.5550	843.75		
3	45" Bend (Vert)	137+71.35	733752.5534	1838051.7322	843.75		
4	45" Bend (Vert)	137+75.00	733752.3386	1838055.3759	840.10		
5	45" Bend (Vert)	137+85.38	733751.7279	1838065.7379	840.10		
6	45" Bend (Vert)	137+90.00	733751.4561	1838070.3499	844.72		
7	3/4" WS (Long)	137+99.00	733750.9074	1838079.6586	844.86		
8	12" Valve w/ Cols. Std HD Valve Box	138+04.32	733750.6132	1838084.6500	844.95		
9	3/4" WS (Long)	138+21.00	733749.6170	1838101.5536	845.21		
10	3/4" WS (Short)	138+83.00	733745.9658	1838163.5023	846.19		
11	3/4" ARO w/ Ferrule Box	138+95.00	733745.2783	1838175.1680	846.38		
12	22.5" Bend (Vert)	139+00.00	733744.9841	1838180.1593	846.46		
13	22.5" Bend (Vert)	139+05.00	733744.6899	1838185.1507	844.39		
14	22.5" Bend (Vert)	139+10.14	733744.3875	1838190.2818	844.39		
15	22.5" Bend (Vert)	139+15.00	733744.1015	1838195.1333	846.40		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	3/4" WS (Short)	139+37.00	733742.7819	1838217.5239	846.40		
2	12"x6" Anchor Tee	139+88.00	733739.8062	1838268.0106	846.40		
3	45" Bend (Vert)	140+16.96	733738.1026	1838296.9167	846.40		
4	45" Bend (Vert)	140+24.56	733737.6554	1838304.5035	838.80		
5	Horiz Bend Use Joint Defl	140+29.56	733737.3607	1838309.5042	838.80		
6	45" Bend (Vert)	140+50.42	733736.0896	1838330.3388	838.80		
7	45" Bend (Vert)	140+57.28	733735.6719	1838337.1861	845.66		
8	45" Bend (Vert)	141+00.00	733733.0704	1838379.8268	844.23		
9	45" Bend (Vert)	141+03.63	733732.8494	1838383.4501	840.60		
10	45" Bend (Vert)	141+09.32	733732.5029	1838389.1295	840.60		
11	45" Bend (Vert)	141+15.00	733732.1570	1838394.7990	842.95		
12	3/4" ARO w/ Ferrule Box	141+20.00	733731.8525	1838399.7897	842.78		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	11.25" Bend (Vert)	142+12.27	733726.2337	1838491.8885	839.70		
2	12"x6" Tee	142+17.55	733725.9123	1838497.1561	838.71		
3	2" WS (Long)	142+21.00	733725.7293	1838500.1506	837.76		
4	11.25" Bend (Vert)	142+46.46	733724.1517	1838526.0150	832.90		
5	45" Bend (Vert)	142+61.30	733723.2480	1838540.8275	832.90		
6	45" Bend (Vert)	142+65.00	733723.0227	1838544.5206	836.60		
7	12" Valve w/ Cols. Std HD Valve Box	142+74.09	733722.4692	1838553.5937	836.60		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	12"x6" Anchor Tee	143+32.00	733718.9427	1838611.3963	836.60		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	3/4" WS (Long)	146+20.00	733701.4045	1838898.8684	836.60		
2	12"x6" Anchor Tee	146+82.00	733697.6297	1838960.7421	836.60		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	22.5" Bend (Vert)	147+27.50	733694.8587	1839006.1623	836.60		
2	22.5" Bend (Vert)	147+32.67	733694.5439	1839011.3227	838.74		
3	3/4" WS (Long)	147+73.00	733692.0777	1839051.7456	839.34		
4	3/4" WS (Short)	147+76.00	733691.9172	1839054.3773	839.39		
5	3/4" WS (Long)	147+87.00	733691.2235	1839065.7475	839.56		
6	22.5" Bend (Vert)	147+98.73	733690.5211	1839077.2601	839.73		
7	22.5" Bend (Vert)	148+02.50	733690.2916	1839081.0231	838.17		
8	22.5" Bend (Vert)	148+07.50	733689.9871	1839086.0138	838.17		
9	22.5" Bend (Vert)	148+12.50	733689.6826	1839091.0045	840.24		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	3/4" WS (Long)	148+63.00	733686.6249	1839141.1242	841.01		
2	22.5" Bend (Vert)	149+02.05	733684.2294	1839180.3883	841.59		
3	22.5" Bend (Vert)	149+09.50	733683.7758	1839187.8245	838.50		
4	22.5" Bend (Vert)	149+14.50	733683.4713	1839192.8152	838.50		
5	22.5" Bend (Vert)	149+21.86	733683.0231	1839198.3050	841.55		
6	12" Valve w/ Cols. Std HD Valve Box	149+75.58	733679.7519	1839200.1616	841.55		
7	12"x12" Tee	149+96.47	733678.4798	1839274.6319	841.55		
8	12" Valve w/ Cols. Std HD Valve Box	150+09.96	733677.6595	1839288.0974	841.55		
9	12"x6" Tee	150+16.88	733677.2394	1839284.9992	841.55		
10	12" Valve w/ Cols. Std HD Valve Box	150+37.00	733676.0168	1839315.0866	841.55		
11	12"x6" Anchor Tee	150+66.00	733674.2551	1839344.0311	841.55		
12	3/4" WS (Short)	151+06.00	733671.8240	1839383.9748	841.55		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	3/4" WS (Short)	151+50.00	733669.1293	1839428.2486	841.55		
2	3/4" WS (Long)	151+56.00	733668.8085	1839433.5193	841.55		
3	22.5" Bend (Vert)	151+56.96	733668.7290	1839434.8250	841.55		
4	22.5" Bend (Vert)	151+65.00	733668.2406	1839442.8502	838.22		
5	22.5" Bend (Vert)	151+70.00	733667.9368	1839447.8410	838.22		
6	22.5" Bend (Vert)	151+76.82	733667.5346	1839454.4487	840.96		
7	3/4" WS (Short)	151+81.00	733667.2853	1839458.5446	840.88		
8	3/4" ARO w/ Ferrule Box	151+82.00	733667.2023	1839459.9086	840.84		
9	3/4" WS (Short)	152+23.00	733664.7126	1839500.8136	839.92		
10	22.5" Bend (Vert)	152+48.26	733663.1823	1839525.9564	839.35		
11	22.5" Bend (Vert)	152+54.00	733662.8336	1839531.6858	836.97		
12	22.5" Bend (Vert)	152+59.00	733662.5299	1839536.6766	836.97		
13	22.5" Bend (Vert)	152+66.11	733662.0799	1839543.7734	839.91		
14	3/4" ARO w/ Ferrule Box	152+71.11	733661.7942	1839548.7642	839.89		
15	3/4" WS (Short)	152+76.00	733661.5015	1839553.5721	839.87		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	3/4" WS (Short)	153+41.00	733657.5526	1839618.4521	839.55		
2	22.5" Bend (Vert)	153+61.11	733656.3265	1839638.5980	839.44		
3	3/4" WS (Short)	153+66.00	733656.0055	1839643.8720	837.41		
4	22.5" Bend (Vert)	153+67.00	733655.9686	1839644.4771	837.00		
5	22.5" Bend (Vert)	153+72.00	733655.6649	1839649.4678	837.00		
6	22.5" Bend (Vert)	153+79.73	733655.1953	1839657.1836	840.20		
7	3/4" WS (Short)	154+31.00	733652.0978	1839708.0749	840.20		
8	3/4" WS (Short)	154+65.00	733649.9910	1839742.6891	840.20		
9	12"x6" Anchor Tee	154+70.00	733649.7112	1839747.2868	840.20		
10	12" Valve w/ Cols. Std HD Valve Box	154+85.00	733648.7999	1839762.2591	840.20		
11	11.25" Bend (Vert)	154+94.97	733648.1942	1839772.2107	840.20		
12	11.25" Bend (Vert)	155+00.00	733647.8886	1839777.2314	841.20		

STREET NAME 1							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	45" Bend (Horiz)	155+07.59	733647.4275	1839784.8074	841.20		
2	12"x6" Reducer	155+07.59	733647.4275	1839784.8074	841.20		
3	45" Bend (Horiz)	155+11.00	733650.6211	1839788.4149	841.20		

STREET NAME 2							
PROPOSED				AS-BUILT			
REF	ITEM	STATION	NORTHING	EASTING	ELEVATION	NORTHING	EASTING
1	11.25" Bend (Horiz)	0+11.45	733729.5072	1838497.0996	838.71		
2	22.5" Bend (Vert)	0+23.02	733740.7054	1838499.9960	838.71		
3	22.5" Bend (Vert)	0+26.38	733743.9584	1838500.8374	837.32		
4	Grade Break Use Joint Defl (Vert)	0+32.36	733749.7479	1838502.3348			




CALCULATED
CHECKED

PAVEMENT MARKING AND SIGNING

PROJECT NAME

XXXX-E



EXISTING RPM'S HAVE BEEN INSTALLED WITH THIS PROPOSED LANE USE CONSIDERED. ALL EXISTING RPM'S SHALL REMAIN. SEE XXXX DR E

LEGEND

- (CH) PROPOSED PAVEMENT MARKINGS
- (DY) EXISTING PAVEMENT MARKINGS (TO REMAIN)
- [] PROPOSED SIGN
- [] EXISTING SIGN

LINE SPECIFICATIONS

WE	EDGE LINE, WHITE	SL	STOP LINE, 20" WHITE
YE	EDGE LINE, YELLOW	XW	CROSSWALK LINE, 10" WHITE
LL	LANE LINE, 5" YELLOW	WT	TRANSVERSE LINE, 20" WHITE
DY	CENTER LINE, 5" SOLID DOUBLE	YT	TRANSVERSE LINE, 20" YELLOW
		WCM	CURB MARKING, WHITE
CSD	CENTER LINE, 5" SOLID & DASHED	YCM	CURB MARKING, YELLOW
		WIM	ISLAND MARKING, WHITE
CD	CENTER LINE, 5" DASHED SINGLE	YIM	ISLAND MARKING, YELLOW
		WD	DOTTED LINE, 4" WHITE
CH	CHANNELIZING LINE, 10" WHITE	YD	DOTTED LINE, 4" YELLOW
		RM	REMOVAL OF PAVEMENT MARKINGS

*STOP SIGN SHALL REMAIN UNTIL NEW SIGNAL IS IN OPERATION.

SUB-SUMMARY OF TRAFFIC CONTROL ITEMS

ITEM NUMBER	QUANTITY	UNIT	ITEM DESCRIPTION	REFERENCE SHEET
202	43	EA	RAISED PAVEMENT MARKER REMOVED	
621	52	EA	RPM	
630	112	LF	GROUND MOUNTED SUPPORT, NO 3 POST, AS PER PLAN	
630	32.5	SF	SIGN, FLAT SHEET, TYPE G, AS PER PLAN	5
630	5	EA	REMOVAL OF GROUND MOUNTED SUPPORT AND DISPOSAL	
630	3	EA	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	
644	164	LF	CENTER LINE, 5", SOLID DOUBLE	
644	868	LF	CHANNELIZING LINE	
644	64	LF	STOP LINE	
644	380	LF	CROSSWALK LINE	
644	11	EA	LANE ARROW	
644	4	EA	WORD ON PAVEMENT	
644	133	LF	DOTTED LINE, 4"	
644	1171	LF	REMOVAL OF PAVEMENT MARKINGS	
644	3	EA	REMOVAL OF PAVEMENT MARKINGS	

GENERAL

THESE SPECIFICATIONS, TOGETHER WITH THE ACCOMPANYING PLANS ARE INTENDED TO DESCRIBE THE TYPE, SIZE AND LOCATION OF THE PRODUCTS AND MATERIALS TO BE PROVIDED AND INSTALLED UNDER THE VARIOUS BID ITEMS RELATED TO TRAFFIC CONTROL. THE CONTRACTOR SHALL FURNISH AND INSTALL TRAFFIC CONTROL DEVICES AND RELATED MATERIALS IN COMPLIANCE WITH THESE PLANS AND SPECIFICATIONS, AS WELL AS THE XXXX CITY OF COLUMBUS CONSTRUCTION AND MATERIAL SPECIFICATIONS, THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, THE STANDARD CONSTRUCTION DRAWINGS ISSUED BY THE CITY OF COLUMBUS AND THE STANDARD CONSTRUCTION DRAWINGS ISSUED BY THE OHIO DEPARTMENT OF TRANSPORTATION. THESE SPECIFICATIONS SET FORTH THE MINIMUM PERFORMANCE AND OPERATING REQUIREMENTS OF THE TRAFFIC CONTROL ITEMS REFERRED TO HEREIN.

EXISTING UTILITIES

THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN ON THESE PLANS ARE OBTAINED FROM THE OWNERS OF THE UTILITIES AS REQUIRED BY THE OHIO REVISED CODE SECTION 153.64

THE TRANSPORTATION DIVISION OR THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THE LOCATION OR THE DEPTHS OF THE UNDERGROUND FACILITIES SHOWN ON THESE PLANS. SUPPORT, PROTECTION, AND RESTORATION OF ALL EXISTING UTILITIES AND APPURTENANCES SHALL BE THE CONTRACTOR'S RESPONSIBILITY. THE COST OF THIS WORK SHALL BE INCLUDED IN THE BID PRICE FOR THE VARIOUS ITEMS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE OHIO UTILITIES PROTECTION SERVICE (OUPS) AND THE FOLLOWING UTILITIES SO THEIR RESPECTIVE UTILITIES CAN BE MARKED. THE PROJECT ENGINEER SHALL NOT AUTHORIZE THE START OF ANY SIGNAL UNDERGROUND WORK UNTIL ALL UTILITIES HAVE BEEN MARKED.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE OHIO UTILITIES PROTECTION SERVICE (OUPS) AND THE UTILITIES NAMED BELOW SO THEIR RESPECTIVE FACILITIES CAN BE MARKED PRIOR TO CONSTRUCTION.

UTILITY	OWNER	TELEPHONE
Telephone Facilities*	AT&T ATTN. MR. TOM ZIOMEK MANAGER OSPE 111 NORTH 4TH STREET COLUMBUS, OHIO 43215	PHONE: (614) 223-7162 FAX: (614) 223-5579 TZ7315@SBC.COM
Cable Facilities	INSIGHT COMMUNICATIONS ATTN. MR. PAUL SIEMER DIRECTOR OF CONSTRUCTION 3770 EAST LIVINGSTON AVENUE COLUMBUS, OHIO 43227	PHONE: (614) 501-9432 EXT-207 FAX: (614) 501-9513 SIEMER.P@INSIGHT-COM.COM
	WIDE OPEN WEST ATTN. JAYTEE NOVARIA CONSTRUCTION SUPERVISOR 3675 CORPORATE DRIVE COLUMBUS, OHIO 43231	PHONE: (614) 948-4653 FAX: (614) 948-4620 JNOVARIA@WIDEOPENWAST.COM
Electric Facilities	AEP- AMERICAN ELECTRIC POWER (TRANSMISSION) ATTN. TINA HAIRSTON 700 MORRISON ROAD GAHANNA, OHIO 43230	PHONE: (614) 552-1801 FAX: (614) 552-1818 TLHAIRSTON@AEP.COM
	AEP- AMERICAN ELECTRIC POWER (DISTRIBUTION) ATTN. MR. ROD SLONEKER ENGINEERING LIAISON COORDINATOR 850 TECH CENTER DRIVE GAHANNA, OHIO 43230	PHONE: (614) 883-6817 FAX: (614) 883-6868 RISLONEKER@AEP.COM
	City of Columbus Attn. Jeff Holmes Business Manager (Division of Power & Water--Power) 3568 Indianola Avenue Columbus, Ohio 43214	PHONE: (614) 645-7627 FAX: (614) 645-7150 JHOLMES@COLUMBUS.GOV
Gas Facilities	COLUMBIA GAS OF OHIO ATTN. MR. SCOTT BAKER SENIOR ENGINEER 920 W. GOODALE BOULEVARD COLUMBUS, OHIO 43212	PHONE: (614) 460-2338 CELL: (614) 989-1325 SBBAKER@NISOURCE.COM
Water Facilities	CITY OF COLUMBUS ATTN. BOB ARNOLD, P.E. DESIGN ENGINEER (DIV. OF POWER&WATER-WATER) 910 DUBLIN ROAD COLUMBUS, OHIO 43215	PHONE: (614) 645-7788 FAX: (614) 645-0220 RJARNOLD@COLUMBUS.GOV
Sanitary Sewer & Storm Sewer	CITY OF COLUMBUS (DIV. OF SEWERAGE & DRAINAGE) 910 DUBLIN ROAD COLUMBUS, OHIO 43215	PHONE: (614) 645-7102 FAX: (614) 645-3242

* - EXISTING UNDERGROUND TELEPHONE CONDUIT WAS PLACED IN 1953 AND IS FRAGILE. IF DAMAGED, CONTRACTOR SHOULD CALL CONNIE HORNER AT (614) 223-6985 OR ROGER RADER AT (614) 256-1290 IMMEDIATELY FOR REPAIRS

THE FOLLOWING CITY OF COLUMBUS UTILITIES ARE LOCATED WITHIN THE WORK LIMITS OF THE PROJECT AND DO NOT SUBSCRIBE TO A REGISTERED UNDERGROUND PROTECTION SERVICE:

CITY OF COLUMBUS DIV. OF PLANNING & OPERATIONS 1820 E. 17TH AVE. COLUMBUS, OHIO 43219 TELEPHONE 645-7393 FAX 645-5967	CITY OF COLUMBUS COMMUNICATIONS DIVISION 220 GREENLAWN AVENUE COLUMBUS, OHIO 43223 TELEPHONE 645-7344 EXT. 125 FAX 645-6588
CITY OF COLUMBUS DEPT. OF TECHNOLOGY 90 W. BROAD STREET COLUMBUS, OHIO 43215 TELEPHONE 645-1501 FAX 645-6627	

FAX ALL REQUESTS TWO (2) WORKING DAYS PRIOR TO THE START OF CONSTRUCTION.



FOR THE DIVISION OF POWER AND WATER

THE DIVISION OF POWER AND WATER (POWER), CITY OF COLUMBUS, OHIO, HAS UNDERGROUND PRIMARY AND STREET LIGHTING IN THE PROJECT AREA. THE CONTRACTOR IS HEREBY REQUIRED TO CONTACT THE DIVISION OF POWER AND WATER BY FAX (614) 645-7150 FORTY-EIGHT HOURS PRIOR TO CONDUCTING ANY ACTIVITY WITHIN THE CONSTRUCTION AREA. THE DOPW DISPATCH OFFICE NUMBER IS: (614) 645-7627 (VOICE).

ANY REQUIRED RELOCATION, SUPPORT, PROTECTION, OR RELATED ACTIVITY CONCERNED WITH THE CITY'S ELECTRICAL FACILITIES IS TO BE PERFORMED SOLELY BY THE CONTRACTOR UNDER THE DIRECTION OF DIVISION OF POWER AND WATER (DOPW) PERSONNEL AND AT THE EXPENSE OF THE PROJECT. DOPW SHALL MAKE ALL FINAL CONNECTIONS TO DOPW'S EXISTING ELECTRICAL SYSTEM AT THE EXPENSE OF THE PROJECT. THE CONTRACTOR SHALL USE MATERIAL AND MAKE REPAIRS TO A CITY OF COLUMBUS STREET LIGHTING SYSTEM BY FOLLOWING THE DIVISION OF POWER AND WATER'S "MATERIAL AND INSTALLATION SPECIFICATIONS" (MIS) AND THE CITY OF COLUMBUS "CONSTRUCTION AND MATERIAL SPECIFICATIONS" (CMS). ANY NEW OR RE-INSTALLED UNDERGROUND STREETLIGHT SYSTEM SHALL REQUIRE TESTING AS REFERRED TO IN SECTION 1000.18 OF THE CMS MANUAL.

THE CONTRACTOR SHALL CONFORM TO THE DIVISION OF POWER AND WATER'S POLICIES FOR CONTRACTOR SAFETY AND HOLD CARD SYSTEM (MIS-95), COPIES OF WHICH ARE AVAILABLE FROM THE DIVISION OF POWER AND WATER. IF YOU HAVE ANY QUESTIONS, CALL CHRIS VOGEL (614) 645-6963 OR MIHAI ORBOCEA (614) 645-6851 FOR LIGHTING. IF ANY ELECTRIC FACILITY BELONGING TO THE DIVISION OF POWER AND WATER IS DAMAGED IN ANY MANNER BY THE CONTRACTOR, ITS AGENTS, SERVANTS, OR EMPLOYEES, AND REQUIRES EMERGENCY REPAIRS, THE DIVISION OF POWER AND WATER SHALL MAKE ALL NECESSARY REPAIRS, AND THE EXPENSE OF SUCH REPAIRS AND OTHER RELATED COSTS SHALL BE PAID BY THE CONTRACTOR TO THE DIVISION OF POWER AND WATER, CITY OF COLUMBUS, OHIO.

PLAN AND SPECIFICATION COMPLIANCE

THE CONTRACTOR SHALL FURNISH AND INSTALL TRAFFIC SIGNAL DEVICES IN COMPLIANCE WITH THESE PLANS AND SPECIFICATIONS, THE 2008 ODOT CONSTRUCTION AND MATERIAL SPECIFICATIONS AND ITS SUPPLEMENTAL SPECIFICATIONS, OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, AND THE "TC" STANDARD CONSTRUCTION DRAWINGS ISSUED BY THE ODOT OFFICE OF TRAFFIC ENGINEERING (SUPPLEMENTS THE PLAN SPECIFICATIONS). THE CITY OF COLUMBUS, TRANSPORTATION DIVISION, SHALL DETERMINE WHETHER THE SUPPLIED ITEMS MEET OR EXCEED THESE SPECIFICATIONS.

TRAFFIC SIGNAL CONTROL EQUIPMENT SHALL MEET OR EXCEED THE STANDARDS SPECIFIED IN THE FOLLOWING DOCUMENTS.

- (a) SPECIFICATIONS LISTED IN THIS PLAN;
- (b) APPLICABLE SECTIONS OF NEMA STANDARDS PUBLICATION NO. TS2-1998 AND/OR TS1-1989;
- (c) XXXX CITY OF COLUMBUS CONSTRUCTION AND MATERIAL SPECIFICATIONS 625, 632, 633, 725, 732 & 733; OTHER CITY OF COLUMBUS DRAWINGS AND SUPPLEMENTALS.
- (d) 2010 ODOT CMS 625,632,633,725,732 & 733; OTHER ODOT DRAWINGS AND SUPPLEMENTALS.

IN CASE OF A CONFLICTING SPECIFICATION STATEMENT, THE SPECIFICATION DOCUMENT HIERARCHY SHALL BE IN THE ORDER LISTED FROM (a), HIGHEST, TO (d), LOWEST.

GROUNDING AND BONDING

The requirements of the ODOT Construction and Material Specifications (C&MS) and the HL and TC series of Standard Construction Drawings are modified as follows:

1. All metallic parts containing electrical conductors shall be permanently joined to form an Effective Ground Fault Current Path back to the grounded conductor in the power service disconnect switch.
 - I. Provide an equipment grounding conductor in metallic conduits (725.04) in addition to the conductors specified and bond the conduit to this grounding conductor.
 - II. When an equipment grounding conductor is required in plastic conduit (725.05), the installation shall include a separate equipment grounding conductor in addition to the conductors specified.
 - III. Metallic conduit carrying the loop wires from in the pavement to the pull box splice location will only be bonded at the pull box end, and will not contain an equipment grounding conductor.
 - IV. Metal pull box lids shall be bonded by attachment of the equipment grounding conductor to the frame diagonal as provided on HL-30.11.
 - V. If multiple conduit runs begin and end at the same points, only one equipment grounding conductor is required.
 - VI. The messenger wire at signalized intersections will be used as the conductive path from corner to corner if conduit is not provided under the roadway. When conduit connects the corners of an intersection, an equipment grounding conductor shall be used in the conduit.

2. Conduits.

- a. The 725.04 conduit shall have grounding bushings installed at all termination points. The bushing material shall be compatible with galvanized steel conduit and the grounding lug material shall be compatible for use with copper wire. Threaded or compression type bushings may be used.
- b. The 725.05 conduit shall have the inside and outside diameters of the conduit deburred at all termination points.
- c. Both ends of metallic conduit shall be bonded to the equipment grounding conductor.
- d. Metallic conduit may be bonded to metallic boxes through the use of conduit fittings UL approved for this type of connection, with the box bonded to the equipment grounding conductor.

ITEM 632 STRAIN POLE FOUNDATION, AS PER PLAN

THE ANCHOR BASE POLE FOUNDATION SIDES SHALL BE ORIENTATED PARALLEL TO THE SIDEWALK OR BACK-OF-CURB OR EDGE-OF-PAVEMENT AS SHOWN ON THE SIGNAL PLANS. THE TOP OF THE FOUNDATION SHALL BE FLUSH WITH ANY ADJACENT SIDEWALK OR CONCRETE AREA EXCEPT WHERE THE GROUND RISES STEEPLY BEHIND THE SIDEWALK OR CONCRETE AREA. THEN THE BACK SIDE OF THE FOUNDATION SHALL MATCH THE GROUND SLOPE AND THE STREET SIDE OF THE FOUNDATION SHALL BE ABOVE THE SIDEWALK OR CONCRETE AREA AND COMPLETELY OUT OF THE SIDEWALK OR CONCRETE AREA. A MINIMUM OF TWO 2" CONDUIT ELLS, USED OR UNUSED, SHALL BE INSTALLED IN EACH POLE FOUNDATION. SEE POLE ORIENTATION CHART FOR ANGULAR POSITION. THE ANCHOR BOLTS AND CONDUIT ELLS ARE INCIDENTAL TO THIS ITEM. THE POLE FOUNDATION TOP SHALL BE EDGED USING A 1/2" SIDEWALK EDGER AND NOT CHAMFERED.

PAYMENT SHALL BE AS PER ITEM 632.

ITEM 632 SLEEVE FOR ANCHOR BASE FOUNDATION, AS PER PLAN

A GALVANIZED CORRUGATED PIPE OR A CARDBOARD-LIKE CONCRETE FORM WITH THE SAME DIAMETER AND DEPTH DIMENSIONS AS THE SPECIFIED FOUNDATION SHALL BE USED AT THE DISCRETION OF THE PROJECT ENGINEER OR AS CALLED FOR IN THE PLANS. THE SLEEVE SHALL BE MEASURED AS A COMPLETE UNIT INSTALLED AND PROPERLY BACKFILLED. BACKFILL SHALL BE A COMPACTABLE GRANULAR MATERIAL THAT IS COMPACTED IN 4" LIFTS OR CONTROLLED DENSITY FILL RATED AT 150 PSI.

PAYMENT SHALL BE PER EACH.

ITEM 632 STRAIN POLE, TYPE TC-81.10, ANCHOR BASE, (BY SIZE), AS PER PLAN

STRAIN POLES SHALL BE MANUFACTURED BY UNION METAL OR VALMONT ONLY. THE POLES SHALL BE GALVANIZED, THEN COATED WITH A SEMI-GLOSS, DARK BRONZE POWDER COATING FINISH. THE GALVANIZING SHALL BE PROPERLY PREPARED SO THE POWDER COATING WILL ADHERE TO THE GALVANIZING.

THE POLE SHAFT SHALL:

1. BE MADE OF WELDABLE GRADE, HOT ROLLED COMMERCIAL QUALITY CARBON STEEL FORMED WITH A BASE DIAMETER AND HEIGHT AS PER PLAN.
2. BE CONTINUOUSLY TAPERED FROM THE POLE BOTTOM TO THE POLE TOP AT A RATE OF 0.14 INCH PER FOOT.
3. BE CONSTRUCTED WITH ONE (1) LONGITUDINAL AUTOMATICALLY, ELECTRICALLY WELDED SEAM.
4. BE CONSTRUCTED USING A CONTINUOUS NON-OVERLAPPING TAPERED TUBE.

5. CONFORM TO ASTM-A572 GRADE 55 OR ASTM-A595 GRADE A (55,000 PSI MINIMUM YIELD STRENGTH AFTER FABRICATION) OR ASTM-A572 GRADE 65 AS PER PLAN DESIGN REQUIREMENTS.
6. HAVE 1 OR 2 HANDHOLES, AS PER PLAN DESIGN, EACH COMPLETE WITH A COVER, A RECTANGULAR OR ELLIPTICAL REINFORCED FRAME, AND A STAINLESS STEEL FASTENER FOR THE COVER. THE FASTENER SHALL BE FLUSH WITH THE HANDHOLE SURFACE. THE HANDHOLES SHALL BE LOCATED AS PER PLAN.
 - A) THE TOP HANDHOLE SHALL HAVE A MINIMUM INSIDE OPENING OF 4" X 6" AND BE SIMILAR IN DESIGN TO THE BOTTOM HANDHOLE EXCEPT THAT NO GROUNDING PROVISION IS REQUIRED.
 - B) THE BOTTOM HANDHOLE SHALL HAVE A MINIMUM INSIDE OPENING OF 5" X 8". A GROUNDING BOLT CAPABLE OF ACCEPTING FOUR (4) #4 AWG AND TWO (2) #8 AWG COPPER GROUNDING WIRE LUGS SHALL BE ATTACHED TO THE POLE FRAME.
7. HAVE A REMOVABLE POLE CAP ATTACHED EITHER BY A MINIMUM OF 3 STAINLESS STEEL SET SCREWS OR BY A STAINLESS STEEL THROUGH BOLT.
8. HAVE 1 OR 2 WELDED CABLE SUPPORT HOOKS ('J' OR 'C' HOOKS) LOCATED ON THE INSIDE OF THE POLE.
9. BE TELESOPED THROUGH A BASE PLATE THAT HAS A BOLT PATTERN AS PER PLAN.

THE POLE BASE PLATE SHALL:

1. BE FABRICATED FROM ASTM-A36 STEEL (36K PSI) OR ASTM-A42 STEEL (42K PSI) AS PER PLAN DESIGN REQUIREMENTS.
2. TELESOPED THE POLE SHAFT AND BE WELDED TO THE POLE BY MEANS OF 2 CONTINUOUS WELDS--ONE ON THE INSIDE OF THE BASE PLATE AT THE END OF THE POLE SHAFT AND THE OTHER ON THE OUTSIDE AT THE TOP OF THE BASE PLATE. ALL INSIDE WELDS SHALL BE VOID OF SHARP EDGES. ALL OUTSIDE WELDS SHALL BE ROLLED OR GROUND SMOOTH.
3. CONFORM TO THE BOLT PATTERN AS PER PLAN.

ANCHOR BOLTS SHALL HAVE ROLLED THREADS FOR ALL POLE DESIGNS UP TO AND INCLUDING D11. CUT THREADS ARE TO BE USED FOR 2.5" DIAMETER BOLTS OR LARGER. THE BOLTS CAN BE A36/M55 FOR DESIGN 7" OR SMALLER POLES. FOR LARGER POLES THE ANCHOR BOLTS SHALL MEET ODOT REQUIREMENTS OR BE AS SPECIFIED BY THE MANUFACTURER. BOLT-NUT COVERS SHALL BE INSTALLED.

EACH ANCHOR BOLT SHALL:

1. CONFORM TO ASTM-F1554 GRADE 105.
2. BE GALVANIZED PER ASTM-A153.
3. COME WITH 2 HEX NUTS MEETING ASTM-F563 GRADE DH, ANSI B18.2.2 AND SHALL HAVE ANSI B1.1 CLASS 2 UNC ROLLED THREADS. A WASHER AND LOCKWASHER SHALL ALSO BE PROVIDED. HARDWARE SHALL BE HD GALVANIZED PER ASTM-A153.
4. HAVE DIMENSIONS AS PER PLAN.

STRAIN POLE STRUCTURE SURFACES SHALL BE PREPARED FOR GALVANIZING BY USING A SOLVENT CLEANING METHOD TO REMOVE DIRT, OIL, DUST, GREASE AND ANY OTHER CONTAMINANT THAT WILL REDUCE THE ADHESION OF THE GALVANIZING. MILL SCALE, RUST OR ANY OTHER FOREIGN MATERIAL NOT REMOVED BY SOLVENTS SHALL BE REMOVED USING MECHANICAL METHODS (PER STEEL STRUCTURES PAINTING COUNCIL, SSPC-VIS-1-67.). MANUFACTURER RECOMMENDED ABRASIVE TECHNIQUES SHALL BE USED TO PROVIDE THE PROPER PROFILE FOR ADHERENCE TO ASTM A123 GALVANIC COATING.

THE STRAIN POLE STRUCTURE SHALL THEN BE COATED AS PER PLAN. EACH COATING LAYER SHALL BE PROPERLY CURED BEFORE THE APPLICATION OF THE NEXT COAT. MINIMUM DRY THICKNESS MEASUREMENTS FOR STEEL SHALL CONFORM TO SECTION SSPC-PA2-82, STEEL STRUCTURES PAINTING COUNCIL.

ALL STRUCTURAL STEEL PRODUCTS SHALL BE GALVANIZED ON THE INTERIOR AND EXTERIOR SURFACES AS PER ASTM A123. THE EXTERIOR SURFACE OF ALL STRUCTURAL STEEL AND ALUMINUM PRODUCTS SHALL BE PROPERLY PREPARED FOR THE APPLICATION OF AN EXTERIOR COATING. THE COATING COLOR ON BOTH STEEL AND ALUMINUM PRODUCTS SHALL MATCH EACH OTHER. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT BOTH PRODUCT MANUFACTURERS MATCH COATING COLORS SO THAT AN EXCELLENT LOOKING END PRODUCT IS ACHIEVED.

ALL EXTERIOR SURFACES OF THE STRAIN POLE STRUCTURE, ALL BOLT COVERS, ALL ATTACHMENT HARDWARE, ALL WIRE ENTRANCES, ALL SPAN WIRE CLAMPS, ALL HANDHOLE COVERS, BRACKETS, POLE CAPS AND TRAFFIC PEDESTAL STRUCTURES SHALL HAVE A COATING APPLIED TO THEM. EXTERIOR SURFACES OF ALL BOLT AND SCREW FASTENERS, WASHERS, NUTS, AND OTHER ATTACHMENT HARDWARE SHALL HAVE A COATING APPLIED TO THEM. FASTENER THREADS SHALL NOT BE CLOGGED WITH COATING MATERIAL.

THE EXTERIOR COATING FOR ALL ITEMS LISTED IN THE PREVIOUS PARAGRAPH SHALL:

1. MEET FEDERAL STANDARD #595B AND CONFORM TO COLOR #20040.
2. BE APPLIED OVER PROPERLY PREPARED GALVANIZING MATERIAL ON STEEL PRODUCTS AND OVER PROPERLY PREPARED ALUMINUM FOR ALUMINUM PRODUCTS.

CALCULATED
CHECKED

TRAFFIC SIGNAL GENERAL NOTES

PROJECT NAME

X
XX

XXXX-E

3. HAVE A MINIMUM 5-YEAR REPAIR WARRANTY OF COATING DELAMINATION, BLISTERING, OR CORROSION. POWDER COATED UNION METAL STRUCTURES SHALL HAVE THE THOMARIOS COATING WARRANTY REVISION DATE JULY 17, 2007. POWDER COATED VALMONT STEEL STRUCTURES SHALL BE COATED WITH FINISH SPECIFICATION F-573 DATED APRIL 11, 2007, WHICH INCLUDES EPOXY POWDER PRIME COAT AND PENTABOND POWDER FINISH COAT.

ALL COATED ITEMS SHALL BE SHIPPED IN A MANNER SELECTED BY THE MANUFACTURER, WHICH WILL PROTECT MATERIAL FROM DAMAGE DURING DELIVERY. MATERIALS DAMAGED IN TRANSIT SHALL BE REPAIRED OR REPLACED. ALL COSTS ASSOCIATED WITH CORRECTING DAMAGED MATERIAL SHALL BE BORNE BY THE CONTRACTOR. PAYMENT SHALL BE AS PER ITEM 632.

ITEM 632 REMOVAL OF TRAFFIC SIGNAL INSTALLATION, AS PER PLAN
ALL REMOVED ITEMS SHALL REMAIN THE PROPERTY OF THE CITY OF COLUMBUS WITH THE EXCEPTION OF FOUNDATIONS, SIGNAL CABLE, MESSENGER WIRE AND CONDUIT. THE CONTRACTOR SHALL PROPERLY DISPOSE OF THOSE ITEMS ONLY AND DELIVER THE OTHER REMOVED ITEMS TO THE TRANSPORTATION DIVISION TRAFFIC MAINTENANCE SHOP AT 1820 EAST 17TH AVENUE; COLUMBUS, OHIO 43219. THE CONTRACTOR SHALL CONTACT THE CITY OF COLUMBUS, TRANSPORTATION DIVISION, TRAFFIC MAINTENANCE MANAGER (614-645-7393) TWENTY-FOUR (24) HOURS, NOT INCLUDING SATURDAY OR SUNDAY, IN ADVANCE TO SCHEDULE DELIVERY. NO ITEM WILL BE ACCEPTED WITHOUT FOLLOWING THIS PROCEDURE. THE TRAFFIC MAINTENANCE MANAGER SHALL INSPECT THE CONDITION OF ALL SALVAGED ITEMS BEING PRESENTED FOR DELIVERY. NO ITEM DAMAGED BY THE CONTRACTOR WILL BE ACCEPTED, AND NO ITEM SHALL BE CONSIDERED DELIVERED UNTIL THE TRAFFIC MAINTENANCE MANAGER ISSUES A RECEIPT TO THE CONTRACTOR ACKNOWLEDGING ACCEPTANCE OF DELIVERY.

EMBEDDED POLES SHALL BE REMOVED IN THEIR ENTIRETY BY PULLING. ALL CONCRETE SHALL BE REMOVED FROM REMOVED EMBEDDED POLES.

FOUNDATIONS

EXISTING TRAFFIC SIGNAL SUPPORT FOUNDATIONS SHALL BE REMOVED IN THEIR ENTIRETY. REMOVAL OF THE ENTIRE FOUNDATION SHALL BE INCIDENTAL TO THIS ITEM OF WORK. NO ADDITIONAL COMPENSATION SHALL BE AWARDED FOR THIS WORK.

REMOVED CONDUIT, FOUNDATION, SIGNAL CABLE AND MESSENGER WIRE SHALL BE DISPOSED OF BY THE CONTRACTOR IN ACCORDANCE WITH ITEM 632. REMOVE CABLE AND ANY MESSENGER WIRE BACK TO ITS TERMINUS POINT. ALL EXISTING UNUSED SIGNAL CABLE SHALL BE REMOVED FROM UNDERGROUND CONDUITS. PAYMENT SHALL BE AS PER ITEM 632.

ITEM 632 POWER CABLE, 3-CONDUCTOR, #6 AWG, AS PER PLAN
AT THE INTERSECTION OF HUDSON STREET/JOYCE AVENUE, POWER SHALL BE SUPPLIED BY THE AMERICAN ELECTRIC POWER COMPANY (AEP), SHALL BE 120VAC, AND SHALL BE FROM THE APPROXIMATE LOCATION AS SHOWN ON THE PLANS. THE CONTRACTOR SHALL CONTACT AEP AND MAKE ARRANGEMENTS FOR THE CONNECTION OF POWER TO THE CONTROLLER CABINET. CONTACT GREG ZORICH (614-883-7935) A MINIMUM OF FOUR (4) WORK WEEKS PRIOR TO THE NEED FOR POWER. PAYMENT SHALL BE AS PER ITEM 632.

ITEM 633 CABINET FOUNDATION, AS PER PLAN
THE PROPOSED TRAFFIC SIGNAL CABINET FOUNDATION SHALL BE AS DETAILED ON THE POLE FABRICATION AND ORIENTATION DETAILS SHEET. PAYMENT SHALL BE AS PER ITEM 633.

ITEM 633 CONTROLLER UNIT, TYPE TS-2/A2, WITH CABINET (P44), TYPE TS-1, AS PER PLAN
IN ADDITION TO THE OTHER REQUIREMENTS OF ODOT 633 & 733, THE CONTROLLER (TS2, TYPE 2/TS1 COMPATIBLE) SHALL BE ECONOLITE ASC/3-210 MODEL OR EAGLE GENESIS EPAC 3108-M40 MODEL. THE TS1 CABINET ASSEMBLY SHALL BE COMPLETELY WIRED (INCLUDES ALL PANELS & HARNESSSES) FOR COAXIAL SYSTEM OPERATION AND FOR THE PHASE OPERATION, DETECTION, AND ALL ADDITIONAL DEVICES AS CALLED FOR IN THE PLANS. THE COLUMBUS MUTCD FLASH CIRCUITRY SHALL BE INSTALLED AS A PANEL MOUNTED, CABINET ASSEMBLY ITEM. THE CABINET ASSEMBLY SHALL MEET ALL CITY STANDARDS AS SET FORTH BETWEEN THE SUPPLIERS AND THIS DIVISION. CONTACT THE TRANSPORTATION DIVISION'S ELECTRONIC SYSTEMS SUPERVISOR FOR DETAILS (614-645-7933).

THE LOOP DETECTOR UNIT SHALL BE A SOLID STATE, 2 CHANNEL, SHELF MOUNTED INTERSECTION DEVELOPMENT CORPORATION (IDC) MODEL 921-2TCS-1, OR RENO A&E MODEL T-210-SS.

IN ADDITION TO THE OTHER SPECIFICATION DOCUMENTS, THE CABINET ASSEMBLY SHALL MEET THE FOLLOWING SPECIFICATIONS.

- (A) ALL LABELS SHALL BE PERMANENTLY SECURED TO THE CABINET. PLASTIC LABEL MAKER TAPE IS NOT CONSIDERED TO BE PERMANENT. CROY TYPE LABELS ARE ACCEPTABLE.
- (B) IN LIEU OF A LAMP ASSEMBLY, A DOOR MOUNTED FLEX LIGHT THAT ILLUMINATES THE ENTIRE BACK PANEL SHALL BE INSTALLED. THE 120 VAC, CONVENIENCE OUTLET ASSEMBLY (GFI TYPE) SHALL BE MOUNTED ON THE RIGHT CABINET SIDE PANEL NEAR THE DOOR HINGE AREA AND FACE THE DOOR OR THE CENTER INTERIOR PORTION OF THE CABINET. THE OUTLET & FLEX LIGHT ASSEMBLIES SHALL NOT INTERFERE WITH THE REMOVAL OR INSTALLATION OF ANY EQUIPMENT.

(C) LOAD SWITCHES SHALL BE EDI MODEL 510 WITH LIGHTS PERMANENTLY LABELED AS R, Y, G OR A, B, C. A LOAD SWITCH SHALL BE PROVIDED FOR EACH BACK PANEL LOAD SWITCH SOCKET POSITION WHETHER USED OR UNUSED. ALL LOAD SWITCHES SHALL REST IN A SUPPORT RACK. LOAD SWITCH POSITIONS 5-8 (4PH) OR 9-12 (8PH) SHALL BE USED FOR EITHER A PEDESTRIAN OR OVERLAP LOAD SWITCH UNLESS SPECIFIED OTHERWISE.

(D) LIGHTNING PROTECTION DEVICES SUCH AS ITT, SURRESTOR, GENERAL ELECTRIC, OR APPROVED EQUAL (AS DETERMINED BY THE COLUMBUS TRANSPORTATION DIVISION) SHALL BE PROVIDED.

(E) THE MAIN CABINET DOOR LOCK (CCL ENCLOSURE LOCK 15481RS) SHALL HAVE A LOCK KEYHOLE COVER AND SHALL BE KEYED TO THE CITY OF COLUMBUS MASTER, # 2 KEY (1R 6380). THE POLICE PANEL DOOR LOCK (CCL ENCLOSURE LOCK # R357SGS) SHALL HAVE A LOCK KEYHOLE COVER AND SHALL BE SUPPLIED WITH A R4266 KEY.

(F) THE NEMA 3R CABINET SHALL BE MADE BY APX ENCLOSURES, CALIFORNIA CHASSIS EAGLE OR ECONOLITE. IT SHALL BE OF STANDARD SIZE AND SHALL BE SUPPLIED WITH A COMPLETE BACK PANEL AS PER PLAN. THE CABINET MATERIAL SHALL BE 5052 MARINE GRADE, 0.125 INCH THICK ALUMINUM SHEETING WITH A 32 HARDNESS IN ITS NATURAL COLOR AND SHALL BE PAINTED WHITE ON THE INSIDE. THE INSIDE OF THE CABINET SHALL BE TREATED WITH A THREE (3) STAGE IRON PHOSPHATE COATING AND A ZINC CHROMATE PRIMER COATING. A BAKED WHITE ALKALI ENAMEL FINISH SHALL THEN BE APPLIED. ALL COATINGS SHALL BE PROPERLY DRIED AND APPLIED SUCH THAT THE INSIDE WHITE PAINT WILL NOT PEEL FOR A GUARANTEED PERIOD OF TWO (2) YEARS. ALL EXTERIOR SEAMS SHALL BE EITHER CONTINUOUSLY WELDED, TACK WELDED, SEALED WITH A 15 TO 20 YEAR SILICONE SEALER, AND/OR OVERLAPPED SUCH THAT WATER DOES NOT ENTER THE CABINET. ALL CABINET EDGES SHALL BE SMOOTH (FREE OF ANY SHARP EDGES). THE CABINET DOOR FRAME OPENING SHALL BE DOUBLE-FLANGED ON ALL FOUR SIDES. THE CABINET DOOR SHALL BE HINGED USING A HEAVY GAUGE CONTINUOUS HINGE THAT HAS A STAINLESS STEEL HINGE PIN. THE HINGE SHALL BE BOLTED TO THE CABINET SO THE DOOR CAN BE REMOVED. THE BOLTS AND NUTS SHALL BE MADE OF STAINLESS STEEL, TAMPERPROOF AND SECURELY FASTENED TO PREVENT VIBRATIONS FROM LOOSENING THE NUTS. THE DOOR, SEALED WITH A NEOPRENE GASKET, SHALL BE EQUIPPED WITH A THREE (3) POINT LATCHING MECHANISM AND A HANDLE WHICH CAN BE PADLOCKED. THE DOOR SHALL BE DESIGNED SUCH THAT THE DOOR CAN BE LOCKED IN AN OPEN POSITION AT 90, 135, AND 180 DEGREES TO THE CABINET FACE (NOMINAL VALUES). THE POLICE DOOR AND MAIN CABINET DOOR SHALL HAVE A KEYHOLE COVER. BOLT PATTERN SHALL CONSIST OF AN ANCHOR BOLT POSITIONED IN EACH CABINET CORNER. THE M36 CABINET SIZE SHALL BE 50"H X 36"W X 17"D WITH A DOOR OPENING OF 39" H X 33.5" W. THE P44 CABINET SIZE SHALL BE 55"H X 44"W X 26"D WITH A DOOR OPENING OF 44" H X 41.5" W.

(G) A THYRECTOR SURGE PROTECTOR WITH A RMS INPUT OF 150 VOLTS AND INPUT PEAK OF 210 VOLTS SHALL BE PROVIDED IN ADDITION TO ANY LIGHTNING PROTECTION DEVICE. THE THYRECTOR SHALL BE PLACED ACROSS THE INPUT AC POWER LINE.

(H) A 35 AMP LINE FILTER SHALL BE SUPPLIED AND SHALL BE MOUNTED ON THE POWER DISTRIBUTION PANEL.

(I) TWO (2) CIRCUIT SOLID STATE FLASHER, EDI MODEL 810, RATED AT 15 AMPS (MINIMUM) PER CIRCUIT SHALL BE PROVIDED (NEMA TYPE 3). CIRCUIT 1 SHALL CONTROL THE MAINLINE FLASHING SIGNAL INDICATIONS. CIRCUIT 2 SHALL CONTROL THE SIDE STREET FLASHING SIGNAL INDICATIONS.

(J) ONE (1) 30 AMP 2 POLE CIRCUIT BREAKER, LABELED AS "MAIN", SHALL BE WIRED AS THE MAIN POWER DISTRIBUTION BREAKER. A SECOND CIRCUIT BREAKER, LABELED AS "PED" AND RATED AT 10 AMPS, 1 POLE SHALL BE SUPPLIED FOR THE PEDESTRIAN SIGNAL LOAD ONLY. THE PEDESTRIAN SIGNAL BREAKER SHALL BE WIRED IN SERIES WITH BUT AFTER THE MAIN POWER BREAKER. A THIRD CIRCUIT BREAKER, LABELED AS "AUX" AND RATED AT 15 AMPS, 1 POLE SHALL SUPPLY A SEPARATE BRANCH OF AC+ POWER TO THE VENTILATING FAN, CONVENIENCE GFI OUTLET AND LIGHT SO THAT THEY MAY OPERATE INDEPENDENTLY OF THE MAIN POWER BREAKER. THE POWER TO THE FAN AND LIGHT SHALL ALSO BE INTERRUPTED BY THE GFI OUTLET. ALL BREAKERS SHALL BE MOUNTED SIDE-BY-SIDE ON THE POWER DISTRIBUTION PANEL.

(K) ALL CONTROLLER MS CONNECTOR HARNESSSES SHALL HAVE A CONDUCTOR FOR EACH PLUG PIN EXCEPT THE REMOTE RESET FUNCTION FOR THE CONFLICT MONITOR. THE CONTROLLER AND CONFLICT MONITOR MS HARNESS CONDUCTORS SHALL BE CONNECTED TO A BACK PANEL TERMINAL STRIP WHICH IS ACCESSIBLE FROM THE FRONT OF THE PANEL. DETECTOR UNIT HARNESS CONDUCTORS SHALL BE CONNECTED TO A LEFT SIDE CABINET MOUNTED TERMINAL STRIP. OTHER EQUIPMENT SHALL BE CONNECTED AS APPROPRIATE.

(L) THE CABINET ASSEMBLY SHALL CONTAIN ALL PEDESTRIAN SIGNAL CIRCUITRY FOR EACH NEMA DEFINED THROUGH PHASE.

(M) A POLICE DOOR MOUNTED SIGNAL SHUTDOWN SWITCH WITH SWITCH POSITIONS LABELED AS "SIG ON" AND "SIG OFF" SHALL BE INSTALLED.

(N) A POLICE DOOR MOUNTED SIGNAL-FLASH SWITCH WITH SWITCH POSITIONS LABELED AS "ON SIG" AND "ON FLASH" SHALL NOT ONLY PLACE THE SIGNALS ON FLASH BUT ALSO STOP-TIME THE CONTROLLER UNIT. A RUN/STOP-TIME SWITCH WITH SWITCH POSITIONS LABELED AS "CONT. RUN" AND "STOP-TIME" SHALL BE INSTALLED ON THE INSIDE OF THE CABINET DOOR. THE RUN/STOP-TIME SWITCH SHALL ALLOW THE CONTROLLER UNIT TO TIME NORMALLY BUT KEEP THE SIGNALS ON FLASH. THE SIGNAL-FLASH SWITCH SHALL NOT RETURN THE SIGNALS TO NORMAL OPERATION UNLESS THE RUN/STOP-TIME SWITCH IS RESET TO THE STOP TIME POSITION SO THE SIGNAL-FLASH SWITCH CAN AGAIN STOP-TIME THE CONTROLLER UNIT. THE SIGNAL-FLASH SWITCH SHALL NOT REMOVE POWER TO THE CONTROLLER UNIT OR ITS AUXILIARY EQUIPMENT.

(O) A POLICE DOOR MOUNTED AUTO-MANUAL TRANSFER SWITCH WITH SWITCH POSITIONS LABELED AS "AUTO" AND "MANUAL" SHALL BE INSTALLED. A MANUAL PUSH BUTTON CONTROL SHALL NOT BE INSTALLED UNLESS SPECIFIED, BUT WIRING FOR A PUSH BUTTON CONTROL SHALL BE PROVIDED UP TO THE POINT WHERE THE PUSH BUTTON WOULD HAVE BEEN CONNECTED.

(P) A CONTROLLER SHUTDOWN SWITCH WITH SWITCH POSITIONS LABELED AS "CONT ON" AND "CONT OFF" AND A COORDINATED/FREE SWITCH WITH SWITCH POSITIONS LABELED AS "COORD" AND "FREE" SHALL BE INSTALLED INSIDE THE CABINET NEXT TO THE RUN/STOP-TIME SWITCH. A COORDINATED/FREE SWITCH SHALL NOT BE REQUIRED IF THE CONTROLLER HAS A BUILT-IN COORD/FREE SWITCH.

(Q) AFTER A NEMA DEFINED POWER INTERRUPTION THE CONFLICT MONITOR SHALL CAUSE THE INTERSECTION SIGNALS TO FLASH AS PER PLAN FOR 10 SECONDS BEFORE THE INITIALIZED CONTROLLER UNIT TAKES CONTROL OF THE INTERSECTION SIGNALS. THE CONFLICT MONITOR SHALL BE EDI MODEL SERIES SSM LE AND SHALL CONTAIN SUFFICIENT CHANNELS AS CALLED FOR IN THESE PLANS.

(R) THE CONFLICT MONITOR SHALL BE CONNECTED DIRECTLY TO THE FIELD TERMINALS. USING JUMPERS OR LINKS ON THE BACK PANEL TO FORM A CIRCUIT FOR THE CONFLICT MONITOR SHALL NOT BE ACCEPTABLE.

(S) THE CONFLICT MONITOR SETTINGS FOR MINIMUM YELLOW TIMING ON ALL CHANNELS SHALL BE SET AT THREE AND ONE HALF (3.5) SECONDS.

(T) THE WATCH DOG TIMER SHALL CAUSE THE CONTROLLER TO GO INTO A FLASH OPERATION IF A MICROPROCESSOR FAILURE IS DETECTED.

(U) ALL BACK PANEL HARDWARE SHALL BE MOUNTED WITH SCREWS. ALL SCREWS SHALL BE COMPLETELY SCREWED DOWN. RIVETS OR OTHER NON-REMOVABLE FASTENERS ARE NOT ACCEPTABLE.

(V) WIRE CONNECTIONS ON THE BACK PANEL SHALL BE MADE WITH CRIMP TERMINALS AND THREADED FASTENERS. TELEPHONE TYPE KNIFE CONNECTORS (SOLDERED OR OTHERWISE) ARE NOT ACCEPTABLE.

(W) ALL WIRES FASTENED TO THE LOAD SWITCH AND FLASHER PLUGS SHALL BE SOLDERED IN PLACE.

(X) THE BACK PANEL AND POWER DISTRIBUTION PANEL SHALL HAVE SILK SCREENED TERMINAL/SOCKET FUNCTION IDENTIFICATION LABELS SUCH AS AC COM, PHASE 3 GREEN, 115 VAC, SIGNAL BUS, ETC. REFERENCE NUMBERS SHALL NOT BE ACCEPTABLE IN LIEU OF FUNCTION LABELS BUT THEY CAN SUPPLEMENT THEM. ADDITIONAL TERMINAL BLOCKS AND AUXILIARY PANELS SHALL USE SILK SCREENED REFERENCE NUMBERS TO IDENTIFY TERMINAL CONNECTIONS.

(Y) ALL TERMINAL STRIPS IN CLOSE PROXIMITY OF SHELF MOUNTED CONTROL DEVICE EQUIPMENT SHALL BE COVERED WITH NON-CONDUCTIVE MATERIAL TO PREVENT ACCIDENTAL CONTACT WITH THE DEVICES. ALL TERMINAL STRIPS SHALL BE READILY ACCESSIBLE WITHOUT REMOVAL OF ANY EQUIPMENT.

(Z) THE CABINET SHALL HAVE TWO (2) NON-VENTED (SOLID) SHELVES SPACED AT LEAST 9" APART. BOTH SHELVES SHALL HAVE A WIDTH OF 13" AND THE BACK EDGE OF THE SHELF SHALL BE LIPPED WITH THE LIP POINTING UP. THE FRONT EDGE OF THE SHELF SHALL BE LIPPED WITH THE LIP POINTING DOWN. ALL LIP EDGES SHALL BE ROUNDED. THE SHELVES SHALL BE ATTACHED TO THE CABINET SIDE PANELS. THE SHELF ARRANGEMENT SHALL BE DESIGNED SO ALL SHELF DEVICES FIT ON THEM.

(aa) THERE SHALL BE A MINIMUM OF ONE (1) INCH EMPTY SPACE BETWEEN ALL ITEMS ATTACHED TO THE DOOR AND ALL SHELF-MOUNTED DEVICES INCLUDING ITS CONNECTING HARNESS(ES), ALL LOAD SWITCHES, FLASHER AND ALL SIDE-PANEL-MOUNTED ITEMS.

(bb) "M" SIZED CABINETS SHALL HAVE TWO VENTILATION FANS. THE THERMOSTAT CONTROLLING THE VENTILATING FAN CIRCUIT SHALL BE SET AT 95 DEGREES FAHRENHEIT.

(cc) ALL FLASH TRANSFER RELAYS SHALL BE WIRED FOR FAIL-SAFE OPERATION (ENERGIZED DURING NORMAL OPERATION) AND WIRED WITH A MAXIMUM OF TWO PHASES PER RELAY.

(dd) THE CONTROLLER ASSEMBLY, WHEN PLACED IN OR COMING OUT OF AN AUTOMATIC FLASHING MODE, SHALL CONFORM TO THE AUTOMATIC FLASHING CRITERIA SET FORTH IN THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, SECTION 4D-12, INCLUDING THE FOLLOWING ADDITIONS.

1) A VEHICULAR CALL SHALL BE PLACED ON ALL PHASES IMMEDIATELY PRIOR TO ENTERING THE "FLASH" MODE SO THE CONTROLLER WILL CYCLE TO THE "FLASH" POINT. IT IS OPTIONAL TO HAVE ONE EXTERNAL VEHICULAR CALL PLACED IMMEDIATELY ON ALL PHASES WHEN THE "FLASH" MODE TERMINATES. THE CONTROLLER SHALL OPERATE NORMALLY ONCE THE "FLASH" MODE SEQUENCE IS TERMINATED.

2) THE CONTROLLER SHALL ENTER THE "FLASH" MODE AT THE END OF THE THROUGH SIDE STREET PHASE(S) YELLOW (OR DURING THE SIDE STREET PHASE(S) RED CLEARANCE INTERVAL) BUT JUST PRIOR TO ANY MAIN STREET GREEN. THE FLASH TRANSFER LOGIC DEVICE SHALL TRIGGER THE "FLASH" OPERATION, SHALL BE SOLID STATE, SHALL BE EXTERNAL TO THE CONTROLLER (A CABINET ASSEMBLY DEVICE), AND SHALL FUNCTION WITH ANY NEMA CONTROLLER. THIS CIRCUITRY SHALL BE SUPPLIED IN ADDITION TO ANY INTERNAL CONTROLLER FLASH LOGIC PROVIDED BY THE CONTROLLER.

(ee) THE POWER CABLE SHALL BE CONNECTED TO AN ACCESSIBLE TERMINAL STRIP THAT SHALL BE LOCATED NEAR THE BOTTOM OF THE CABINET AND SHALL BE OF SUFFICIENT SIZE TO ACCEPT A SUPPLIED #6 WIRE LUG. THE TERMINAL STRIP SHALL BE COVERED OR SHIELDED TO MINIMIZE ACCIDENTAL CONTACT DURING NORMAL SERVICING OPERATIONS. THE COVER SHALL BE SNAPPED ON/OFF OR SECURED BY STANDARD SCREWS. THE POWER CABLE LUG TERMINAL CONNECTION SHALL BE LOCATED IMMEDIATELY BELOW THE MAIN POWER DISTRIBUTION BREAKER. POWER SHALL BE JUMPERED TO THE MAIN POWER DISTRIBUTION BREAKER. THE POWER DISTRIBUTION PANEL SHALL BE LOCATED IN THE BOTTOM RIGHT SIDE OF THE CABINET OR IT SHALL BE AN INTEGRAL PART OF THE RIGHT SIDE OF THE BACK PANEL. THERE SHALL BE A MINIMUM OF TWO (2) INCHES CLEARANCE BETWEEN THE POWER TERMINAL AND THE BOTTOM OF THE CABINET.

(ff) A #4 WIRE LUG SHALL BE PROVIDED FOR ATTACHING A GROUNDING WIRE FROM A GROUND ROD. THE GROUNDING WIRE LUG SHALL BE ATTACHED TO THE POWER DISTRIBUTION PANEL (LOWER LEFT CORNER), OR IF NONE, TO THE BACK PANEL (BOTTOM MIDDLE). IT SHALL BE DIRECTLY GROUNDING IN ACCORDANCE WITH THE GROUNDING AND BONDING NOTES.

(aa) A SINGLE POLE MERCURY PLUNGER RELAY SHALL BE INSTALLED WHICH WILL ALLOW POWER TO BE REMOVED FROM THE VEHICULAR AND PEDESTRIAN POWER BUSES. THE MERCURY RELAY SHALL BE RATED AT 35 AMPS AND THE RELAY COIL WIRED WITH A NOISE SUPPRESSION DEVICE.

(hh) ALL EXTERNAL RELAY COILS SHALL HAVE NOISE SUPPRESSION DEVICES.

(ii) THE DOOR FILTER (U.L. LISTED CLASS 2, STANDARD 900) SHALL CONSIST OF THREE DISTINCT LAYERS OF FILTERING MEDIA. THE FIRST AIR ENTERING LAYER SHALL BE COMPOSED OF A DUAL FIBER BLEND OF 100% NON-WOVEN POLYESTER TO TRAP LARGER SIZED PARTICLES. THE NEXT LAYER SHALL BE A DUAL PLY, DUAL DENIER, 100% NON-WOVEN POLYESTER OF SMALLER SIZE TO TRAP FINER PARTICLES PASSING THROUGH THE FIRST LAYER. A NON-TOXIC, NON-MIGRATORY, ODORLESS TACKIFIER SHALL BE APPLIED TO THESE LAYERS. ADHESIVES SPRAYED ON THE LAYERS ARE NOT ACCEPTABLE. THE TACKIFIER SHALL BE INCORPORATED INTO THE LAYER MEDIA DURING THE MANUFACTURING PROCESS OF THE RAW MATERIAL. A 10 GAUGE MESH SHALL BE INCORPORATED IN THE FILTER DESIGN FOR RIGIDITY. SUFFICIENT MEDIA OVERLAP SHALL BE PRESENT ABOUT THE WIRE PERIMETER TO INSURE POSITIVE SELF SEAL. THE DOOR FILTER HOLDER SHALL BE DESIGNED SO THE FILTER MAKES POSITIVE CONTACT WITH THE CABINET DOOR AT ALL TIMES AND UNDER ALL CONDITIONS AND SITUATIONS.

FOUR (4) SETS OF CABINET WIRING SCHEMATICS, TWO (2) SERVICE MANUALS AND TWO (2) INSTRUCTIONAL MANUALS SHALL BE PROVIDED PER CABINET. DELIVERY OF THESE DIAGRAMS & MANUALS SHALL ACCOMPANY THE CABINET. THE CONTRACTOR SHALL CLEARLY NOTE ANY DEVIATIONS, CHANGES, ADDITIONS OR OTHER MODIFICATIONS ON THE DIAGRAMS AND MANUALS THAT ARE APPROPRIATE TO REFLECT THE EXACT EQUIPMENT TO BE PROVIDED. THE COST FOR THIS MATERIAL SHALL BE INCIDENTAL TO THE COST OF THE SIGNAL EQUIPMENT. THE COPIES OF DIAGRAMS AND MANUALS SHALL BE STORED IN A PLASTIC ENVELOPE MOUNTED HORIZONTALLY AND SECURELY FASTENED TO THE INSIDE OF THE MAIN CABINET DOOR. THE ENVELOPE OPENING SHALL BE TO THE RIGHT OR LEFT. THE ENVELOPE SHALL NOT BLOCK ANY PART OF THE AIR FILTER OR THE AIR INTAKE LOCATED IN THE DOOR.

SERVICE & INSTRUCTIONAL MANUALS SHALL INCLUDE SECTIONS COVERING THE GENERAL DESCRIPTION OF EQUIPMENT, EQUIPMENT INSTALLATION PROCEDURES, EQUIPMENT PROGRAMMING PROCEDURES, THEORY OF OPERATION WITH SYSTEM DESCRIPTION INCLUDING BLOCK DIAGRAMS AND DETAILED CIRCUIT DIAGRAMS, PREVENTIVE MAINTENANCE, FIELD TROUBLE ANALYSIS, BENCH TROUBLE ANALYSIS, TROUBLESHOOTING ANALYSIS CHART, WAVE FORMS, VOLTAGE MEASUREMENTS, VOLTAGE MEASUREMENT CHARTS, PARTS LIST, ELECTRICAL INTERCONNECTION DRAWINGS, SCHEMATIC AND LOGIC DIAGRAMS, ASSEMBLY DRAWINGS WITH PICTORIAL DIAGRAMS SHOWING PHYSICAL LOCATIONS AND IDENTIFICATION OF EACH COMPONENT.

PROVIDE AN ARC FLASH WARNING SIGN ON THE OUTSIDE FRONT DOOR OF THE CABINET IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE PARAGRAPH 110.16.

PAYMENT SHALL BE AS PER ITEM 633.

CALCULATED
CHECKED

TRAFFIC SIGNAL GENERAL NOTES

PROJECT NAME

X
XX

XXXX-E

ITEM 633 CONTROLLER ITEM, MISC.: TRANSCEIVER INTERFACE UNIT, AS PER PLAN

THE INTERSECTION RF TRANSCEIVER INTERFACE UNIT SHALL BE THE VENTURE ENGINEERING CORPORATION REMOTE COMMUNICATIONS UNIT, MODEL #732-002A.

THE CONTRACTOR SHALL INSTALL A GILBERT "F" SERIES RF TERMINATOR (GILBERT PART NO. GTR-59-A) ON THE TEST PORT. THE COST OF THE "F" SERIES RF TERMINATOR IS CONSIDERED INCIDENTAL TO THE COMMUNICATIONS UNIT.

THE CONTRACTOR SHALL SUPPLY AN EDCO 1 GHZ COAXIAL CABLE LIGHTNING PROTECTOR, EDCO PART NO. CATV-145A. THE COST OF THE LIGHTNING PROTECTOR IS CONSIDERED INCIDENTAL TO THE COMMUNICATIONS UNIT. TRANSPORTATION DIVISION PERSONNEL SHALL INSTALL THE LIGHTNING PROTECTOR IN THE CONTROLLER CABINET.

PAYMENT SHALL BE PER EACH UNIT FURNISHED AND INSTALLED.

COAXIAL CABLE SYSTEM GENERAL REQUIREMENTS

THE CONTRACTOR SHALL INSTALL A COAXIAL INTERCONNECT CABLE SYSTEM IN ACCORDANCE WITH THE DESIGN PLANS.

AT LEAST TEN (10) DAYS IN ADVANCE OF BEGINNING COAXIAL CABLE WORK, THE CONTRACTOR SHALL NOTIFY THE DIVISION OF DESIGN AND CONSTRUCTION PROJECT MANAGER BY EMAIL OF THE AREA WHERE CABLE WORK WILL TAKE PLACE AND THE STARTING DATE OF WORK. AT THE SAME TIME, THE CONTRACTOR SHALL ALSO REQUEST THE PROJECT MANAGER TO SET UP A PRE-CONSTRUCTION MEETING WITH THE DIVISION OF DESIGN AND CONSTRUCTION SIGNAL PLAN REVIEWER TO REVIEW THE COAXIAL CABLE INTERCONNECT INSTALLATION PLANS PRIOR TO BEGINNING WORK. THE COAXIAL CABLE PRE-CONSTRUCTION MEETING SHALL BE HELD AT LEAST TWO (2) WORKING DAYS IN ADVANCE OF BEGINNING COAXIAL CABLE WORK. THE DIVISION WILL VERIFY THE PLAN IN THIS AREA AND NOTIFY THE CONTRACTOR OF ANY SPECIAL CONDITIONS OR CORRECTIONS. IF THE CONTRACTOR FAILS TO DO SO AND IF UNFORESEEN CIRCUMSTANCES, SUCH AS UTILITY POLE RELOCATIONS, NECESSITATE CHANGES TO THE COAXIAL CABLE SYSTEM PLAN, ALL CHANGES NECESSARY FOR THE COAXIAL CABLE SYSTEM TO MEET THE APPROVAL OF THE DIVISION OF DESIGN AND CONSTRUCTION SIGNAL PLAN REVIEWER SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND AT THE EXPENSE OF THE CONTRACTOR.

THE EXISTING COAXIAL INTERCONNECT CABLE SHALL BE MAINTAINED AND REMAIN OPERATIONAL UNTIL IT IS DISCONNECTED AND THE NEW COAXIAL INTERCONNECT CABLE HAS BEEN CONNECTED INTO THE COAXIAL CABLE SYSTEM. THE CONTRACTOR SHALL UTILIZE A PROCEDURE WHICH WILL RETAIN CONTROL (ON-LINE STATUS) OF ANY EXISTING SIGNAL INTERCONNECT TO ANY SIGNAL(S). THE EXISTING COAXIAL INTERCONNECT CABLE SYSTEM SHALL BE FULLY OPERATIONAL DURING THE WEEKDAY HOURS OF 6:30 A.M. TO 9:00 A.M. AND 2:45 P.M. TO 6:00 P.M., MONDAY THROUGH FRIDAY. DEVIATION FROM THE ABOVE TIMES MUST BE APPROVED BY THE DIVISION OF DESIGN AND CONSTRUCTION SIGNAL PLAN REVIEWER PRIOR TO IMPLEMENTATION.

FOR CONNECTIONS OF NEW COAXIAL CABLE TO THE EXISTING COAXIAL CABLE SYSTEM, DIVISION OF PLANNING AND OPERATIONS PERSONNEL SHALL INSTALL ALL CONNECTORS AND MAKE ALL CONNECTIONS OF THE NEW COAXIAL CABLE TO THE EXISTING COAXIAL CABLE SYSTEM. THE CONTRACTOR SHALL CONTACT THE DIVISION OF DESIGN AND CONSTRUCTION PROJECT MANAGER AND SIGNAL PLAN REVIEWER BY EMAIL AT LEAST FORTY-EIGHT (48) HOURS, NOT INCLUDING SATURDAY AND SUNDAY, IN ADVANCE TO SCHEDULE THIS WORK. ALL OTHER CONNECTIONS OF COAXIAL CABLE AND EQUIPMENT INSTALLED OR RELOCATED ACCORDING TO THE COAXIAL CABLE SYSTEM PLAN SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, UNLESS OTHERWISE SPECIFIED.

CABLE SYSTEM MATERIALS

ALL CABLE SYSTEM MATERIALS AND EQUIPMENT REQUIRED TO PROVIDE A FULLY OPERATIONAL AND COMPLETE COAXIAL CABLE INTERCONNECT SYSTEM SHALL BE FURNISHED BY THE CONTRACTOR, EXCEPT AS NOTED IN THE PLANS. ALL EQUIPMENT SHALL BE EQUIPPED WITH COAXIAL CABLE FITTINGS OF POSITIVE MOISTURE PROTECTION AND EFFECTIVE ELECTRICAL CONNECTION. MATERIALS AND EQUIPMENT INCLUDE, BUT ARE NOT LIMITED TO THE FOLLOWING:

A. SYSTEM PASSIVES

ALL DROPS SHALL BE GROUNDED IN CONFORMANCE WITH THE NATIONAL ELECTRICAL CODE, AND THE NATIONAL ELECTRICAL SAFETY CODE.

B. CONNECTORS

THE CONTRACTOR SHALL FURNISH AND INSTALL ALL CONNECTORS EXCEPT THE CONNECTORS ON COAXIAL RG-6 CABLE. ALL "F" SERIES MALE CONNECTORS FOR COAXIAL RG-6 CABLE SHALL BE SUPPLIED BY AND INSTALLED BY TRANSPORTATION DIVISION PERSONNEL. FOR THE FOLLOWING TYPES OF CONNECTIONS, THE CONNECTORS SHALL BE:

1. CABLE TO CABLE
 - A) 0.750-INCH CABLE TO 0.750-INCH CABLE: GILBERT SPLICE CONNECTOR, PART NO. GRS-750-SP-DU-01.
 - B) 0.750-INCH CABLE TO 0.500-INCH CABLE: GILBERT FEMALE SPLICE ADAPTER, PART NO. GSKSFS, WITH A GILBERT PIN TYPE CONNECTOR, PART NO. GRS-750-CH-DU-01, AND A GILBERT SPLICE CONNECTOR, PART NO. GRS-500-SP-DU-03.
 - C) 0.500-INCH CABLE TO 0.500-INCH CABLE: GILBERT SPLICE CONNECTOR, PART NO. GRS-500-SP-DU-03.
2. CABLE TO DEVICE HOUSING
 - A) 0.750-INCH CABLE TO DEVICE HOUSING: GILBERT PIN TYPE CONNECTOR, PART NO. GRS-750-CH-DU-01.
 - B) 0.500-INCH CABLE TO DEVICE HOUSING: GILBERT PIN TYPE CONNECTOR, PART NO. GRS-500-CH-DU-03.

3. DEVICE HOUSING TO DEVICE HOUSING: ROTATIONAL HOUSING-TO-HOUSING

CONNECTOR, GILBERT PART NO. G-KS-KS-M-T

4. "F" CONNECTIONS

- A) 0.750-INCH CABLE TO "F" CONNECTOR: GILBERT PIN TYPE CONNECTOR, PART NO. GRS-750-CH-DU-01, AND GILBERT ADAPTER (CHASSIS MOUNTING CONNECTOR TO "F" SERIES FEMALE), PART NO. G-CH-BAFF-KS.
- B) 0.500-INCH CABLE TO "F" CONNECTOR: GILBERT PIN TYPE CONNECTOR, PART NO. GRS-500-CH-DU-03, AND GILBERT ADAPTER, (CHASSIS MOUNTING CONNECTOR TO "F" SERIES FEMALE), PART NO. G-CH-BAFF-KS.
- C) DEVICE HOUSING TO "F" CONNECTOR: GILBERT "F" FEMALE-'KS' ADAPTER [AC (60 HZ) POWER BLOCKING], PART NO. GF-625-CH-DCB FOR EQUIPMENT TO "F" CONNECTOR CONNECTIONS.

5. PORT TERMINATION

- a) PORT TERMINATION ON DEVICES: GILBERT 'KS' PORT TERMINATOR, PART NO. GTR-MPORT.
- b) PORT TERMINATION ON COMMUNICATIONS UNITS: GILBERT "F" SERIES RF TERMINATOR, PART NO. GTR-59-A.
- c) PORT TERMINATION ON TAPS: GILBERT "F" SERIES RF TERMINATOR, PART NO. GTR-59-A.

HEAT SHRINK TUBING WITH CATV SEALANT SHALL BE INSTALLED FOR ALL CABLE TO CABLE SPLICE CONNECTIONS AND ALL CABLE TO ACTIVE AND PASSIVE DEVICE HOUSING CONNECTIONS, EXCEPT THOSE LOCATED INSIDE A CABINET OR POLE ENCLOSURE, TO INSURE WATER-TIGHT INTEGRITY. THE HEAT SHRINK TUBING USED SHALL BE DSG-CANUSA PART NO. CFTV-1500 OR GILBERT PART NO. GC-HST-15. A 12-IN. LENGTH OF HEAT SHRINK TUBING SHALL BE USED FOR SPLICE CONNECTIONS. AN 8-IN. LENGTH OF HEAT SHRINK TUBING SHALL BE USED FOR PIN TYPE CONNECTOR TO DEVICE HOUSING CONNECTIONS. THE HEAT SHRINK TUBING COST IS INCIDENTAL TO THE COST OF THE COAXIAL CABLE AND EACH ACTIVE AND PASSIVE DEVICE INSTALLED.

FOR ALL CONNECTIONS OF FLOODED COAXIAL CABLE, CABLE CLAMPS, BREEZE PART NO. 3604, SHALL BE USED ON THE FLOODED COAXIAL CABLE TO PREVENT THE JACKET FROM SLIPPING BACK ON CABLE. THE CABLE CLAMPS SHALL BE INSTALLED PRIOR TO INSTALLATION OF THE HEAT SHRINK TUBING, AND THE HEAT SHRINK TUBING SHALL COMPLETELY COVER THE CLAMPS.

COLD SHRINK TAPE, AMP CST11 FUSION REPAIR TAPE, PART NO. 605262-1, SHALL BE USED ON ANY ADAPTER (CHASSIS MOUNTING CONNECTOR TO "F" SERIES FEMALE) CONNECTION NOT LOCATED INSIDE A CABINET OR POLE ENCLOSURE. APPLICATION OF THE COLD SHRINK TAPE SHALL BEGIN 0.5 IN. ON THE HEAT SHRINK TUBING, SO THAT IT COVERS THE ENTIRE LENGTH OF EXPOSED THREADS AT "F" MALE END OF ADAPTER, AND SHALL CONTINUE 1 IN. ONTO THE RG-6 DROP CABLE, SO THAT THE "F" CONNECTOR IS COMPLETELY COVERED.

COLD SHRINK TAPE, AMP CST11 FUSION REPAIR TAPE, PART NO. 605262-1, SHALL BE USED ON ANY ROTATIONAL CONNECTION NOT LOCATED INSIDE A CABINET OR POLE ENCLOSURE. THE COLD SHRINK TAPE SHALL BE APPLIED SO THAT THE ROTATIONAL IS COMPLETELY COVERED.

C.SUSPENSION CLAMPS

THE CONTRACTOR SHALL FURNISH AND INSTALL ALL SUSPENSION CLAMPS AS PER PLANS. ACCEPTABLE DEVICES SHALL BE 3 BOLT GROOVED SUSPENSION CLAMPS (CABLE TV SUPPLY PART # 551G, JOSLYN PART # J1096 OR NORTH ELECTRIC PART # S721046).

D.INCIDENTAL MATERIAL

ALL OTHER CABLE SYSTEM MATERIAL THAT IS REQUIRED AND NOT DESCRIBED IN THIS SPECIFICATION SHALL BE FURNISHED AND INSTALLED AS REQUIRED TO SATISFY THE CABLE DESIGN. THIS "INCIDENTAL MATERIAL" SHALL BE CONSIDERED AS PART OF THE RELATED BID ITEM DELIVERED AND NO ADDITIONAL COMPENSATION PROVIDED.

INSTALLATION OF COAXIAL CABLE AND EQUIPMENT

A.GENERAL

MESSANGER WIRE USED FOR INTERCONNECT WORK SHALL BE ATTACHED TO STEEL

POLES BY WRAP AROUND CLAMPS THAT ARE APPROVED BY THE TRANSPORTATION DIVISION. HOLES MAY NOT BE DRILLED OR BURNED IN ANY POLE WITHOUT THE PERMISSION OF THE DIVISION AND THEN APPROVAL WILL BE ON A POLE-BY-POLE BASIS. ANY PAINT DAMAGED BY BURNING SHALL BE CLEANED AND REPLACED WITH PAINT OF A MATCHING COLOR.

DAMAGE PREVENTION IS THE FIRST CONSIDERATION IN THE INSTALLATION OF CABLE. THE CABLE LASHER SHALL BE IN GOOD WORKING ORDER WITH NO SHARP EDGES THAT COULD DAMAGE THE OUTER SHIELD OF THE CABLE. CABLE ROLLERS SHALL BE USED TO KEEP THE CABLE WITHIN A FEW FEET OF THE MESSENGER WIRE. A CABLE ROLLER SHALL BE PLACED DIRECTLY IN FRONT OF THE LASHER TO ENSURE THAT THE CABLES WILL LAY STRAIGHT AND BE LASHED TO THE MESSENGER WIRE IN THE SAME POSITION. CABLE ROLLERS SHALL BE PLACED AT EACH POLE AS WELL AS ALL ACTIVE AND PASSIVE DEVICES.

DURING AND AFTER INSTALLATION, CABLE SHALL NOT BE ALLOWED TO RUB ON POLE HARDWARE, SPAN CLAMPS, LASHING WIRE CLAMPS, OR ANY OTHER HARD SURFACE. WHEN PLACING CABLES IN RISERS, THE CABLE SHALL NOT COME IN CONTACT WITH THE SHARP EDGES OF THE CONDUIT. BUSHINGS SHALL BE USED IN THESE LOCATIONS. AN EXPANSION LOOP SHALL BE PLACED AT EVERY POLE TO PROVIDE FOR EXPANSION AND CONTRACTION AND TO AVOID CONTACT WITH POLE HARDWARE. WHERE THE CABLE RUNS THROUGH TREES, TREE GUARDS MUST BE USED IF THE TREES CANNOT BE PROPERLY TRIMMED.

THERE SHALL BE NO SPLICES IN THE CABLE, EXCEPT AS DESIGNATED IN THE PLANS.

A.INSTALLATION OF ACTIVE AND PASSIVE EQUIPMENT

1. ALL ACTIVE AND PASSIVE EQUIPMENT SHALL BE MOUNTED BETWEEN 18 IN. AND 48 IN. FROM THE SUSPENSION CLAMP. NO EQUIPMENT SHALL BE MOUNTED MID-SPAN, UNLESS OTHERWISE STATED ON THE PLANS.
2. THE CENTER CONDUCTOR MUST BE THE EXACT LENGTH SPECIFIED BY THE MANUFACTURER OF THE EQUIPMENT BEING INSTALLED.
3. THE CABLE MUST BE PREPARED WITH THE PROPER CORING TOOL AND WIPED CLEAN OF ANY SHAVINGS.
4. WHEN PREPARING CABLE FOR INSTALLATION INTO THE EQUIPMENT, THERE SHALL BE NO MEASURABLE CHANGE IN THE INSIDE DIAMETER OF THE CABLE. USE OF THE CABLE PREPARATION TOOL FOR REMOVING THE ALUMINUM SHEATH IS REQUIRED.
5. THERE SHALL BE NO VISIBLE MARKS ON THE ALUMINUM SHEATH AFTER REMOVAL OF THE POLYETHYLENE JACKET. UTILITY TOOL NO. JST OR EQUIVALENT IS RECOMMENDED.
6. WHEN INSTALLING AN AMPLIFIER AND/OR SPLITTER, A HOUSING-TO-HOUSING CONNECTOR, RATHER THAN A CABLE JUMPER, SHALL BE USED BETWEEN THE TWO PIECES OF EQUIPMENT.
7. SILICONE LUBRICANT SHALL NOT BE USED ON ANY CONNECTOR.

C. SYSTEM BONDING AND GROUNDING

1. THE MESSENGER WIRE SHALL BE GROUNDED AT EACH AMPLIFIER AND POWER SUPPLY LOCATION AND OTHER LOCATIONS AS SPECIFIED IN 625.16 AND AS SHOWN IN TC-84.20 AND TC-84.21. GROUND RODS SHALL CONFORM TO 725.16. THE GROUND WIRE CABLE SHALL BE CROSS-LINKED POLYETHYLENE, #4 AWG COPPER, STRANDED, RHW INSULATED, 600 VOLT RATED. A 10-FT. PLASTIC SHIELD SHALL BE INSTALLED AT EACH LOCATION.
2. ON ALL BONDS, MESSENGER WIRE TO MESSENGER WIRE AND MESSENGER WIRE TO COPPER, THE CLAMP USED MUST BE OF A SUITABLE TYPE THAT WILL PREVENT CORROSIVE ACTION BETWEEN DISSIMILAR METALS.
3. THE CLAMP MUST BE INSTALLED IN THE MANNER PRESCRIBED BY THE MANUFACTURER.
4. WHEN INSTALLING THE CLAMP, THE CUT END OF THE CONDUCTOR MUST NOT PROTRUDE BEYOND THE EDGE OF THE CLAMP.
5. THE BONDING CLAMP MUST BE INSTALLED DIRECTLY TO THE MESSENGER WIRE AND NOT ON ANY PART OF THE DEAD-ENDING HARDWARE.
6. ALL BONDING AND GROUNDING CONDUCTORS MUST NOT HAVE ANY RIGHT ANGLE BENDS. ALL BENDS MUST BE AS GRADUAL AS POSSIBLE AND STILL MAINTAIN AN ORDERLY APPEARANCE.
7. ALL DEAD-END BONDS OR GROUNDS MUST BE COMPLETED ALONG WITH THE INSTALLATION OF MESSENGER WIRE.
8. THE MESSENGER WIRE MUST BE GROUNDED TO A LOW-IMPEDANCE GROUND (10 OHMS OR LESS) IF IT IS PLACED ON POLES CARRYING POWER WIRES OR IF IT CROSSES POWER WIRES. THIS PRECAUTION IS NECESSARY TO MINIMIZE THE POSSIBILITY OF ELECTRIC SHOCK, SHOULD THERE BE ACCIDENTAL CONTACT WITH POWER WIRES.
9. GROUNDING AT UTILITY POLES WITH SPARK GAPS, LIGHTNING ARRESTERS OR PRIMARY SWITCHING DEVICES SHALL NOT BE ACCEPTABLE.
10. LOCATION OF GROUND RODS SHALL BE AS SHOWN ON THE INTERCONNECT PLAN SHEETS. SHOULD THE LOCATION SO SPECIFIED BE IN CONFLICT WITH ANY OF THE OTHER PROVISIONS OF THIS SECTION, THE CONTRACTOR IS REQUIRED TO BRING THE SITUATION TO THE ATTENTION OF THE DIVISION'S SIGNAL PLAN REVIEWER.

D. CABLE INSTALLATION

1. THE CABLE SHALL BE LASHED TO THE MESSENGER WIRE USING 0.061 IN. STAINLESS LASHING WIRE, HAVING AN AVERAGE OF ONE WRAP PER LINEAR FOOT OF MESSENGER WIRE. DOUBLE LASHINGS SHALL BE USED.
2. LASHING WIRE SHALL MAINTAIN A CONSISTENT SPIRAL THROUGHOUT THE ENTIRE SPAN, WITHOUT EXCEPTION, AND MUST MAINTAIN A MINIMUM OF 40 LB. PULL DURING AND AFTER INSTALLATION.
3. THERE SHALL BE NO VISIBLE SEPARATION OF MESSENGER WIRE AND CABLE OR TRUNK AND FEEDER CABLE IN MID-SPAN LASHING.
4. TREE GUARDS SHALL BE INSTALLED ON CABLE AND MESSENGER WIRE WHERE LIMBS OR OTHER OBSTACLES ARE WITHIN 4 IN. OF CABLE. TREES WITHIN 2 IN. OF THE CABLE SHALL BE TRIMMED BACK TO 6 IN. FROM THE CABLE.
5. EXPANSION LOOPS SHALL BE OF THE TYPE AND AT THE LOCATION SPECIFIED BY THE TYPICAL DRAWINGS.
6. EXPANSION LOOPS SHALL BE PLACED IN THE FOLLOWING LOCATIONS RELATIVE TO POLES AND DEVICES:
 - A) ON THE INPUT AND OUTPUT OF EACH ACTIVE AND PASSIVE DEVICE USED BY THE CONTRACTOR TO CONSTRUCT THE SYSTEM.
 - B) AT EACH AND EVERY LOCATION WHERE OVERHEAD COAXIAL TRUNK OR FEEDER CABLE ENTERS A CONNECTOR OF ANY TYPE, EXCEPT A "F" CONNECTOR; AN EXPANSION LOOP SHALL NOT BE PLACED ON THE TRUNK CABLE AT A 0.750-IN. CABLE TO "F" CONNECTION OR ON THE FEEDER CABLE AT A 0.500-IN. CABLE TO "F" CONNECTION.
 - C) AT EVERY POLE LOCATION.
 - D) AT EVERY LOCATION WHERE THE CABLE IS BEING SECURED BY MEANS OF A SUPPORT STRAP OR CABLE CONNECTOR, THE CABLE MUST REMAIN PARALLEL TO THE MESSENGER WIRE FOR A MINIMUM OF 3 IN. FROM THE EDGE OF THE SUPPORT OR CONNECTOR.
7. EXPANSION LOOPS SHALL BE PLACED AT A MINIMUM OF 20 IN. FROM THE CENTER OF THE POLE, AND BE SUPPORTED WITH A STRAP AND SPACER ON EACH SIDE OF THE LOOP, WITHIN 6 IN. OF POINT OF CONTACT (SEE EXPANSION LOOP TYPICAL).
8. MINIMUM CABLE BENDING RADIUS SHALL BE AS SPECIFIED BY THE EXPANSION LOOP TYPICAL. FORMING BLOCKS OR EQUIVALENT SHALL BE USED WHEN CABLE IS TO BE BENT.

9. THE LASHED CABLE REQUIRES SUPPORT WHEN IT EXTENDS BEYOND THE POINTS OF TERMINATION OF THE LASHING WIRE. THIS SUPPORT IS NECESSARY TO KEEP THE CABLE IN PLACE AND TO MAINTAIN CLEARANCES BETWEEN THE CABLE SHEATH AND VARIOUS ITEMS OF HARDWARE. A POLYPROPYLENE AERIAL SUPPORT TIE WITH AN INTEGRAL 0.50-IN. SPACER, PANDUIT PART NO. AST20-5-C100, SHALL BE USED TO FASTEN THE CABLE TO THE SUPPORTING MESSENGER WIRE AND MAINTAIN SEPARATION BETWEEN THE CABLE AND MESSENGER WIRE.
10. FIFTEEN (15) FEET OF CABLE SHALL BE COILED IN ALL PULL BOXES WHERE ACTIVE AND PASSIVE DEVICES ARE INSTALLED.
11. WHEN CABLE IS INSTALLED UNDERGROUND INTO AN AMPLIFIER CABINET, 15 FEET OF CABLE SHALL BE COILED IN THE PULL BOX NEAREST TO THAT AMPLIFIER CABINET.
12. WHEN FEEDER CABLE IS INSTALLED UNDERGROUND INTO THE CONTROLLER CABINET, 15 FEET OF UNDERGROUND FEEDER CABLE SHALL BE COILED IN THE PULL BOX NEAREST TO THE CONTROLLER CABINET.
13. WHEN CABLE IS INSTALLED UNDERGROUND INTO A CONDUIT RISER, 15 FEET OF CABLE SHALL BE COILED IN THE PULL BOX NEAREST TO THAT CONDUIT RISER.

CABLE MARKERS

THE CONTRACTOR SHALL INSTALL CABLE MARKERS ON THE COAXIAL CABLE INSTALLED ON THIS PROJECT. THE CABLE MARKERS SHALL BE SUPPLIED BY THE DIVISION OF PLANNING AND OPERATIONS.

IN AERIAL INSTALLATIONS, IT SHALL BE NECESSARY TO INSTALL ONLY ONE CABLE MARKER ON ONE CABLE, EVEN IF THERE ARE MORE THAN ONE CABLE IN THE SAME BUNDLE. THERE SHALL BE A CABLE MARKER INSTALLED ON THE EXPANSION LOOP OF THE COAXIAL CABLE NEAREST EACH POLE ATTACHMENT.

IN UNDERGROUND INSTALLATIONS, A CABLE MARKER SHALL BE INSTALLED ON EACH CABLE IN EACH PULL BOX.



CALCULATED
CHECKED

TRAFFIC SIGNAL GENERAL NOTES

PROJECT NAME



XXXX-E

ITEM 632 INTERCONNECT CABLE, COAXIAL TRUNK, .750-IN. OVERHEAD WITH ACCESSORIES, AS PER PLAN

This cable shall be Commscope Parameter III 750 cable (Part No. P3 750 JCA) or Times Fiber T10 750 Series Semiflex cable (Part No. T10750J).

The cable length shall be marked sequentially on the jacket of the cable. No tracer shall be used on this cable.

This item includes lashing wire, hangers, connectors, and any other accessories necessary to install the coaxial trunk cable (see Cable System Materials section of these specifications).

Payment shall be as per Item 632.

ITEM 632 INTERCONNECT CABLE, COAXIAL FEEDER, .500-IN. OVERHEAD, WITH ACCESSORIES, AS PER PLAN

This cable shall be Commscope Parameter III 500 cable (Part No. P3 500 JCA) or Times Fiber T10 500 Series Semiflex cable (Part No. T10500J).

The cable length shall be marked sequentially on the jacket of the cable. No tracer shall be used on this cable.

This item includes lashing wire, hangers, connectors and any other accessories necessary to install the coaxial feeder cable (see Cable System Materials section of these specifications).

Payment shall be as per Item 632.

ITEM 632 INTERCONNECT CABLE, COAXIAL FEEDER, .500-IN. OVERHEAD, AS PER PLAN

This item is intended to be installed in the same lashing bundle with other Item 632 Interconnect Cable, Coaxial, With Accessories, As Per Plan. Therefore, this item does not include lashing wire, cable markers, hangers and other accessories.

This cable shall be Commscope Parameter III 500 cable (Part No. P3 500 JCA) or Times Fiber T10 500 Series Semiflex cable (Part No. T10500J).

The cable length shall be marked sequentially on the jacket of the cable. No tracer shall be used on this cable.

ITEM 632 INTERCONNECT CABLE, COAXIAL DROP, RG-6 UNDERGROUND, AS PER PLAN

When any portion of the interconnect drop cable is installed in underground conduit, the entire length of interconnect drop cable shall be Commscope 6 Series Drop Cable, Part No. F690BEF.

All "F" series male connectors for coaxial RG-6 cable shall be supplied by and installed by Division of Planning and Operations personnel.

Payment shall be per Item 632.

ITEM 632 MESSENGER WIRE, 7-STRAND, 0.25-IN. DIAMETER WITH ACCESSORIES, AS PER PLAN

The Contractor shall furnish and install messenger wire as shown in the plans to support the coaxial cable system. The cable shall be attached to the messenger wire by a double 0.061-inch stainless spinning wire. Messenger wire shall be rated as extra-high strength and meet the requirements of 732.18. Accessories used with messenger wire shall include thru bolts, eye bolts, suspension hangers, thimbles, preformed guy grips, pole clamps, dead-ends, and three bolt clamps as needed to support the temporary interconnect cable. The messenger wire shall be dead-ended on both sides of a street crossing. Messenger wire shall be attached using thimbles to the clevises of strain pole span wire clamps and to eye bolts. All accessories shall have a rated loading strength equal to or greater than the messenger wire minimum breaking strength.

Payment shall be as per Item 632.

ITEM 632 SIGNALIZATION, MISC.: SPLITTER, TWO-WAY, AS PER PLAN

The two-way splitter shall be RMS Part No. RMS 7502K.

ITEM 632 REMOVAL OF COAXIAL INTERCONNECT CABLE, AS PER PLAN

The Contractor shall salvage and deliver the following items to the City of Columbus, Division of Planning and Operations, at 1820 East 17th Avenue: amplifiers, amplifier cabinet assemblies, pilot generators, power supplies with cabinets, directional couplers, splitters, power inserters, camera and dome assemblies, and camera cabinet assemblies (including all equipment contained within). The Contractor shall dispose of all other items, including coaxial cable, messenger wire, lashing wire, and pole attachment hardware, unless otherwise specified.

The Contractor shall contact the City of Columbus, Division of Planning and Operations, Traffic Maintenance Manager (645-7393) twenty-four (24) hours, not including Saturday and Sunday, in advance to schedule delivery. No item will be accepted without following this procedure. The Traffic Maintenance Manager shall inspect the condition of all salvaged items being presented for delivery. No item damaged by the Contractor will be accepted, and no item shall be considered delivered until the Traffic Maintenance Manager issues a receipt to the Contractor acknowledging acceptance of delivery.

Payment shall be at the lump sum contract bid amount.

ITEM SPECIAL RELOCATION OF AERIAL INTERCONNECT CABLE, AS PER PLAN




The existing signal interconnect cable connecting the Street Name 1/Street Name 2 and Street Name 1/Street Name 3 intersections shall be relocated as detailed within.

Various existing utility poles supporting the existing aerial interconnect cable and devices between these two intersections will be relocated as part of the project. This item is intended to provide for the transfer of the existing interconnect cable(s) to the relocated poles.

The result of the relocation process shall be a continuous interconnect run, without splices, between the devices shown in the plans. It shall be the Contractor's responsibility to ensure that the cable is not damaged during the removal or relocation process. If the cable is damaged, as determined by the City of Columbus Division of Planning and Operations, the Contractor shall furnish and install new interconnect cable between devices. No additional compensation will be awarded for the new cable or its installation.

Payment for the work described above shall be at the lump sum bid amount.

ITEM 625 PULL BOX, 725.08, 27", AS PER PLAN



SUB-SUMMARY OF TRAFFIC SIGNAL AND INTERCONNECT ITEMS				
ITEM NUMBER	TOTAL	UNIT	ITEM DESCRIPTION	REF. SHIT. NO.
625	244	LF	Conduit, Encased, 2", 725.05, As Per Plan	172
625	53	LF	Conduit, Encased, 3", 725.05, As Per Plan	172
625	3	LF	Conduit, 2", 725.04	-
625	377	LF	Conduit, 2", 725.05, As Per Plan	172
625	1	EA	Conduit Riser, 2"	-
625	652	LF	Trench, As Per Plan	172
625	1	EA	Pull Box, 725.08, 27", GL, As Per Plan	175
625	11	EA	Pull Box, As Per Plan	172
625	6	EA	Ground Rod, As Per Plan	172
625	410	LF	No. 4 AWG, 600 Volt Distribution Cable, As Per Plan	172
630	LUMP	SUM	Signs, As Per Plan	172
630	4	EA	Sign Support Assembly, Pole Mounted, As Per Plan	172
630	4	EA	Sign, Double-Faced Street Name (Installation Only)	-
630	4	EA	Removal of Pole Mounted Sign and Storage	-
632	5	EA	Vehicular Signal Head, L.E.D., 3-Section, 12-inch Lens, 1-Way, As Per Plan	172
632	3	EA	Vehicular Signal Head, L.E.D., 5-Section, 12-inch Lens, 1-Way, As Per Plan	172
632	8	EA	Pedestrian Signal Head, As Per Plan	172
632	4	EA	Pedestrian Pushbutton, As Per Plan	172
632	8	EA	Covering of Vehicular Signal Head, As Per Plan	173
632	8	EA	Covering of Pedestrian Signal Head, As Per Plan	173
632	4	EA	Covering of Pedestrian Pushbutton, As Per Plan	173
632	4	EA	Strain Pole Foundation, As Per Plan	173
632	4	EA	Strain Pole, Type TC-81.10, Anchor Base, Design 5, As Per Plan	173
632	1	EA	Sleeve for Anchor Base Foundation, As Per Plan	173
632	345	LF	Messenger Wire, 7 Strand, 3/8 in. Diameter With Accessories	-
632	1	EA	Removal of Traffic Signal Installation, As Per Plan	173
632	316	LF	Signal Cable, 9-Conductor, No. 14 AWG	-
632	991	LF	Signal Cable, 7-Conductor, No. 14 AWG	-
632	1808	LF	Loop Detector Lead in Cable, IMSA 50-2	-
632	14	EA	Detector Loop, As Per Plan	172
632	270	LF	Power Cable, 3-Conductor #6, AWG As Per Plan	173
633	1	EA	Cabinet Foundation, As Per Plan	173/178
633	1	EA	Controller Unit, Type TS-2/A2, With Cabinet (P44). Type TS-1, As Per Plan	173
633	1	EA	Controller Item Misc.: Transceiver Interface Unit, As Per Plan	174
632	2011	LF	Messenger Wire, 7 Strand, 0.25 In. Diameter With Accessories, As Per Plan	175
632	1679	LF	Interconnect Cable, Coaxial Trunk, 0.750-In. Overhead, With Accessories, As Per Plan	175
632	99	LF	Interconnect Cable, Coaxial Feeder, 0.500-In. Overhead, With Accessories, As Per Plan	175
632	500	LF	Interconnect Cable, Coaxial Feeder, 0.500-In. Overhead, As Per Plan	175
632	44	LF	Interconnect Cable, Coaxial Drop, RG-6 Underground, As Per Plan	175
632	1	EA	Signalization Misc.: Splitter, Two-Way, As Per Plan	175
632	LUMP	SUM	Removal of Coaxial Interconnect Cable, As Per Plan	175
SPEC.	LUMP	SUM	Relocation of Aerial Interconnect Cable, As Per Plan	175

TOTALS CARRIED TO GENERAL SUMMARY

CALCULATED
WJF
CHECKED
JDS


TRAFFIC SIGNAL GENERAL NOTES
AND SUB-SUMMARY OF QUANTITIES

PROJECT NAME


X
XX

- NOTES:
- The Contractor shall ensure that all sidewalks/pathways meet ADA guidelines per City specifications.
 - Power, service and interconnect cable shall be continuous with no splices except as noted.
 - For signing and pavement markings, see sheets 165-170.
 - Center all loops in the center of their lane unless specified otherwise. Install loops after the asphalt surface course is laid.
 - The top of the pole base foundation shall be edged using a 1/2" sidewalk edger instead of being chamfered.
 - The Division of Design and Construction Personnel shall approve bolt alignment, pole foundation location and elevation prior to the Contractor installing the foundation.
 - Tagging of cable in the 27" or 32" pull box next to the control cabinet is not required except for tagging of certain cable as directed by the Project Engineer or as per plan.
 - The pedestrian signal head unit shall be aimed at the centerline of the crosswalk area (not the curb ramp) that is opposite of the unit. The pedestrian unit shall also have a slight downward angle to it.
 - Do not encase the ground rod, the grounding wire or the EMT conduit in concrete outside of their foundation. Full access to these items must be maintained at all times. Permanently mark the top of concrete, if visible, with a marker or symbol so the rod location can be known by others.
 - Any signal support base foundation within or adjacent to a sidewalk area shall be flush with the top of the sidewalk.
 - The Contractor shall not install pole foundations until the pole location area is at finished grade.
 - Underground conduit and trench that are under proposed sidewalk or roadway areas shall be installed prior to the placement of sidewalks or any asphalt or concrete roadway course.
 - The Contractor shall provide and install power and/or service cable between the control cabinet and the designated power source location. The triplex power service cable shall be run separately and shall not be bundled with any other cable.
 - See interconnect schematic sheets XXX-XXX for interconnect items.
 - The control cabinet door shall be located on the NORTHEAST side of the cabinet.
 - The cabinet foundation shall be placed adjacent to the back of the sidewalk. The top surface of a cabinet foundation located next to sidewalk areas shall be 4" above the surrounding walk. Expansion material shall be used between all foundations and adjacent sidewalk.
 - Use a separate conduit for each grouping of cables unless otherwise indicated: one conduit for 120VAC signal cable (5C, 7C, 9C); one conduit for power; one conduit for 2 conductor cable (loop & pushbutton); and one conduit for interconnect cable (twisted pair, fiber optics or coax). Any other low voltage cable not specified above can be placed in the 2 conductor cable conduit. Power cable must be in its own conduit.
 - Unless otherwise specified the following shall apply. A preformed PVC conduit elbow shall be used to change the PVC conduit direction beyond what its natural bending flex would yield. Rigid metal conduit can be bent to form an elbow or any other bending angle required only if a proper conduit bending machine is used. The elbow radius for any non-interconnect conduit shall be 24" or larger when used in a horizontal or vertical manner. Any type of elbow used for interconnect conduit shall have a radius of 36" or larger when used in a horizontal direction or in a vertical direction when the trench is 36" or deeper. If the trench is less than 36" then the vertical elbow radius shall be 24".
 - All clamps and banding material shall be painted to match the signal supports.
 - Run the RG-6 cable into the cabinet. Coil 5 ft of RG-6 cable in the cabinet. Connect the RG-6 cable to the feeder cable. Make certain that the RG-6 conduit clears the load switch rack support.


LEGEND



UTILITY NOTES:
 1. ACTUAL LOCATIONS FOR RELOCATED UTILITY POLES WILL BE PER THE UTILITY OWNER. LOCATIONS SHOWN ARE FOR REFERENCE PURPOSES ONLY.



TRAFFIC SIGNAL HEADS



ITEM 632 REMOVAL OF TRAFFIC SIGNAL INSTALLATION, AS PER PLAN

QUANTITY	REMOVED ITEM DESCRIPTION	DELIVERED TO 1820 E 17TH AVE	DISPOSED OF BY PROJECT	REUSE WITH TEMPORARY
1	SIGNAL POLE (EMBEDDED)	X		
8	VEHICULAR SIGNAL HEAD	X		
8	PEDESTRIAN SIGNAL HEAD	X		
1	POLE MT'D CONTROLLER	X		
4	POLE MT'D SIGN	X		
1	POLE FOUNDATIONS		X	
LUMP	SIGNAL CONDUIT		X	
LUMP	MESSENGER WIRE		X	
LUMP	SIGNAL CABLE		X	

* = CONDUIT SHALL BE REMOVED WHERE CONFLICTS WITH PROPOSED IMPROVEMENTS EXIST.

PROJECT NAME

TRAFFIC SIGNAL PLAN

STREET NAME 1 AT STREET NAME 2

XXXX-E

FIELD WIRING HOOK-UP CHART

SIGNAL HEAD #	INDICATION	FIELD TERMINAL	FLASH	SIGNAL HEAD #	INDICATION	FIELD TERMINAL	FLASH
1 (WBLT)	R	ø2 R	Y	W	DON'T WALK	ø4-DW	OFF
	Y	ø2 Y			WALK	ø4-W	
	G	ø2 G			DON'T WALK	ø6-DW	
	ø5 Y	ø6-W					
2 (WB)	R	ø2 R	Y	S	DON'T WALK	ø2-DW	OFF
	Y	ø2 Y			WALK	ø2-W	
	G	ø2 G			DON'T WALK	ø8-DW	
	ø8 R	ø8-W					
3 (NBLT)	R	ø8 R	R	E	DON'T WALK	ø8-DW	OFF
	Y	ø8 Y			WALK	ø8-W	
	G	ø8 G			DON'T WALK	ø8-DW	
	ø3 Y	ø8-W					
4 (NB)	R	ø8 R	R	E	DON'T WALK	ø8-DW	OFF
	Y	ø8 Y			WALK	ø8-W	
	G	ø8 G			DON'T WALK	ø8-DW	
	ø3 G	ø8-W					
5 (EBLT)	R	ø6 R	Y	E	DON'T WALK	ø8-DW	OFF
	Y	ø6 Y			WALK	ø8-W	
	G	ø6 G			DON'T WALK	ø8-DW	
	ø1 Y	ø8-W					
6 (EB)	R	ø6 R	Y	E	DON'T WALK	ø8-DW	OFF
	Y	ø6 Y			WALK	ø8-W	
	G	ø6 G			DON'T WALK	ø8-DW	
	ø6 G	ø8-W					
7 & 8 (SB)	R	ø4 R	R	E	DON'T WALK	ø8-DW	OFF
	Y	ø4 Y			WALK	ø8-W	
	G	ø4 G			DON'T WALK	ø8-DW	
	ø4 G	ø8-W					


SIGNAL HEAD & CABINET FIELD WIRING HOOK-UP

SIGNAL DISPLAY	WIRE COLOR	PER APPROACH
THRU R	RED	
THRU Y	ORANGE	
THRU G	GREEN	
L/T R	BLACK (FUTURE ONLY)	
L/T Y	WHITE W/BLACK TRACER	
L/T G	BLUE	
R/T Y	RED W/BLACK TRACER	
R/T G	GREEN W/BLACK TRACER	

PED UNIT FIELD WIRING HOOK-UP

PED UNIT LOCATION	CROSSWALK DISPLAY	WIRE COLOR
SOUTH	WALK	BLACK
	DONT WALK	ORANGE
WEST	WALK	GREEN
	DONT WALK	RED
NORTH	WALK	BLUE
	DONT WALK	WHITE W/BLACK TRACER
EAST	WALK	GREEN W/BLACK TRACER
	DONT WALK	RED W/BLACK TRACER


NOTES:
White shall be used for common. Splice all wires in the signal head or ped unit. Use #14 AWG 2 wire spade terminal for 2 wire connections and #14 AWG 1 wire spade terminal for single wire connections on all wires to all field terminals. Use butt splices on all through wires. All unused wires shall be spliced through and shall have a dead-end terminal at the end of the wire.



- Notes:
- Set conflict monitor for 10 sec flash.
 - Loop detector lead-in cable shall be used for the pedestrian pushbuttons. Ground the shield only at the cabinet.
 - All loop spade terminals shall have the loop homerun wire soldered to the spade terminal. The loop homerun wires shall be twisted together as close to the spade terminal screws as possible. The cable drain wire shall be connected to the closest grounding point. Solder the loop wire and homerun connection.
 - Back Panel Wiring (front side jumpers only)
 - Hard wire 'ped recycle' to ground. Hook the detector count output to the CICU system inputs as indicated.
 - Install a diode between terminals, ø2 'ø ON' output and 'ø1 OMIT' input, so the left turn phase (ø1) is omitted during the through phase (ø2).
 - Install a diode between terminals, ø6 'ø ON' output and 'ø5 OMIT' input, so the left turn phase (ø5) is omitted during the through phase (ø6).
 - Use diodes to prevent feedback on multi-use terminals.
 - Install diodes to prevent phase green feedback between phases 4 & 7 and phases 3 & 8.
 - Controller Software Programming
 - Initialize in ø2 & ø6 green
 - Enable dual entry. Activate ø4 & ø8.
 - Enable simultaneous gap out. Activate ø2, ø4, ø6 & ø8.

WIRING-DIAGRAM LEGEND

- L-2 Loop Detector
- Power Source (AEP)
- 3/C #6 AWG (Power)
- Vehicular Signal Head
- Pedestrian Signal Head
- Pedestrian Push Button



DETECTOR ASSIGNMENTS

DET #	DETECTOR ASSIGNMENT		PHASE	LOOP SIZE	NO. TURNS	LOOP DELAY DATA		DET UNIT RACK & CABLE LABEL
	UNIT #	CHAN #				DELAY IN SECONDS	INHIBIT DELAY DURING GRN ø	
L1	1	1	ø6	6'X6'	3	-	-	EB
L2	1	2	ø1	5'X25'	2	2	ø1	EBLT
L3	2	1	ø5	5'X25'	2	2	ø5	WBLT
L4	2	2	ø2	6'X6'	3	-	-	WB
L5	3	1	ø3	5'X25'	2	2	ø3	NBLT (F)
L6	3	2	ø8	5'X31'	2	2	ø8	NBLT (N)
L7	4	1	ø8	5'X30'	2	5	ø8	NB
L8	4	2	ø4	5'X31'	2	2	ø4	SBLT
L9	5	1	ø4	5'X30'	2	10	ø4	SB

Note:
Loops are to be hooked to the unit and channel as indicated to enhance loop performance and decrease loop crosstalk.

TIMING CHART

PHASE	ø1	ø2	ø3	ø4	ø5	ø6	ø7	ø8
MOVEMENT	EBLT	WB	NBLT	SB	WBLT	EB	SBLT	NB
MIN INITIAL	7	15	7	10	7	15	-	10
PASS TIME	3.0	3.0	3.0	3.0	3.0	3.0	-	3.0
MAX GRN 1	15	40	15	40	15	40	-	40
MAX GRN 2	99	60	99	99	99	60	-	99
YELLOW	3.6	3.6	3.6	3.6	3.6	3.6	-	3.6
RED CLR	2.0	2.0	2.0	2.0	2.0	2.0	-	2.0
WALK	-	7	-	7	-	7	-	7
PED CLR	-	12	-	13	-	15	-	13
PED RECALL	OFF	ON	OFF	OFF	OFF	ON	-	OFF
VEH RECALL	OFF	MIN	OFF	OFF	OFF	MIN	-	OFF
MEMORY	OFF	ON	OFF	OFF	OFF	ON	-	OFF

CICU INPUT CONNECTOR

HARNESS PIN	HARNESS FUNCTION	BOX FUNCTION
13	PHASE 1 GREEN	EBLT GREEN (PHASE 1)
8	PHASE 2 GREEN	WB THRU GREEN (PHASE 2)
7	PHASE 3 GREEN	NBLT GREEN (PHASE 3)
6	PHASE 4 GREEN	SB THRU GREEN (PHASE 4)
12	PHASE 5 GREEN	WBLT GREEN (PHASE 5)
11	PHASE 6 GREEN	EB THRU GREEN (PHASE 6)
18	PHASE 7 GREEN	SBLT GREEN (PHASE 7)
3	PHASE 8 GREEN	NB THRU GREEN (PHASE 8)
10	WALK 1 MONITOR	PHASE 4 WALK
16	WALK 2 MONITOR	PHASE 8 WALK
22	PED CALL 1 (SYSTEM DETECTOR 7)	PHASE 4 PED CALL
36	PED CALL 2 (SYSTEM DETECTOR 8)	PHASE 8 PED CALL
4	FLASH	SIGNAL POWER
15	PREEMPT	MANUAL CONTROL ENABLE
2	SPECIAL FUNCTION 1 MONITOR	110 V OUTPUT FROM 24 VDC RELAY SENSING PHASES 1 & 5 OMIT ACTIVE
1	SPECIAL FUNCTION 2 MONITOR	110 V OUTPUT FROM 24 VDC RELAY SENSING PHASE 3 OMIT ACTIVE
5	SPECIAL FUNCTION 3 MONITOR	
24	ADDRESS-1	LOGIC GROUND
25	ADDRESS-2	LOGIC GROUND
30	ADDRESS-4	LOGIC GROUND
31	ADDRESS-8	
32	ADDRESS-16	
26	ADDRESS-32	
27	ADDRESS-64	
21	ADDRESS-128	LOGIC GROUND
29	SYSTEM DETECTOR 1	
34	SYSTEM DETECTOR 2	
35	SYSTEM DETECTOR 3	
37	SYSTEM DETECTOR 4	
33	SYSTEM DETECTOR 5	
28	SYSTEM DETECTOR 6	
20	RETURN FOR AC MONITOR	AC-
23	RETURN FOR NEMA MONITOR	LOGIC GROUND


CICU OUTPUT CONNECTOR

HARNESS PIN	HARNESS FUNCTION	BOX FUNCTION
25	HOLD (COMMON)	LOGIC GROUND
21	HOLD (N.O.)	RING 1 & RING 2: MAX2 + CALL-TO-NONACTUATED I
28	HOLD (COMMON)	LOGIC GROUND
5	HOLD (N.O.)	PHASES 2 & 6 HOLD
8	FORCE OFF 1 (COMMON)	LOGIC GROUND
10	FORCE OFF 1 (N.O.)	FORCE OFF 1 (RING 1)
31	FORCE OFF 2 (COMMON)	LOGIC GROUND
20	FORCE OFF 2 (N.O.)	FORCE OFF 2 (RING 2)
24	CALL ALL (COMMON)	LOGIC GROUND
30	CALL ALL (N.O.)	PHASES 1, 3, 4, 5, & 8 VEH CALL, DIODE SEPARATE
12	FLASH (COMMON)	LOGIC GROUND
4	FLASH (N.O.)	FLASH SYNCHRONIZER
32	SPECIAL FUNCTION 1 (COMMON)	LOGIC GROUND
26	SPECIAL FUNCTION 1 (N.O.)	PHASES 1 & 5 OMIT
17	SPECIAL FUNCTION 2 (COMMON)	LOGIC GROUND
11	SPECIAL FUNCTION 2 (N.O.)	PHASE 3 OMIT
22	SPECIAL FUNCTION 3 (COMMON)	LOGIC GROUND
9	SPECIAL FUNCTION 3 (N.O.)	
1	AC+	AC+
2	AC-	AC-
3	GROUND	EARTH GROUND


DROP #XXX TRUNK #X, AND INT #XXXX

PUSHBUTTON & SIGN INSTALLATION


CM-R73
PUSH BUTTON TO CROSS STREET NAME
Contact the Division of Planning & Operations for CM-R73 sign details. Mount the center of the pushbutton 42" above the pedestrian pathway. Mount the signs just above the pushbutton housing.



For pushbutton located at the back of a landing area.
For pushbutton located at the side of a landing area.



VEHICLE DETECTOR DETAILS (No Scale)



MULTIPLE LOOP DETECTOR INSTALLATION DETAIL (No Scale)



CALCULATED
CHECKED



TRAFFIC SIGNAL DETAILS
STREET NAME 1 AT STREET NAME 2

PROJECT NAME


XXXX-E

INTERSECTION	SHEET NO.	POLE SIZES & SPAN ATTACHMENT HEIGHT					POLE FABRICATION DATA CLOCKWISE FROM HANDHOLE AT 0 DEGREES					FIELD ORIENTATION		
		POLE DESIGNATION	POLE DESIGN NO. (TC-81.10)	POLE HT. (FT.)	ATTACHMENT HT. (FT.)		ANCHOR BOLT REF. LINE	2" BHC ANGLE/HT. (DEG.)/(FT.)	3" BHC ANGLE/HT. (DEG.)/(FT.)	PED. SIGNALS	PED. PUSH BUTTON	INDEX LINE ANGLE (HANDHOLE)	ANCHOR BOLT REF. LINE	UNUSED *2-2" CONDUIT ELL (CAPPED)
					SPAN @ HT. (FT.) 4% SAG	SPAN @ HT. (FT.) 4% SAG								
STREET NAME 1 @ STREET NAME 2	176	A	5	29'	A-B @ 23.5	A-D @ 25.5	90°		180°/28'	229°/319'	255°	234°	54°	*125'
		B	5	29'	B-A @ 23.5	B-C @ 25.0	90°		180°/28'	29°/131°	295°	144°	54°	270°
		C	5	28'	C-B @ 24.5	C-D @ 23.0	90°		180°/27'	238°/330°	246°	235°	55°	125°
		D	5	28'	D-C @ 23.0	D-A @ 25.0	90°		180°/27'	39°/134°	119°	135°	45°	250°


*NOTE: One unused 2" conduit (capped) for Pole A.



- NOTES:
- All angles measured clockwise.
 - Index line goes through the center of the handhole.



TYPICAL STRAIN POLE ORIENTATION DETAIL




NOTE:
The lowest signal head height in each direction shall be set at 16.5 Feet. Adjust the span accordingly.

See ODOT Standard Drawing TC 21.20 for Foundation Details.
See ODOT Standard Drawing TC 81.10 for Additional Pole Data.

TYPICAL SIGNAL ELEVATION

TC 81.10/81.20 POLE FOUNDATION IN SIDEWALK AREA



LEVEL & SLOPE THE SUBGRADE AS SHOWN. COMPACT THE SUBGRADE AROUND THE FOUNDATION. THOROUGHLY CLEAN THE CONCRETE FOUNDATION SURFACE SO THE WALK CONCRETE WILL BOND.

LEAVE THE FOUNDATION CONCRETE DOWN 8" TO 9". POUR THE WALK CONCRETE OVER THE LOWERED FOUNDATION.


WHEN POURING WALK, EMBED 1/2" THICK EXPANSION JOINT FILLER (ODOT 608.03C & 705.03). FORM A 3'x3' SQUARE & CENTER THE JOINT FILLER AROUND THE FOUNDATION AS DIRECTED BY TRANS. DIV. SIGNAL INSPECTION PERSONNEL. ORIENTATE THE FILLER SQUARE PARALLEL TO OTHER GEOMETRIC LINES.

CALCULATED
CHECKED

SIGNAL POLE FABRICATION AND ORIENTATION DETAILS

PROJECT NAME

X
XX




CALCULATED WJF
CHECKED JDS

SIGNAL INTERCONNECT PLAN
STREET NAME 1

PROJECT NAME

XXXX-E
XX



NEW MESSENGER WIRE W/(1)-NEW
0.750" TRUNK CABLE = 85'

Ex. Aerial Interconnect (REMOVE)
Ex. Pole (RELOCATED BY AEP)

NEW MESSENGER WIRE W/(1)-NEW
0.750" TRUNK CABLE = 37'

Ex. Pole (TO REMAIN)

NEW MESSENGER WIRE W/(1)-NEW
0.750" TRUNK CABLE = 54'

NEW MESSENGER WIRE W/(1)-NEW
0.750" TRUNK CABLE = 72'

NEW MESSENGER WIRE W/(1)-NEW
0.750" TRUNK CABLE = 111'

NEW MESSENGER WIRE W/(1)-NEW
0.750" TRUNK CABLE = 85'

Match Line Sta. 141+50 - See Sheet XX

Match Line Sta. 147+00 - See Below

NEW MESSENGER WIRE (2' ABOVE SIGNAL WIRES)
W/(1)-NEW 0.750" TRUNK CABLE = 165'

EX. Aerial Interconnect
DELASH AND RELOCATE EX. 0.750" TRUNK CABLE
FROM UTILITY POLE TO SIGNAL POLE C ON N.E. CORNER
REMOVE MESSENGER WIRE

NEW MESSENGER WIRE (2' ABOVE SIGNAL WIRES)
W/(1)-NEW 0.750" TRUNK CABLE = 62'
W/(1)-NEW 0.500" FEEDER CABLE = 62'

NEW MESSENGER WIRE W/(1)-NEW
0.750" TRUNK CABLE = 47'

NEW MESSENGER WIRE W/(1)-NEW
0.750" TRUNK CABLE = 145'

SIGNAL POLE B (SEE SIGNAL PLAN)

EX. Aerial Interconnect Splitter
(REMOVE)

EX. GUY POLE
(TO BE REMOVED BY AEP)

SIGNAL POLE C
(SEE SIGNAL PLAN)
W/(1)-2-WAY SPLITTER,
WEST SIDE OF POLE

NEW MESSENGER WIRE
W/(1)-NEW 0.750" TRUNK CABLE = 37'
W/(1)-NEW 0.500" FEEDER CABLE = 37'

Match Line Sta. 147+00 - See Above

Match Line Sta. 151+50 - See Sheet XX

LEGEND

- Centerline of Road
- Right-of-Way: Existing Ex R/W Proposed Prop R/W
- Fence Line
- Utility Poles: Power Telephone Combination
- Signal Poles: Existing Proposed
- Signal Pull Box: Existing Proposed
- Signal Controller: Existing Proposed
- New Interconnect Cable: IC
- Relocated Interconnect Cable:

SIGNAL POLE A (SEE SIGNAL PLAN)
STA. 149+33.7, 27.2' RT.

(1)-3" CONDUIT
W/(1)-RG-6 (FLOODED)
ENCASED IN TRENCH = 17'
PULL BOX (27" RND.)
INTERCONNECT CONDUIT SHALL
NOT ENTER THIS PULL BOX.
(SEE SIGNAL PLAN)
STA. 149+40.9, 38.2' RT.

GROUND MOUNTED CONTROLLER
(SEE SIGNAL PLAN)
STA. 149+42.9, 42.1' RT.

(1)-MESSENGER WIRE (2' ABOVE SIGNAL WIRES)
W/(1)-0.500" FEEDER CABLE = 99'

(1)-MESSENGER WIRE (2' ABOVE SIGNAL WIRES)
W/RELOCATED AND RELASHED 0.750" TRUNK CABLE
AND (1)-NEW 0.500" FEEDER CABLE = 65'

(1)-MESSENGER WIRE = 17'

RELOCATED 0.750 AERIAL TRUNK CABLE
W/NEW MESSENGER WIRE = 71'

EX. Aerial Interconnect
DELASH EX. 0.750" TRUNK CABLE AND RELOCATE


NOTES:
1. ACTUAL LOCATIONS FOR RELOCATED
UTILITY POLES WILL BE PER THE UTILITY
OWNER. LOCATIONS SHOWN ARE FOR
REFERENCE PURPOSES ONLY.

SUB-SUMMARY OF LIGHTING ITEMS

ITEM NUMBER	MIS NUMBER	QUANTITY TOTAL	UNIT	ITEM DESCRIPTION	REF
1000	1	5	EA	Down Guy Anchor	
1000	6	1	EA	12' Aluminum Bracket (For Wood Pole)	
1000	10	15	EA	8' Aluminum Bracket (For Wood Pole)	
1000	26	3	EA	Overhead Circuit Ground Unit	
1000	42	3	EA	Pole, Wooden, 35' - V	
1000	46	1	LUMP	System Removal, Existing Overhead	
1000	68	16	EA	Clean and Re-Lamp HPS Luminaires	
1000	11	2507	LF	Overhead Circuit #2 AWG Aluminum (2 wire)	
Spec.	-	1	EA	Alley Arm (2-8' Crossarms)	
Spec.	-	1	LUMP	Transfer Secondary Conductor	
Spec.	-	1	LUMP	Transfer Primary Conductor, Install Alley Arm	
Spec.	-	2	EA	Bollard	
1000	-	1	EA	Pole, Wooden, 40' - 3	

TOTALS CARRIED TO GENERAL SUMMARY

NOTE:
ACTUAL LOCATIONS FOR RELOCATED UTILITY POLES WILL BE PER THE UTILITY OWNER. LOCATIONS SHOWN ARE FOR REFERENCE PURPOSES ONLY.



- LEGEND**
- Existing Overhead Circuit
 - Proposed Overhead Circuit
 - Other Overhead Electric or Communication
 - ⊙ Pole W/Telephone, Power and Lighting
 - AEP - American Electric Power
 - DOPW(P) - Division Of Power And Water (Power)
 - TBR - To Be Removed
 - TBRL - To Be Relocated

SCALE

CALCULATED

CHECKED

LIGHTING PLAN

PROJECT NAME

X
XX



HORIZ. SCALE



CALCULATED
CHECKED


LANDSCAPE PLAN STA. 150+00 TO STA. 154+00
LANDSCAPE PLAN STA. 124+00 TO STA. 130+50

PROJECT NAME

X
XX

XXXX-E

REVISION 12/2/11




STREET NAME
SCALE: 1" = 40'

Existing shrubs to remain

SEE PREVIOUS SHEET FOR (STREET NAME)
TREES WEST OF (STREET NAME)

Sta. 154+00




STREET NAME
SCALE: 1" = 30'

LEGEND:



- ACE - MOZART AMUR MAPLE
- MAA - STARBURST AMUR MAACKIA
- SYR - IVORY SILK TREE LILAC
- EXISTING DECIDUOUS TREE TO REMAIN
- EXISTING EVERGREEN TREE TO REMAIN
- EXISTING SHRUBS TO REMAIN

ITEM NO.	ESTIMATE QUANTITIES	KEY	UNIT	DESCRIPTION
PLANTING				
SPEC	44	ACE	EACH	ACER ginnala 'MOZART' MOZART AMUR MAPLE 2" CAL. B&B
SPEC	32	MAA	EACH	MAACKIA amurensis 'STARBURST' STARBURST AMUR MAACKIA 2" CAL. B&B
SPEC	10	SYR	EACH	SYRINGA retic ulata 'IVORY SILK' IVORY SILK TREE LILAC 2" CAL. B&B, TREE FORM
MISC.				
SPEC	2150		GAL.	LANDSCAPE WATERING (25 GAL./TREE)


NOTE:
REMOVE DEAD & BROKEN BRANCHES
& ALL SUCKER GROWTH. DO NOT DAMAGE
OR REMOVE CENTRAL LEADER.



STREET TREE PLANTING
N.T.S.



**SUGGESTED DETAIL TO FORM
1 1/2" DEEP KEY FOR CONCRETE WALL**
(1 1/2" = 1'-0")



SECTION D-D
(1 1/2" = 1'-0")

RETAINING WALLS			503	601	SPECIAL	
REF. NO.	STATION	SIDE	UNCLASSIFIED EXCAVATION	ROCK CHANNEL PROTECTION TYPE B WITH FILTER	RETAINING WALL	
			LUMP SUM	C.Y.	LUMP SUM	
R1	124+00	124+90	RT	1	60	1
R2	124+72	125+15	LT	1	-	1
SHEET TOTALS				2	60	2

GENERAL NOTES

All labor, material, and equipment necessary to construct the retaining wall as detailed on these plans, including excavation, backfill, concrete, reinforcement, joints, drainage, fence and incidentals shall be included in the lump sum price bid for Retaining Walls.

All existing drainage courses shall be maintained during construction and placement of the proposed structure. The contractor shall submit to the City of Columbus a Schedule of Sequence and Method of maintaining the watercourse. Special attention shall be observed to insure that all erosion control features are installed and maintained throughout the duration of the project. Adequate precautions shall be taken to prevent concrete from freezing.

The contractor shall supply 6 sets of reinforcing steel shop drawings to XXX for a plan conformance review. Five sets of the reviewed drawings will be returned to the contractor for distribution.

The foundation, as designed, will produce a bearing pressure of 1.25 ton per square foot (2500 psf). Bottom of footings shall be cast against undisturbed earth.

If unsuitable bearing material occurs at the bottom of the footing elevation, the footing shown shall be deepened or widened to accommodate the changed condition. A registered soil engineer employed by the City of Columbus shall verify the suitability of the bearing material prior to placement of any concrete for the footing. The engineer must approve any changes in the footing.

Construction joints shall be provided as shown on the plans. Additional joints requested by the contractor shall be submitted for review and approval by the engineer. All vertical wall joints shall contain waterstop. Waterstop for vertical construction joints shall be approved prior to installation.




Porous backfill shall be placed behind the retaining wall and shall extend from below the walk to 6" below the weephole elevation. Place two cubic feet of bagged aggregate at each weephole.

Backfill shall not be placed and the structure shall not impound water until concrete has achieved 4000 psi. Water shall not be impounded against the structure until backfill is in place.

All exposed non-reentrant corners of concrete shall be cast with a 3/4" x 3/4" chamfer.

Railing shall be chain link fence. Posts that are to be mounted on wall shall be according to details on this sheet. Railing, posts, plates and anchors shall be galvanized.


All concrete surfaces above grade shall be treated with a clear sealer designed to protect concrete surfaces from graffiti. The material shall be applied in conformance with manufacturer's recommendations. One brand of sealer shall be used for all treated surfaces. Contractor shall provide owner with 5 gallons of unopened sealer for future use by owner. Cost of additional sealer provided to owner shall be included in the price for the wall. Sealer shall be approved prior to application.




RETAINING WALLS
SECTIONS AND GENERAL NOTES

PROJECT NAME


XXXX-E




R2 - WEST WALL (WEST ELEVATION)



FOOTING STEP DETAIL
(1" = 1'-0")



R1 - EAST WALL (EAST ELEVATION)



RETAINING WALL DETAILS

PROJECT NAME

X
XX

XXXX-E

REVISED 12/2/11

ROAD NO. 1

SECTION 2 AND SECTION 3, TOWNSHIP 4, RANGE 22, CONGRESS LANDS CITY OF COLUMBUS FRANKLIN COUNTY, OHIO



BASIS FOR BEARINGS:
ALL BEARINGS SHOWN ARE FOR PROJECT USE ONLY. BEARINGS ARE BASED ON THE OHIO STATE PLANE COORDINATE SYSTEM, OHIO SOUTH ZONE, NAD83 (1986 ADJUSTMENT), WITH A BEARING OF N03°52'47"E ESTABLISHED ALONG THE CENTERLINE OF ROAD NO. 1, AND ALL OTHER BEARINGS CALCULATED FROM THIS MERIDIAN.

NOTE: THE EXISTING R/W WIDTH AND LOCATION WERE DETERMINED BY USING FRA-104-8.73 RIGHT-OF-WAYS PLAN, ON FILE WITH THE DEPARTMENT OF TRANSPORTATION, DIST. 6 AND RECORDED PROPERTY DEEDS.


CONVENTIONAL SIGNS

- Fence Line (existing) - - - - (proposed) - - - -
- Center Line - - - -
- Trees, Stumps (to be removed)
- Utility Poles: Telephone ϕ , Power ϕ , Light ϕ
- Permanent Drainage Easement - P -
- Temporay Construction - TMP -
- Easement - - - -
- Exist. Right of Way - EX. R/W -
- Property Line - P - (in existing fence)
- Guardrail (existing) σ σ σ (proposed)

PROPERTY MAP
SCALE: 1" = 200'



- MONUMENT LEGEND**
- ϕ RAILROAD SPIKE FOUND
 - \circ P.F. PIN FOUND
 - \oplus P.F. PIPE FOUND
 - \odot PS PIPE SET (3/4" I.D. HOLLOW STEEL PIPE, 30 INCHES LONG, WITH PLASTIC CAP INSCRIBED "CEC, INC.")



PERMANANT DRAINAGE EASEMENT

LINE	BEARING	DISTANCE
L1	S03°52'47"W	72.00'
L2	N86°07'13"W	11.30'
L3	N03°52'47"E	16.90'
L4	N46°07'21"W	52.79'
L5	N03°52'47"E	21.16'
L6	S86°07'13"E	51.75'

TEMPORARY EASEMENTS LINE TABLE


LINE	BEARING	DISTANCE
L7	S03°52'47"W	48.00'
L6	N86°07'13"W	51.75'
L5	S03°52'47"W	21.16'
L4	S46°07'21"E	52.79'
L3	S03°52'47"W	16.90'
L2	S86°07'13"E	11.30'
L8	S03°52'47"W	8.37'
L9	N86°07'13"W	12.30'
L10	N46°07'21"W	64.55'
L11	N03°52'47"E	86.88'
L12	S86°07'13"E	61.75'
L13	S86°07'13"E	20.00'
L14	S03°52'47"W	55.00'
L15	N86°07'13"W	20.00'
L16	N03°52'47"E	55.00'

LEAD-IN COURSES LINE TABLE

LINE	BEARING	DISTANCE
LE1	N86°07'13"W	20.00'
LE2	S03°52'47"W	48.00'
LE3	S86°07'13"E	20.00'

UTILITY	UTILITY OWNER	UTILITY	UTILITY OWNER
TELEPHONE	AT&T (FORMERLY SBC) 150 EAST GAY STREET ROOM 7A COLUMBUS, OHIO 43215 (614) 223-4784	GAS	COLUMBIA GAS OF OHIO 920 WEST GOODALE STREET COLUMBUS, OHIO 43212 (614) 280-7372
ELECTRIC	AEP 850 TECH CENTER DRIVE GAHANNA, OHIO 43230 (800) 277-2177	ELECTRIC	CITY OF COLUMBUS DIVISION OF ELECTRIC 3500 INDIANOLA AVENUE COLUMBUS, OHIO 43214 (614) 645-7758
WATER	CITY OF COLUMBUS DIVISION OF WATER 910 DUBLIN ROAD COLUMBUS, OHIO 43215 (614) 645-7788	SEWERS	CITY OF COLUMBUS DIVISION OF SEWAGE 910 DUBLIN ROAD COLUMBUS, OHIO 43215 (614) 645-7175
CABLE TV	TIME WARNER CABLE 1266 DUBLIN ROAD COLUMBUS, OHIO 43215 (614) 481-5363		

THE LOCATION OF UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE AS OBTAINED FROM THE OWNERS OF THE UTILITY AS REQUIRED BY SECTION 153.64 O.R.C.



TOTAL NUMBER OF :
3 OWNERSHIPS 0 TOTAL TAKES
3 PARCELS 0 OWNERSHIPS W/ STRUCTURES INVOLVED

SUMMARY OF ADDITIONAL RIGHT-OF-WAY

ALL AREAS IN ACRES

GRANTEE:
ALL EASEMENTS ACQUIRED IN THE NAME OF
CITY OF COLUMBUS, UNLESS OTHERWISE SHOWN.

PARCEL NO.	OWNER	SHEET NO.	OWNERS RECORD		AUDITOR'S PARCEL	RECORD AREA	TOTAL P.R.O.	GROSS TAKE	P.R.O. IN TAKE	NET TAKE	STRUC-TURE	NET RESIDUE		TYPE FUND	REMARKS	AS ACQUIRED	
			BOOK	PAGE								LEFT	RIGHT			BOOK	PAGE
1-P	PROPERTY OWNER 1	THIS SHT.	INSTR.	200309170297908	xxx-xxxxxx	4.317	0.000	0.054		0.054	NO	4.263		CITY	PERMANENT DRAINAGE EASEMENT		
1-T	PROPERTY OWNER 1	THIS SHT.	INSTR.	200309170297908	xxx-xxxxxx	4.317	0.000	0.104		0.104	NO			CITY	FOR REMOVAL AND REPLACEMENT OF CULVERT		
2	PROPERTY OWNER 2	THIS SHT.	INSTR.	200403160057069	xxx-xxxxxx	3.192	0.087				NO			CITY	NO ADDITIONAL RIGHT-OF-WAY REQUIRED		
3-T	PROPERTY OWNER 3	THIS SHT.	INSTR.	200511150241837	xxx-xxxxxx	5.5264	0.000	0.025		0.025	NO			CITY	FOR REMOVAL AND REPLACEMENT OF CULVERT		

NOTES:
RECORD AREA - TOTAL PRO - NET TAKE = NET RESIDUE
GROSS TAKE - PRO IN TAKE = NET TAKE
RECORD AREA ACREAGE IS ASSESSED ACREAGE (OBTAINED FROM FRANKLIN COUNTY AUDITOR'S OFFICE)

NOTE: ALL TEMPORARY PARCELS TO BE OF 12 MONTH DURATION.

REV. BY	DATE	DESCRIPTION
FIELD REVIEW BY:	xx/xx	DATE: 01-05-07
OWNERSHIP VERIFIED BY:	xxx	DATE: 01-05-07
DATE COMPLETED:	APRIL 1, 2007	

XXXX-E

RIGHT OF WAY PLAN
STATION TO STATION

PROJECT NAME

X
XX